

SHERWOOD-LOGAN & ASSOCIATES, INC.

WASH. (301) 970-2181

2140 RENARD COURT
ANNAPOLIS, MARYLAND 21401
FAX: (410) 841-6330

BALT: (410) 841-6810

32384 CHARLES COUNTY POMONKEY PUMP STATION IMPROVEMENTS

UPS PANEL SUBMITTAL

SECTION 17441 - CONTROLS SYSTEM HARDWARE

February 20, 2026

ENGINEER: WRA

CONTRACTOR: JOHNSTON CONSTRUCTION

***MANUFACTURERS' REPRESENTATIVE FOR ENGINEERED INSTRUMENTATION,
PROCESS EQUIPMENT AND PUMPING SYSTEMS***

Branch Offices: RICHMOND, VA and LEOLA, PA

32384 CHARLES COUNTY POMONKEY PUMP STATION IMPROVEMENTS

Table of Contents

Comments

Parts Index

Data Sheets

Drawing Index

Drawings

**32384 CHARLES COUNTY POMONKEY PUMP STATION
IMPROVEMENTS**

General Comments:

Parts Index:

SHT	MANUFACTURER	MODEL	DESCRIPTION
1	SCE	SCE-30H2412SSLP	Wall Mount Enclosure - NEMA 4X
1	SCE	SCE-30P24	Enclosure Backpanel
2	Leviton	5801-W	Single Receptacle, 20A
3	Schneider Electric	RXM3AB2F7	Miniature Relay, 120VAC, 11 Blade
3	Schneider Electric	RXZE2S111M	Miniature Relay Socket, 120VAC, DIN
4	APC	SRT1000XLA	Uninterruptible Power Supply
4	APC	APC9614	Dry Contact I/O Card
4	APC	SRT48BP	UPS External Battery Pack
5	SCE	SCE-TSH50	Enclosure Heater
6	Finder	7T.81.0.000.2403	Enclosure Heater Thermostat, NC
7	Phoenix Contact	3044076	Terminal Block
7	Phoenix Contact	3044092	Grounding Terminal Block
7	Phoenix Contact	3047028	Terminal End Barrier
7	Phoenix Contact	0800886	Terminal Anchor

**32384 CHARLES COUNTY POMONKEY PUMP STATION
IMPROVEMENTS**

Data Sheet 1

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/20/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: SCE: Wall Mount Enclosure - NEMA 4X Model Number: SCE-30H2412SSLP Tags/Service: ENC / UPS Panel Specifications: • 0.075" stainless steel type 304 • Flange trough around all sides of door opening • Oil-resistant door gasket • Hasp and staple for padlocking • Stainless steel continuous hinge • Ground stud on door • NEMA 4X rated
1	Mfg: SCE: Enclosure Backpanel Model Number: SCE-30P24 Tags/Service: ENC / UPS Panel Specifications: • Bent subpanel • 27"H x 21"W x 0.88"D dimensions • Powder coated white finish



Saginaw Control and Engineering
95 Midland Road Saginaw, MI 48638-5770
(800) 234-6871 - Fax: (989) 799-4524
SCE@SaginawControl.com

WALL MOUNT ENCLOSURE - NEMA 4X

SCE-30H2412SSLP

TAGS: ENC

~~SCE-30EL2412SSLP Cost Effective Alternative~~



Product Specifications:

Part Number: SCE-30H2412SSLP
Description: Nema 4X LP Enclosure
Height: 30.00"
Width: 24.00"
Depth: 12.00"
Price Code: S3
List Price: \$1,776.20
Catalog Page: 268
Est. Ship Weight: 69.00 lbs

Construction

- * 0.075 In. stainless steel Type 304.
- * Continuously welded seams ground smooth.
- * Flange trough collar around all sides of door opening.
- * Oil-resistant door gasket.
- * Collar studs provided for mounting optional subpanels.
- * Hasp and staple for padlocking.
- * Stainless steel continuous hinge.
- * Removable print pocket furnished if height and width of enclosure is greater than 12 Inches.
- * Ground stud on door.
- * Stainless steel clamps on three sides door when greater than 30 inch wide.
- * Mounting provision top and bottom of back.

Application

Designed to house electrical and electronic controls, instruments and components in areas which may be regularly hosed down or are very wet conditions. Provides protection from dust, dirt, oil and water. For outdoor application a drip shield is recommended. For outdoor application a drip shield and drain vent is recommended.

For details about the design, performance expectations, applications and design suggestions - See Design Considerations
www.saginawcontrol.com/instman/considerations.pdf

Finish

#4 brushed finish on all exterior surfaces. Optional sub-panels are powder coated white.

Industry Standards - (IS6)

- * NEMA Type 3R, 4, 4X, 12 and Type 13
- * UL Listed Type 3R, 4, 4X and 12
- * CSA Type 4, 4X and 12
- * IEC 60529
- * IP 66

Notes

Provision for Lifting Lugs on enclosures when Height >48" and Depth >16". The Lifting Lug assembly will be included with the enclosure bolt pack.

Optional Accessories

- SCE-30P24 Subpanel, Bent
- SCE-30P24GALV Subpanel, Bent Galvanized
- SCE-BVK Breather Vent
- SCE-DS24SS Shield, S.S. Drip
- SCE-LPCLAMPSS Assembly, S.S. LP Clamp (2pcs)
- SCE-LPQR LP Style Quick Release Clamp Assy (Stainless)
- SCE-NADFKSS Kit, S.S. Swing-Out Panel Mounting
- SCE-RD30H24SS Door, Replacement

Similar Part Numbers

- SCE-20H1606SSLP Nema 4X LP Enclosure
- SCE-20H1608SSLP Nema 4X LP Enclosure
- SCE-20H1610SSLP Nema 4X LP Enclosure
- SCE-20H2006SSLP Nema 4X LP Enclosure
- SCE-20H2408SSLP Nema 4X LP Enclosure
- SCE-24H1608SSLP Nema 4X LP Enclosure
- SCE-24H2006SSLP Nema 4X LP Enclosure
- SCE-24H2008SSLP Nema 4X LP Enclosure
- SCE-24H2010SSLP Nema 4X LP Enclosure
- SCE-24H2406SSLP Nema 4X LP Enclosure

Installation Information

- * Drip Shield Kit Assembly
- * Swing Panel Assembly for LP Enclosures
- * Clamp Fastened Single Door Enclosures (Stainless Steel)
- * NEMA 12 and 4 Clamp Fastened Single Door Enclosure



Your Enclosure Source®

ENCLOSURE BACKPANEL

Saginaw Control and Engineering
95 Midland Road Saginaw, MI 48638-5770
(800) 234-6871 - Fax: (989) 799-4524
SCE@SaginawControl.com

SCE-30P24 TAGS: ENC

Product Specifications:



Part Number: SCE-30P24
Description: Subpanel, Bent
Height: 27.00"
Width: 21.00"
Depth: 0.88"
Price Code: P3
List Price: \$78.18
Catalog Page: 444
Est. Ship Weight: 22.00 lbs

Finish

Powder Coated White.

Industry Standards - (IS17)

- ⚙ NEMA Not Applicable
- ⚙ UL Not Applicable
- ⚙ CSA N/A

Similar Part Numbers

SCE-16P10Subpanel, Flat
SCE-16P14Subpanel, Flat
SCE-16PB12Subpanel, Flat for SCE-20PBH
SCE-18P16PCSubpanel, Flat
SCE-20P12Subpanel, Flat
SCE-20P16Subpanel, Flat
SCE-20P16JSubpanel, Flat Junction
SCE-20P18HMISubpanel, Flat
SCE-20P20Subpanel, Flat
SCE-20P20CSubpanel, Flat

Installation Information

- ⚙ Sub-Plate Layout & Grounding for 10-32

Data Sheet 2

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/20/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Leviton: Single Receptacle, 20A Model Number: 5801-W Tags/Service: RECP3204 / UPS Panel Specifications: • 125VAC rated supply voltage • 20A rated current • 2-pole, 3 wire grounding • White nylon body material • Brass 8-32 grounding screw • Zinc-plated steel strap material • -40...60°C operating temperature

SINGLE RECEPTACLE, 20A

TAGS: RECP3204



5801-W

20 Amp Single Receptacle/Outlet, Commercial Grade

Single Receptacle Outlet, Commercial Specification Grade, Smooth Face, 20 Amp, 125 Volt, Side Wire, NEMA 5-20R, 2-Pole, 3-Wire, Grounding - White

ROHS Compliant : Yes

Leviton's line of Heavy-Duty Specification Grade receptacles are designed and manufactured to withstand the most demanding environments. Available in a wide variety of configurations, including isolated ground, tamper-resistant, etc., these Commercial Grade devices are the electrical contractor's choice for use in hotels, schools, hospitals and commercial office buildings.


Color :  White

UPC Code : 078477249208

Country Of Origin : Mexico

NEMA :  5-20R

Available Colors :



Technical Information

AC Horsepower Ratings

At Rated Voltage : 1 HP

Electrical Specifications

Amperage : 20 A

Current Limiting : Full Rated Current

Dielectric Voltage :
Withstands 2000V per UL498

Grounding : Grounding

Pole : 2

Temperature Rise : Max 30C
after 100 cycles OL at 150
percent rated current

Voltage : 125 VAC

Wire : 3

Environmental Specifications

Flammability : Rated V-2 per
UL 94

Operating Temperature : -40°
C to 60°C

Material Specifications

Body Material : Nylon

Color : White

Face Material : Nylon

Grounding Screw : Brass 8-32

Line Contacts : Brass Double
Wipe .031 Thick

Strap Material : Zinc-Plated
Steel

Terminal Screws : Brass 8-32

Mechanical Specifications

Product ID : Ratings are
permanently marked on device

Product Features

Color : White

Device Type : Single
Receptacle Outlet

Screw Terminal Torque : 14-18 in-lbs

Terminal Accom. : 14-10 AWG

Terminal ID : Brass-Hot, Green-Ground, Silver-Neutral

Termination : Side Wire

Feature : Indented Face

Grade : Commercial Specification Grade

NEMA : 5-20R

Standards and Certifications

ANSI : C-73

CSA C22.2 No. 42 : File 152105

NEMA : WD-2 WD-6


NOM : 057

UL Fed Spec WC-596 : File E13399


UL498 : File E13399

Warranty : 10-Year Limited

Wiring Diagram



Dimensional Drawing



Leviton Manufacturing Co., Inc

201 North Service Road, Melville, NY 11747

Telephone: +1-800-323-8920 · FAX: +1-800-832-9538 · Tech Line (8:30AM-7:30PM E.S.
T. Monday-Friday): +1-800-824-3005

Leviton Manufacturing of Canada, Ltd.

165 Hymus Boulevard, Pointe Claire, Quebec H9R 1E9 · Telephone: +1-800-461-2002 ·
FAX: +1-800-824-3005 ·

Leviton S. de R.L. de C.V.

Lago Tana 43, Mexico DF, Mexico CP 11290 · Tel.: (+52)55-5082-1040 · FAX: (+52)
5386- 1797 ·

Visit our Website at: www.leviton.com

© 2025 Leviton Manufacturing Co., Inc. All Rights Reserved. Subject to change without notice.

Leviton has a global presence.

If you would like to know where your local Leviton office is located please go to:

www.leviton.com/company/about-leviton/locations

© 2025 Leviton Manufacturing Co., Inc.

Data Sheet 3

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/20/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Schneider Electric: Miniature Relay, 120VAC, 11 Blade Model Number: RXM3AB2F7 Tags/Service: CR3213 / UPS Panel Specifications: • 120VAC 50/60Hz control circuit voltage • 6.7A continuous current output • 3 C/O contact composition • With status LED and lockable test button • 10A load current at 250VAC • 1.2VA average power consumption • 100000 cycle electrical durability
1	Mfg: Schneider Electric: Miniature Relay Socket, 120VAC, DIN Model Number: RXZE2S111M Tags/Service: CR3213 / UPS Panel Specifications: • <300 VAC UL rated operational voltage • 10A conventional free air thermal current • 3 C/O contact composition



miniature plug in relay, Harmony Electromechanical Relays, 10A, 3CO, with LED, lockable test but to n, 120V AC

RXM3AB2F7

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Harmony Electromechanical Relays
Series name	RXM series
Product or Component Type	Plug-in relay
Relay Type	Miniature relay
Contacts type and composition	3 C/O
Status LED	With
Control Type	Lockable test button
[Uc] control circuit voltage	120 V AC 50/60 Hz
[Ithe] conventional enclosed thermal current	10 A
Continuous output current	6.7 A

Complementary

[Uimp] rated impulse withstand voltage	4 kV 1.2/50 µs
[Ie] rated operational current	10 A 28 V DC) NO-IEC 10 A 250 V AC) NO-IEC 5 A 28 V DC) NC-IEC 5 A 250 V AC) NC-IEC 10 A 30 V DC) UL 10 A 277 V AC) UL
Minimum switching capacity	170 mW 10 mA, 17 V
Electrical durability	100000 cycles resistive
Average coil consumption in VA	1.2 60 Hz
Rated operational voltage limits	96...132 V AC
[Ui] rated insulation voltage	250 V IEC 300 V CSA 300 V UL
Average consumption	1.2 VA 60 Hz
Maximum switching voltage	250 V IEC
Drop-out voltage threshold	>= 0.15 Uc
Load current	10 A 250 V AC 10 A 28 V DC
Operating time	20 ms
Maximum switching capacity	2500 VA/280 W
Average resistance	4430 Ohm 20 °C +/- 15 %

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Mechanical durability	10000000 cycles
Safety reliability data	B10d = 100000
Operating rate	<= 1200 cycles/hour under load <= 18000 cycles/hour no-load
Utilisation coefficient	20 %
CAD overall height	3.1 in (79 mm)
CAD overall depth	3.09 in (78.45 mm)
reset time	20 ms
Dielectric strength	1300 V AC between contacts with micro disconnection 2000 V AC between coil and contact 2000 V AC between poles
Compatibility code	RXM
Protection category	RT I
Pollution degree	2
Operating position	Any position
Test levels	Level A group mounting
Device presentation	Complete product
Contacts material	AgNi
Shape of pin	Flat (faston type)
Net Weight	0.082 lb(US) (0.037 kg)

Environment

Ambient air temperature for operation	-40...131 °F (-40...55 °C)
IP degree of protection	IP40 conforming to IEC 60529
Standards	UL 508 IEC 61810-1 CSA C22.2 No 14
Product Certifications	UL Lloyd's CE CSA EAC IECEE CB Scheme
Ambient Air Temperature for Storage	-40...185 °F (-40...85 °C)
Vibration resistance	3 gn +/- 1 mm 10...150 Hz)5 cycles in operation 5 gn +/- 1 mm 10...150 Hz)5 cycles not operating
Shock resistance	10 gnin operation 30 gnnot operating

Ordering and shipping details

Category	US10CP221127
Discount Schedule	0CP2
GTIN	3389119403665
Returnability	Yes
Country of origin	CN

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	0.984 in (2.500 cm)
Package 1 Width	1.181 in (3.000 cm)
Package 1 Length	1.772 in (4.500 cm)
Package weight(Lbs)	1.305 oz (37.000 g)
Unit Type of Package 2	BB1
Number of Units in Package 2	10
Package 2 Height	1.181 in (3.000 cm)
Package 2 Width	4.134 in (10.500 cm)
Package 2 Length	4.921 in (12.500 cm)
Package 2 Weight	13.968 oz (396.000 g)
Unit Type of Package 3	S02
Number of Units in Package 3	240
Package 3 Height	5.906 in (15.000 cm)
Package 3 Width	11.811 in (30.000 cm)
Package 3 Length	15.748 in (40.000 cm)
Package 3 Weight	21.497 lb(US) (9.751 kg)

Contractual warranty

Warranty (in months)	18
----------------------	----

Product data sheet

MINIATURE RELAY SOCKET, 120VAC, DIN

Specifications

TAGS: CR3213



socket, Harmony Electromechanical Relays, for RXM3 relays, screw connec to rs, separate contact

RXZE2S111M

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Harmony Electromechanical Relays
Product compatibility	Plug-in relay RXM 3 C/O
Device short name	RXZ
[Ith] conventional free air thermal current	10 A
Product or Component Type	Socket
Contacts type and composition	3 C/O

Complementary

[Ue] rated operational voltage	< 250 V IEC < 300 V UL
Connections - terminals	Screw connectors, 1 x 0.34...1 x 2.5 mm² AWG 22...AWG 14) flexible with cable end Screw connectors, 2 x 0.34...2 x 1 mm² AWG 22...AWG 17) flexible with cable end Screw connectors, 1 x 0.5...1 x 2.5 mm² AWG 20...AWG 14) solid without cable end Screw connectors, 2 x 0.5...2 x 1.5 mm² AWG 20...AWG 16) solid without cable end
Shape of pin	Flat
Tightening torque	< 1 N.m M3
Fixing mode	By screw (panel) Clip-on (35 mm symmetrical DIN rail)
Wire stripping length	0.3 in (8 mm)
Contact terminal arrangement	Separate
[Uimp] rated impulse withstand voltage	4 kV
Overvoltage category	III
Pollution degree	3
Sale per indivisible quantity	10
Width	1.06 in (27 mm)
Net Weight	0.128 lb(US) (0.058 kg)

Environment

IP degree of protection	IP20 conforming to IEC 60529
Dielectric strength	2500 V
Standards	IEC 61984
Product Certifications	UL Lloyd's CSA
Marking	CE

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Ambient Air Temperature for Storage	-40...185 °F (-40...85 °C)
Ambient Air Temperature for Operation	-40...131 °F (-40...55 °C)

Ordering and shipping details

Category	US10CP221128
Discount Schedule	0CP2
GTIN	3389119404273
Returnability	Yes
Country of origin	CN

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	2.402 in (6.100 cm)
Package 1 Width	1.063 in (2.700 cm)
Package 1 Length	2.953 in (7.500 cm)
Package weight(Lbs)	2.116 oz (60.000 g)
Unit Type of Package 2	BB1
Number of Units in Package 2	10
Package 2 Height	2.598 in (6.600 cm)
Package 2 Width	5.354 in (13.600 cm)
Package 2 Length	4.331 in (11.000 cm)
Package 2 Weight	22.787 oz (646.000 g)
Unit Type of Package 3	S03
Number of Units in Package 3	200
Package 3 Height	11.811 in (30.000 cm)
Package 3 Width	11.811 in (30.000 cm)
Package 3 Length	15.748 in (40.000 cm)
Package 3 Weight	29.568 lb(US) (13.412 kg)

Contractual warranty

Warranty (in months)	18
----------------------	----

Data Sheet 4

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/20/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: APC: Uninterruptible Power Supply Model Number: SRT1000XLA Tags/Service: UPS / UPS Panel Specifications: • 120VAC single phase main input voltage • NEMA 5-15P receptacle input connection type • 40-70Hz auto-sensing input frequency • 120VAC single phase main output voltage • 1000VA rated power • 6 NEMA 5-15R receptacle outputs • Built-in bypass • On-line UPS, sine wave waveform type
1	Mfg: APC: Dry Contact I/O Card Model Number: APC9614 Tags/Service: UPS / UPS Panel Specifications: • 24VDC rated voltage • Self powered via UPS SmartSlot • 0...200mA line rated current • 0.522ft cable length

1	Mfg: APC: UPS External Battery Pack Model Number: SRT48BP Tags/Service: BP / UPS Panel Specifications: • External lead-acid battery pack • 2U rack unit size • Stand alone battery stack • 48VDC battery voltage • 2 replacement battery cartridges
---	--



TAGS: UPS

APC Smart-UPS On-Line,
1000VA, Tower, 120V, 6x 5-15R
NEMA outlets, SmartSlot,
Extended runtime, W/O rail kit

SRT1000XLA

Overview

Presentation	High density, double-conversion on-line power protection with scalable runtime.
Lead time	Usually in Stock

Main

Main Input Voltage	120 V AC 1 phase
Input Connection Type	NEMA 5-15P
Efficiency at full load	50...150 V 40% load 80...150 V
Input Frequency	40 - 70 Hz auto-sensing
Output voltage	120 V 1 phase
Rated power in W	900 W
rated power in VA	1000 VA
output connection type	6 NEMA 5-15R
Bypass type	Built-in Bypass
Crest factor	3 : 1
Harmonic distortion	Less than 2%
Maximum configurable power in VA	1000 VA
Max Configurable Power (Watts)	900 W
Topology	On-Line
Waveform Type	Sine wave
Output Frequency (sync to mains)	50/60 Hz +/- 3 Hz sync to mains

Complementary

Battery Size	Lead-acid internal included
Emergency Power Off (EPO)	Yes
Free slots	1
Alarm	Audible and visible alarms : prioritized by severity
UPS connectivity	Serial port USB port
Surge energy rating	432 J
Cable length	5.9 ft (1.8 m)
Number of cables	1
color	Black

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Height	17.008 in (432 mm)
Width	3.3 in (85 mm)
Depth	20 in (508 mm)
Net Weight	48.5 lb(US) (22 kg)
Mounting preference	No preference
Mounting Mode	Tower
Two post mountable	0
USB compatible	Yes
Mounting position	Vertical
Mounting mode	Tower
Provided equipment	CD with software Communication Cable Documentation CD Installation guide Removable support feet USB cable Warranty card
Number of power module filled slots	0
Number of power module free slots	0
Additional specification	High density
Redundant	No
Range of Product	Smart-UPS On-Line
Product or Component Type	Uninterruptible power supply (UPS)

Environment

Product Certifications	ENERGY STAR V2.0 (USA)
Ambient Air Temperature for Operation	32...104 °F (0...40 °C)
Ambient Air Temperature for Storage	-4...122 °F (-20...50 °C)
Storage altitude	0...50000 ft (0...15240 m)
IP degree of protection	IP20
Relative Humidity	0...95 % non-condensing
Storage Relative Humidity	0...95 % non-condensing
Acoustic level	50 dBA
Heat dissipation	317 Btu/h
Operating altitude	0...10000 ft

Batteries & Runtime

Run Time	View Runtime Graph 
Efficiency	View Efficiency Graph 
Battery Type	Lead-Acid battery
Battery Voltage	48V
Extendable Run Time	1
Included Battery Modules	0

Battery Slots Empty	0
Typical recharge time	3 h
RBC Quantity	1
Battery Life	3...5 year(s)
Replacement battery	APCRBC155 
Battery Charge Power (Watts)	102 W rated

Ordering and shipping details

GTIN	731304329985
------	--------------

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	9.6 in (24.5 cm)
Package 1 Width	27.2 in (69.0 cm)
Package 1 Length	23.4 in (59.5 cm)
Package weight(Lbs)	71.83 lb(US) (32.58 kg)

Contractual warranty

Warranty (in months)	24 Battery 36 UPS
----------------------	-------------------

TAGS: UPS



Dry contact, Management Options, Dry Contact I/O Card, monitor external UPS environmental sensors, output relays, and input contacts

AP9614

Product availability: Non-Stock - Not normally stocked in distribution facility

Overview

Lead time	Usually in Stock
-----------	------------------

Main

Range of Product	Management Options and Cables
Provided Equipment	User Manual USB cable
Product or Component Type	Dry contact
Number of rack unit	0U
Cable length	0.522 ft (0.159 m)
Rated voltage	24 V
Line Rated Current	0...200 mA

General

Power supply type	Self powered via SmartSlot
-------------------	----------------------------

Physical

Height	1.5 in (3.8 cm)
Width	4.8 in (12.1 cm)
Depth	5.04 in (12.8 cm)
Net Weight	0.44 lb(US) (0.20 kg)
Mounting Mode	Not rack-mountable

Conformance

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Standards	EN 55022 Class A EN 55024 EN 61000-3-2 EN 61000-3-3 EN 61000-4-2 EN 61000-4-3 EN 61000-4-4 EN 61000-4-6 FCC Part 15 class A FCC CFR 47 part 15 EN 61000-6-3 (2007) BS EN 61000-6-3 EN 55032 BS EN 55032 VCCI class A CISPR 32 EN/IEC 61000-3-2 AS/NZS CISPR 32 EN 61000-6-1 (2007) EN 55035 BS EN 55024 IEC 62040-2 BS EN 62040-2 EN 61326-2 BS EN 61326-2 BS EN 61000-4-2 BS EN 61000-4-3 BS EN 61000-4-4 EN 61000-4-5 BS EN 61000-4-5 BS EN 61000-4-6 EN 61000-4-8 BS EN 61000-4-8 EN 61000-4-11 BS EN 61000-4-11 BS EN 55035 EN 62040-2 ICES-003 class A EN 61000-6-3 BS EN 61000-3-2 BS EN 61000-3-3 AS/NZS EN 61000-3-2:2023 AS/NZS EN 61000-3-3:2023
-----------	--

Environmental

Ambient Air Temperature for Operation	32...104 °F (0...40 °C)
Operating altitude	0...10000 ft 0...50000 ft
Ambient Air Temperature for Storage	5...149 °F (-15...65 °C)
Storage altitude	0...50000 ft (0...15240 m)

Ordering and shipping details

GTIN	731304733065
------	--------------

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	2.008 in (5.1 cm)
Package 1 Width	6.5 in (16.5 cm)
Package 1 Length	9.4 in (23.8 cm)
Package weight(Lbs)	15.5 oz (440 g)

Product data sheet

Specifications



APC Smart-UPS SRT 48V 1kVA 1.5kVA Battery Pack

SRT48BP

Overview

Lead time	Usually in Stock
-----------	------------------

Main

Product or Component Type	External battery pack
Number of rack unit	2U
Battery Type	Lead-Acid battery
Provided Equipment	Documentation CD Installation guide
Range of Product	Smart-UPS Battery Systems

Batteries & Runtime

Battery Slots Empty	0
Included Battery Modules	0
Device mounting	Stand alone battery stack
Battery Voltage	48V
RBC Quantity	2
Replacement battery	APCRBC155

Physical

Color	Black
Height	17.008 in (432 mm)
Width	3.3 in (85 mm)
Depth	21.1 in (536 mm)
Net Weight	65.9 lb(US) (29.9 kg)
Mounting Mode	Rack-mounted with kit

Output

Battery Capacity	11 Ah
------------------	-------

Environmental

Ambient Air Temperature for Operation	32...104 °F (0...40 °C)
Operating altitude	0...10000 ft
Relative Humidity	0...95 % non-condensing

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Ambient Air Temperature for Storage	5...113 °F (-15...45 °C)
Storage altitude	0...50000 ft (0...15240 m)
Storage Relative Humidity	0...95 % non-condensing

Ordering and shipping details

GTIN	731304330141
------	--------------

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	9.646 in (24.500 cm)
Package 1 Width	29.134 in (74.000 cm)
Package 1 Length	23.425 in (59.500 cm)
Package weight(Lbs)	83.335 lb(US) (37.800 kg)
Unit Type of Package 2	P06
Number of Units in Package 2	2
Package 2 Height	25.591 in (65.000 cm)
Package 2 Width	23.622 in (60.000 cm)
Package 2 Length	31.496 in (80.000 cm)
Package 2 Weight	179.897 lb(US) (81.600 kg)

Contractual warranty

Warranty (in months)	24
----------------------	----

Data Sheet 5

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/20/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: SCE: Enclosure Heater Model Number: SCE-TSH50 Tags/Service: HTR3203 / UPS Panel Specifications: • For protection from condensation • Positive temperature coefficient application • 35mm DIN rail clip for mounting • Touch safe heater, with 2 screw terminals for standard AWG 14 wire



ENCLOSURE HEATER

TAGS: HTR3203

Saginaw Control and Engineering
 95 Midland Road Saginaw, MI 48638-5770
 (800) 234-6871 - Fax: (989) 799-4524
 SCE@SaginawControl.com

SCE-TSH50

Product Specifications:



Part Number: SCE-TSH50
Description: Heater - 50W
Height: 4.92"
Width: 1.61"
Depth: 1.61"
Price Code: P1
List Price: \$142.60
Catalog Page: 402
Est. Ship Weight: 0.35 lbs
Max. Current : 3.5
Model Number: 501050

Application

PTC (Positive Temperature Coefficient)
 Din rail clip design for 35mm Din Rail. Designed for protection from low temperatures, condensation and corrosion. Touch Safe with 2 screw terminal for standard AWG 14 wire. 110-240V AC.

For low temperatures management use with thermostat

For condensate management no thermostat is necessary - continuous heat is most effective see installaton Instruction for sizing.

Industry Standards - (IS24)

✱ UL Component Recognized

Notes

UL File #E358386

Optional Accessories

~~SCE-TEMD Thermostat (Dual)~~
~~SCE-TEMNC Thermostat (Normally Closed)~~

Similar Part Numbers

~~SCE-TSH100Heater - 100W~~
~~SCE-TSH150Heater - 150W~~
~~SCE-TSH25Heater - 25W~~
~~SCE-TSH75Heater - 75W~~

Installation Information

~~✱ Touch Safe Heaters~~

Data Sheet 6

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/20/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Finder: Enclosure Heater Thermostat, NC Model Number: 7T.81.0.000.2403 Tags/Service: THERMOSTAT / UPS Panel Specifications: • 1 NC SPST contact configuration • 10A rated current, 20A maximum peak current • 0.3A breaking capacity at 110VAC • Silver Nickel standard contact material • 0...60°C setting range • 7±4K switch differential • 100 * 10¹³ cycle electrical life at 2500VA load • IP20 protection category • -45...80°C ambient temperature range



TAGS: THERMOSTAT

Panel Thermo-Hygrostat and Thermostats

7T
SERIES



Drying kilns



Industrial refrigeration



Road / tunnel lighting



Industrial furnaces and ovens



Automatic car-washes



Panels for electrical distribution



Control panels



Forced-air ventilators



Panel Thermo-Hygrostat

- Small, compact size (17.5 mm wide)
- Electronic control
- 4 functions
- Nominal voltage 110...240 V AC/DC
- Temperature ranges from +10 ° to +60°C
- Humidity range up to 90%
- LED status indication contact ON
- 35 mm rail (EN 60715) mount

Panel thermostat

- Small, compact size (17.5 mm wide)
- Snap action thermostatic Bimetal sensor
- Wide temperature setting range
- Long electrical life
- 35 mm rail (EN 60715) mount

7T.51/7T.81
Box clamp



* Measured with 0.3 K/min
** Measured with 0.5 %/min

For outline drawing see page 6

Contact specification

Contact configuration	1 NO (SPST-NO)	1 NC (SPST-NC)	1 NO (SPST-NO)
Rated current/Maximum peak current	A	10/15	10/20
Rated voltage/ Maximum switching voltage	V AC	250/400	250/250
Rated load AC1	VA	2500	2500
Rated load AC15 (230 V AC)	VA	500	250
Single phase motor rating AC3 (230 V AC)	kW	—	1.1
Breaking capacity DC1: 24/110/220 V	A	10/0.3/0.12	1/0.3/0.15
Minimum switching load	mW (V/mA)	500 (12/10)	500 (12/10)
Standard contact material	AgNi	AgNi	AgNi

Coil specifications

Nominal Voltage	V AC/DC	110...240	—	—
Rated Power	VA (50Hz)/W	1.8/0.44	—	—
Operating range	V AC/DC	88...264	—	—

Temperature specifications *

Setting range (ventilation)	°C	+10...+60	-20...+40 -20...+60 0...+60	-20...+40 -20...+60 0...+60
Switch differential	K	4 ± 2	7 ± 4	7 ± 4
Setting accuracy full range	K	-1...+3	—	—

Humidity specifications **

Setting range (humidity)	%	50...90	—	—
Hysteresis	%	4 ± 2	—	—
Setting accuracy	%	5	—	—

Technical data

Electrical life at rated load AC1	cycles	100 · 10 ³	100 · 10 ³	100 · 10 ³
Ambient temperature range	°C	-25...+60	-45...+80	-45...+80
Protection category		IP 20	IP 20	IP 20

Approvals (according to type)

NEW 7T.51



- Thermo-Hygrostatic control
- Nominal voltage 110...240 V AC/DC

7T.81.0.000.240x



- Heating control


7T.81.0.000.230x



- Ventilation control

Ordering information


Example: 7T Series, Thermo-Hygrostat for temperature and humidity control, 110...240 V AC/DC, Multifunction, 35 mm rail (EN 60715) mount.



Technical data

Insulation		7T.51	7T.81
Dielectric strength between open contacts	V AC	1000	500
Dielectric strength between supply and contact	V AC	2000	—
Other data		7T.51	7T.81
Vibration resistance	g	—	16
Shock resistance	g	—	20
		7T.51/7T.81	
Screw torque	Nm	0.5	0.5
Max. wire size		solid cable	stranded cable
	mm ²	1 x 4 / 2 x 2.5	1 x 4 / 2 x 2.5
	AWG	1 x 12 / 2 x 14	1 x 12 / 2 x 14
Wire strip length	mm	9	9


Functions 7T.51



HT: RH > RHset or Tamb > Tset

Power is permanently applied to the thermo-hygrostat.
The contact 13-14 closes if the ambient humidity (RH) is > of set humidity (RHset) or if the ambient temperature (Tamb) is > of set temperature (Tset).


When contact is close, LED is ON



TH: RH > RHset or Tamb < Tset

The contact 13-14 closes if the ambient humidity (RH) is > of set humidity (RHset) or if the ambient temperature (Tamb) is < of set temperature (Tset).


When contact is close, LED is ON



HL: RH < RHset

The contact 13-14 closes if the ambient humidity (RH) is < of set humidity (RHset)

When contact is close, LED is ON







HM: RH > RHset

The contact 13-14 closes if the ambient humidity (RH) is > of set humidity (RHset)

When contact is close, LED is ON

G


Functions 7T.81



Heating control - Should the panel temperature fall below the (minimum) set temperature the contact will close to call for heat.
The contact will open when this set temperature is exceeded.


Ventilation control - Should the panel temperature exceed the (maximum) set temperature then the contact will close to call for cooling.
The contact will open when the temperature falls below this set temperature.

Wiring diagrams




Outline drawings

Type 7T.51
Box clamp



Type 7T.81
Box clamp



Data Sheet 7

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/20/2026
<u>Qty</u>	<u>Description</u>
A/R	Mfg: Phoenix Contact: Terminal Block Model Number: 3044076
A/R	Mfg: Phoenix Contact: Grounding Terminal Block Model Number: 3044092
A/R	Mfg: Phoenix Contact: Terminal End Barrier Model Number: 3047028
A/R	Mfg: Phoenix Contact: Terminal Anchor Model Number: 0800886 Tags / Service: TB-AC / UPS Panel Specifications: • Feed through and grounding terminals • Screw clamps • End plates and anchors • DIN rail mount

UT 2,5

Order No.: 3044076

<http://eshop.phoenixcontact.de/phoenix/treeViewClick.do?UID=3044076>

Universal terminal block, Type of connection: Screw connection,
Screw connection, Cross section: 0.14 mm² - 4 mm², AWG 26 - 12,
Width: 5.2 mm, Color: gray, Mounting type: NS 35/7,5, NS 35/15

**Commercial data**

EAN	4017918960377
Pack	50 pcs.
Customs tariff	85369010
Weight/Piece	0.008227 KG
Catalog page information	Page 26 (CL-2009)

Product notes

WEEE/RoHS-compliant since:
01/01/2003



[http://
www.download.phoenixcontact.com](http://www.download.phoenixcontact.com)
Please note that the data given
here has been taken from the
online catalog. For comprehensive
information and data, please refer
to the user documentation. The
General Terms and Conditions of
Use apply to Internet downloads.

Technical data**General**

Number of levels	1
Number of connections	2
Color	gray

Insulating material	PA
Inflammability class acc. to UL 94	V0

Dimensions

Width	5.2 mm
Length	47.7 mm
Height NS 35/7,5	47.5 mm
Height NS 35/15	55 mm

Technical data

Maximum load current	32 A (with 4 mm ² conductor cross section)
Rated surge voltage	8 kV
Pollution degree	3
Surge voltage category	III
Insulating material group	I
Connection in acc. with standard	IEC 60947-7-1
Nominal current I _N	24 A
Nominal voltage U _N	1000 V
Open side panel	ja

Connection data

Conductor cross section solid min.	0.14 mm ²
Conductor cross section solid max.	4 mm ²
Conductor cross section stranded min.	0.14 mm ²
Conductor cross section stranded max.	4 mm ²
Conductor cross section AWG/kcmil min.	26
Conductor cross section AWG/kcmil max	12
Conductor cross section stranded, with ferrule without plastic sleeve min.	0.14 mm ²
Conductor cross section stranded, with ferrule without plastic sleeve max.	2.5 mm ²
Conductor cross section stranded, with ferrule with plastic sleeve min.	0.14 mm ²
Conductor cross section stranded, with ferrule with plastic sleeve max.	2.5 mm ²
2 conductors with same cross section, solid min.	0.14 mm ²
2 conductors with same cross section, solid max.	1.5 mm ²
2 conductors with same cross section, stranded min.	0.14 mm ²

2 conductors with same cross section, stranded max.	1.5 mm ²
2 conductors with same cross section, stranded, TWIN ferrules with plastic sleeve, min.	0.5 mm ²
2 conductors with same cross section, stranded, TWIN ferrules with plastic sleeve, max.	1.5 mm ²
2 conductors with same cross section, stranded, ferrules without plastic sleeve, min.	0.14 mm ²
2 conductors with same cross section, stranded, ferrules without plastic sleeve, max.	1.5 mm ²
Type of connection	Screw connection
Stripping length	9 mm
Internal cylindrical gage	A3
Screw thread	M3
Tightening torque, min	0.6 Nm
Tightening torque max	0.8 Nm

Certificates / Approvals



Certification

CB, CSA, CUL, DNV, GL, GOST, LR, UL, VDE-PZI

Certification Ex:

IECEX, KEMA-EX

CSA

Nominal voltage U_N	600 V
Nominal current I_N	20 A
AWG/kcmil	26-12

CUL


Nominal voltage U_N	600 V
Nominal current I_N	20 A
AWG/kcmil	26-12

UL

Nominal voltage U_N	600 V
Nominal current I_N	20 A
AWG/kcmil	26-12

UT 2,5-PE

Order No.: 3044092

<http://eshop.phoenixcontact.de/phoenix/treeViewClick.do?UID=3044092>

Feed-through modular terminal block, Type of connection: Screw connection, Screw connection, Cross section: 0.14 mm² - 4 mm², AWG 26 - 12, Width: 5.2 mm, Color: green-yellow, Mounting type: NS 35/7,5, NS 35/15



Commercial data

EAN	4017918960360
Pack	50 pcs.
Customs tariff	85369010
Weight/Piece	0.012156 KG
Catalog page information	Page 32 (CL-2009)

Product notes

WEEE/RoHS-compliant since:
01/01/2003



<http://www.download.phoenixcontact.com>
Please note that the data given here has been taken from the online catalog. For comprehensive information and data, please refer to the user documentation. The General Terms and Conditions of Use apply to Internet downloads.

Technical data

General

Number of levels	1
Number of connections	2
Color	green-yellow

Insulating material	PA
Inflammability class acc. to UL 94	V0

Dimensions

Width	5.2 mm
Length	47.7 mm
Height NS 35/7,5	47.5 mm
Height NS 35/15	55 mm

Technical data

Rated surge voltage	8 kV
Pollution degree	3
Surge voltage category	III
Insulating material group	I
Connection in acc. with standard	IEC 60947-7-2
Open side panel	ja

Connection data

Conductor cross section solid min.	0.14 mm ²
Conductor cross section solid max.	4 mm ²
Conductor cross section stranded min.	0.14 mm ²
Conductor cross section stranded max.	4 mm ²
Conductor cross section AWG/kcmil min.	26
Conductor cross section AWG/kcmil max	12
Conductor cross section stranded, with ferrule without plastic sleeve min.	0.14 mm ²
Conductor cross section stranded, with ferrule without plastic sleeve max.	2.5 mm ²
Conductor cross section stranded, with ferrule with plastic sleeve min.	0.14 mm ²
Conductor cross section stranded, with ferrule with plastic sleeve max.	2.5 mm ²
2 conductors with same cross section, solid min.	0.14 mm ²
2 conductors with same cross section, solid max.	1.5 mm ²
2 conductors with same cross section, stranded min.	0.14 mm ²
2 conductors with same cross section, stranded max.	1.5 mm ²

2 conductors with same cross section, stranded, TWIN ferrules with plastic sleeve, min.	0.5 mm ²
2 conductors with same cross section, stranded, TWIN ferrules with plastic sleeve, max.	1.5 mm ²
2 conductors with same cross section, stranded, ferrules without plastic sleeve, min.	0.14 mm ²
2 conductors with same cross section, stranded, ferrules without plastic sleeve, max.	1.5 mm ²
Type of connection	Screw connection
Stripping length	9 mm
Internal cylindrical gage	A3
Screw thread	M3
Tightening torque, min	0.6 Nm
Tightening torque max	0.8 Nm

Certificates / Approvals



Certification CB, CSA, CUL, DNV, GL, LR, UL, VDE-PZI

Certification Ex: IECEX, KEMA-EX

CSA

AWG/kcmil	26-12
-----------	-------

CUL

AWG/kcmil	26-12
-----------	-------

UL

AWG/kcmil	26-12
-----------	-------

D-UT 2,5/10

Order No.: 3047028



<http://eshop.phoenixcontact.de/phoenix/treeViewClick.do?UID=3047028>

End cover, Length: 47.7 mm, Width: 2.2 mm, Height: 48.4 mm,
Color: gray

Commercial data

EAN	4017918960346
Pack	50 pcs.
Customs tariff	85389099
Weight/Piece	0.00248 KG
Catalog page information	Page 26 (CL-2009)

Product notes

WEEE/RoHS-compliant since:
01/01/2003



<http://www.download.phoenixcontact.com>
Please note that the data given here has been taken from the online catalog. For comprehensive information and data, please refer to the user documentation. The General Terms and Conditions of Use apply to Internet downloads.

E/NS 35 N - End bracket


0800886

<https://www.phoenixcontact.com/us/products/0800886>



Please be informed that the data shown in this PDF document is generated from our online catalog. Please find the complete data in the user documentation. Our general terms of use for downloads are valid.

End clamp, width: 9.5 mm, color: gray



Your advantages

- Large-surface marking

Commercial data


Item number	0800886
Packing unit	50 pc
Minimum order quantity	50 pc
Sales key	BE07
Product key	BE7111
GTIN	4017918129309
Weight per piece (including packing)	14.16 g
Weight per piece (excluding packing)	13.708 g
Customs tariff number	39269097
Country of origin	DE

Technical data

Connection data

Screw thread	M3
Tightening torque	0.5 ... 0.8 Nm

Dimensions

Dimensional drawing	
Width	9.5 mm
Height	48.6 mm
Depth	32.8 mm
Depth on NS 35/7,5	34.3 mm
Length	48.6 mm

Material specifications

Color	gray (RAL 7042)
Material	PA
Flammability rating according to UL 94	V0
Static insulating material application in cold	-60 °C
Temperature index of insulation material (DIN EN 60216-1 (VDE 0304-21))	125 °C
Relative insulation material temperature index (Elec., UL 746 B)	130 °C

Environmental and real-life conditions

Ambient conditions

Ambient temperature (operation)	-60 °C ... 105 °C (max. short-term operating temperature RTI Elec.)
Ambient temperature (storage/transport)	-25 °C ... 60 °C (for a short time, not exceeding 24 h, -60 °C to +70 °C)
Ambient temperature (assembly)	-5 °C ... 70 °C
Ambient temperature (actuation)	-5 °C ... 70 °C
Permissible humidity (storage/transport)	30 % ... 70 %

Mounting

Mounting type	NS 35/7,5
	NS 35/15

E/NS 35 N - End bracket

0800886

<https://www.phoenixcontact.com/us/products/0800886>



Phoenix Contact 2026 © - all rights reserved
<https://www.phoenixcontact.com>

Phoenix Contact USA
586 Fulling Mill Road
Middletown, PA 17057, United States
(+717) 944-1300
info@phoenixcon.com

**32384 CHARLES COUNTY POMONKEY PUMP STATION
IMPROVEMENTS**

Drawings Index:

Drawing Number	Drawing Description
D32384-30	POMONKEY PUMP STATION UPS PANEL ENCLOSURE EXT. LAYOUT
D32384-31	POMONKEY PUMP STATION UPS PANEL ENCLOSURE INT. LAYOUT
D32384-32	POMONKEY PUMP STATION UPS PANEL UPS WIRING DIAGRAM

**32384 CHARLES COUNTY POMONKEY PUMP STATION
IMPROVEMENTS**

Drawings:

WARNING NAMEPLATE DETAIL

S-L CONTROLS, DWG D32384-30
VOLTAGE: 120VAC, 60HZ, SINGLE PHASE
AMPS: 28.75

SHORT CIRCUIT CURRENT: N/A

ENCLOSURE RATING: UL TYPE 4X

CAUTION: MULTIPLE POWER SOURCES ARE PROVIDED FROM FIELD
TERMINALS. EACH SOURCE SHOULD BE DISCONNECTED FOR
SERVICING.

WARNING: TO MAINTAIN OVERCURRENT, SHORT CIRCUIT, AND
GROUND FAULT PROTECTION, THE MANUFACTURER'S INSTRUCTIONS
FOR SELECTING CURRENT ELEMENTS MUST BE FOLLOWED

NAMEPLATES SIZED AS REQUIRED



NAME PLATE LEGEND TABLE

ITEM	QTY	DESCRIPTION
1	1	UPS CONTROL PANEL

NOTES:
ALL PLATES SHALL BE ENGRAVED ON WHITE BACKGROUND WITH
BLACK CHARACTERS. LETTER HEIGHT SHOULD BE MINIMUM 1/4"

WIRING:


- 1) □ - INDICATES CABINET TERMINAL BLOCK
- 2) DASHED LINES INDICATE WIRING REMOTE TO CONTROL PANEL.
- 3) PROVIDE 20% SPARE TERMINALS
- 4) UL APPROVED NO. TO BE PROVIDED AT TIME OF MANUFACTURING
- 5) ELECTRICAL CONNECTION TORQUES:
TERMINAL: 12 INCH POUNDS
CIRCUIT BREAKER: 20 INCH POUNDS



PANEL WIRING


AREA	VOLTAGE	NOUN NAME	ID	GAGE	COLOR	TYPE
INTERNAL	120VAC	HOT	(1), (1A), (X1)	14	BLACK	MTW
INTERNAL	120VAC	NEUTRAL	(N)	14	WHITE	MTW
CONTROL	120VAC	HOT	VARIOUS	16	RED	MTW
CONTROL	120VAC	NEUTRAL	N	16	WHITE	MTW
CONTROL	24VDC	DC+	VARIOUS	16	BLUE	MTW
CONTROL	24VDC	DC-	VARIOUS	16	WHT/BLU	MTW

TOLERANCES	REVISIONS			POMONKEY PUMP STATION UPS PANEL EXT. ENCLOSURE LAYOUT		
	NO.	DATE	BY	S-L CONTROLS		
DECIMAL	1					
	2					
FRACTIONAL	3			DRAWN BY ZBB		
	4					
ANGULAR	5			DATE 12-31-2025		
	6					
TRACED				SCALE NONE	MATERIAL	D32384-30
				CHK'D MN	DRAWING NUMBER	
				APP'D		



TAGS	QTY	CATALOG	DESCRIPTION	MANUFACTURER
ENC	1	SCE-30H2412SSLP	WALL MOUNT ENCLOSURE – NEMA 4X	SCE
ENC	1	SCE-30P24	ENCLOSURE BACKPANEL	SCE
CB3203	1	7940102572	CIRCUIT BREAKER, 120VAC, 2A	WEIDMULLER
CB3203A	1	7940102584	CIRCUIT BREAKER, 120VAC, 20A	WEIDMULLER
CB3204	1	7940102582	CIRCUIT BREAKER, 120VAC, 15A	WEIDMULLER
CB3211	1	7940102580	CIRCUIT BREAKER, 120VAC, 10A	WEIDMULLER
RECP3204	1	5801-W	SINGLE RECEPTACLE, 20A	LEVITON
CR3213	1	RXM3AB2F7	MINIATURE RELAY, 120VAC, 11 BLADE	SCHNEIDER ELECTRIC
CR3213	1	RXZE2S111M	MINIATURE RELAY SOCKET, 120VAC, DIN	SCHNEIDER ELECTRIC
UPS	1	SRT1000XLA	UNINTERRUPTIBLE POWER SUPPLY	APC
UPS	1	AP9614	DRY CONTACT I/O CARD	APC
BP	1	SRT48BP	UPS EXTERNAL BATTERY PACK	APC
HTR3203	1	SCE-TSH50	ENCLOSURE HEATER	SCE
THERMOSTAT	1	7T.81.0.000.2403	ENCLOSURE HEATER THERMOSTAT, NC	FINDER
TB-AC, TB-UPS	10	3044076	UNIVERSAL TERMINAL BLOCK – UT 2,5	PHOENIX CONTACT
TB-AC, TB-UPS	A/R	3047028	TERMINAL END BARRIER	PHOENIX CONTACT
TB-AC, TB-UPS	A/R	3044092	GROUNDING TERMINAL BLOCK	PHOENIX CONTACT
TB-AC, TB-UPS	A/R	0800886	TERMINAL ANCHOR	PHOENIX CONTACT

TOLERANCES		REVISIONS			POMONKEY PUMP STATION UPS PANEL INT. PANEL LAYOUT		
		NO.	DATE	BY			
DECIMAL	1						
	2						
FRACTIONAL	3				DRAWN BY ZBB	SCALE NONE	MATERIAL
	4				CHK'D MN	DATE 12-31-2025	DRAWING NUMBER
ANGULAR	5						
	6				TRACED	APP'D	D32384-31



TOLERANCES	REVISIONS			POMONKEY PUMP STATION UPS PANEL		
	NO.	DATE	BY	UPS WIRING DIAGRAM		
DECIMAL	1					
	2					
FRACTIONAL	3			DRAWN BY ZBB	SCALE NONE	MATERIAL
	4			CHK'D MN	DATE 12-31-2025	DRAWING NUMBER
ANGULAR	5			TRACED	APP'D	D32384-32
	6					