

SHERWOOD-LOGAN & ASSOCIATES, INC.

WASH. (301) 970-2181

2140 RENARD COURT
ANNAPOLIS, MARYLAND 21401
FAX: (410) 841-6330

BALT: (410) 841-6810

**32384 CHARLES COUNTY POMONKEY PUMP STATION
IMPROVEMENTS**

RVSS CONTROL PANELS RESUBMITTAL

SECTION 17441 - CONTROLS SYSTEM HARDWARE

February 24, 2026

ENGINEER: WRA

CONTRACTOR: JOHNSTON CONSTRUCTION

***MANUFACTURERS' REPRESENTATIVE FOR ENGINEERED INSTRUMENTATION,
PROCESS EQUIPMENT AND PUMPING SYSTEMS***

Branch Offices: RICHMOND, VA and LEOLA, PA

32384 CHARLES COUNTY POMONKEY PUMP STATION IMPROVEMENTS

Table of Contents

Comments

Parts Index

Data Sheets

Heating and Cooling Sizes

Drawing Index

Drawings

32384 CHARLES COUNTY POMONKEY PUMP STATION IMPROVEMENTS

General Comments:

Resubmittal Comment Confirmations:

1. Main Circuit Breaker: Provide 30-amp circuit breaker as called out in Contract Documents

Sherwood Logan Response:

The main circuit breaker has been swapped out for 30-amp main circuit breaker as described in the contract documents.

2. Panel Size: Per Contract Drawing I-8, backplate width shall be 11ft. Submitted panel widths are as follows:
 - SCP: 20.00 in.
 - SPMP-01: 31.38 in.
 - SPMP-02: 31.38 in.
 - SFAN-01: 16.00 in.

Based on Contract Drawings, UPS and PLC panels are estimated to be 20 and 30 inches wide, respectively. Total width of all panels currently comes to 149in. approximately, which will not suit the 11ft backplate. Contractor shall minimize panel widths (to match Contract Drawings) as necessary to meet backplate width requirements.

Sherwood Logan Response:

The size of the SPMP-01 and SPMP-02 panels have been modified such that the width of all designed panels will fit on the 11ft. backplate.

3. Wall Mount Foot Kit: Foot Kit shall be stainless steel as indicated in Contract Drawing I-4.

Sherwood Logan Response:

The foot kit for the RVSS panels has been swapped to a stainless steel version per the requirement on Contract Drawing I-4.

4. Transient Voltage Surge Suppressor: TVSS submitted is not required per Contract Drawing I-4. Provide justification for TVSS.

Sherwood Logan Response:

The TVSS has been removed as it is not required per Contract Drawing I-4.

5. Power Meter: Power Meter submitted does not include LCD as required per Specification 17441 Section 2.18. Provide Socomec, Diris A40 Series or Approved Equal.

Sherwood Logan Response:

The submitted power meter has been changed to a Diris A40 series power meter as required by Specification 17441 Section 2.18.

6. MiniCas:
 - a. MiniCas II cutsheet provided indicates line power at terminal 2 of MiniCas (Page 148 of 175). Drawings submitted indicates line power at terminal 6 of MiniCas. Confirm/revise drawings as necessary.
 - b. Add fuse as shown upstream of MiniCas on Contract Drawing I-4. Update accordingly.

Sherwood Logan Response:

- a. The MiniCAS cut sheet has been updated to reflect the correct part number and wiring diagram. It is confirmed that line power is on terminal 6 of the MiniCAS.

- b. A fuse has been added upstream of the MiniCAS as shown on Contract Drawing I-4.

Parts Index:

SHT	MANUFACTURER	MODEL	DESCRIPTION
1	SCE	SCE-48XEL1612SSLP	Wall Mount Enclosure - NEMA 4X
1	SCE	SCE-48P16	Enclosure Backpanel
1	SCE	SCE-ELMFK4SS6-OS	Wall Mount Foot Kit
2	Square D	9422A2	Flange Mounted Disconnect Handle - NEMA 4X
2	Square D	9422CSB30	Cable Operated Disconnect Mechanism
3	Trumeter	722-0001	Elapsed Time Meter
3	Trumeter	5003-010	Gasket, Rectangular, 2-Hole
4	Schneider Electric	9001SKT38LGG31	PTT Light, 120VAC LED, Green
4	Schneider Electric	9001SKT38LRR31	PTT Light, 120VAC LED, Red
4	Schneider Electric	9001SKT38LYA31	PTT Light, 120VAC LED, Amber
5	Schneider Electric	9001SKR1B	Pushbutton, Black
5	Schneider Electric	9001KA2	1 NO Contact
5	Schneider Electric	9001KA3	1 NC Contact
6	Schneider Electric	9001SKS43BH2	3 Position Switch, Black
7	Square D	9070TF150D1	CPT-480/120V, 150VA
8	Square D	BDL36030	Main Circuit Breaker, 30A
9	Weidmuller	9926251002	Circuit Breaker, 120VAC, 2A
10	Schneider Electric	RXM2AB2F7	Miniature Relay, 120VAC, 8 Blade
10	Schneider Electric	RXZE2M114	Relay Socket, 120VAC, 8 Blade, DIN
11	Mersen	ATMR2	Fuse, Fast Acting, 2A
11	Mersen	ATMR1/2	Fuse, Fast Acting, 0.5A
11	Mersen	ATQR8/10	Fuse, Time Delay, 0.8A
11	Mersen	GGM6/10	Fast Blow Fuse, 0.6A
11	Phoenix Contact	3046100	Fuse Terminal Block, 120VAC
11	Mersen	30324R	Class CC Fuse Block, 4 Poles
12	Schneider Electric	ATS490D17Y	Reduced Voltage Soft Starter
13	Socomec	48250500	Modbus Power Meter
13	Socomec	48290555	Split Core TR-10 Sensor, 25-63A
13	Socomec	48290584	RJ12 Connection Cable, 3 Count
14	Square D	9050JCK13V20	Timing Relay, 0-60 Sec, 120VAC, 8 Pin Octal, DPDT

SHT	MANUFACTURER	MODEL	DESCRIPTION
14	Square D	8501NR51	Relay Socket, 120VAC, 8 Pin Octal, DIN
15	Square D	9050JCK23V20	Timing Relay, 0-60 Sec, 120VAC, 11 Pin Octal, DPDT
15	Square D	8501NR61	Relay Socket, 120VAC, 11 Pin Octal, DIN
16	Flygt	14-407129	Pump Monitoring Relay
17	SCE	SCE-TSH50	Enclosure Heater
17	Finder	7T.81.0.000.2403	Enclosure Heater Thermostat, NC
18	Phoenix Contact	UT 2,5	Terminal Block
18	Phoenix Contact	UT 2,5-PE	Grounding Terminal Block
18	Phoenix Contact	D-UT 2,5-10	Terminal End Barrier
18	Phoenix Contact	E/NS 35 N	Terminal Anchor

32384 CHARLES COUNTY POMONKEY PUMP STATION IMPROVEMENTS

Data Sheet 1

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: SCE: Wall Mount Enclosure - NEMA 4X Model Number: SCE-48XEL1612SSLP Tags/Service: ENC / SPMP-01/02 RVSS Control Panels Specifications: • 0.075" stainless steel type 304 • Continuously welded seams ground smooth • Stainless steel concealed hinges • Pour in place oil and water resistant gasket • Ground studs on door and body • Flange trough collar around all sides of door opening
1	Mfg: SCE: Enclosure Backpanel Model Number: SCE-48P16 Tags/Service: ENC / SPMP-01/02 RVSS Control Panels Specifications: • Subpanel, bent • Powder coated white finish • 33"H x 27"W x 0.88"D

1	Mfg: SCE: Wall Mount Foot Kit Model Number: SCE-ELMFK4SS6-OS Tags/Service: ENC / SPMP-01/02 RVSS Control Panels Specifications: • Made from heavy gauge type 316 stainless steel • Rated for NEMA 4X • 3/18-16 stainless steel mounting stud
---	---



Saginaw Control and Engineering
95 Midland Road Saginaw, MI 48638-5770
(800) 234-6871 - Fax: (989) 799-4524
SCE@SaginawControl.com

WALL MOUNT ENCLOSURE - NEMA 4X

SCE-48XEL3712SSLP

TAGS: ENC



Product Specifications:

Part Number: SCE-48XEL3712SSLP

Description: S.S. XEL Enclosure

Height: 48.00"

Width: 37.38" 16

Depth: 12.00"

Price Code: S5

List Price: \$3,066.29

Catalog Page: 274

Est. Ship Weight: 134.00 lbs

Construction

- * 0.075 In. stainless steel Type 304.
- * Seams continuously welded and ground smooth.
- * Flange trough collar around all sides of door opening.
- * Pour in place oil & water resistant gasket.
- * Collar studs 3/8-16 provided for mounting optional panels.
- * Holes provided in body for mounting disconnect operating handle and operating mechanism.
- * Stainless steel concealed hinges.
- * Doors are interchangeable and easily removed by pulling hinge pin.
- * 3-point latching mechanism when door height is greater or equal to 40 inches, 2-point latching mechanism when door height is less than 40 inches.
- * Latches are opened or closed with screwdriver (optional tamper-resistant inserts available).
- * Mounting holes in back of enclosure.
- * Mounting hardware, sealing washer and hole plug included.
- * Ground studs on door and body.
- * Black zinc die cast coinproof/padlocking handle.
- * Removable print pocket.

Application

Designed to house electrical and electronic controls, instruments and components in areas which may be regularly hosed down or are in very wet conditions. Designed to house most standard type disconnects. Provides protection from dust, dirt, oil, and water. For outdoor application a drip shield and drain vent is recommended.

For details about the design, performance expectations, applications and design suggestions - See Design Considerations
www.saginawcontrol.com/instman/considerations.pdf

Finish

#4 brushed finish on all exterior surfaces. Optional sub-panels are powder coated white.

Industry Standards - (IS6)

- * NEMA Type 3R, 4, 4X, 12 and Type 13
- * UL Listed Type 3R, 4, 4X and 12
- * CSA Type 4, 4X and 12
- * IEC 60529
- * IP 66

Notes

Disconnect switch (or circuit breaker) and operating mechanism are not furnished with this enclosure.

Special Instructions apply for IS3, IS4 and IS6 to maintain the environmental rating of Type 3R for these parts. Instructions are located on the enclosure door. Drip shield is required on IS3, drip shield is recommended on IS4 and IS6. Drain holes are required on all.

Provision for Lifting Lugs on enclosures when Height >48" and Depth >16". The Lifting Lug assembly will be included with the enclosure bolt pack.

Accessories Included

SCE-ELMFK4 Foot Kit, EL Mounting (4pc.)

Optional Accessories

SCE-48P36 Subpanel, Bent
SCE-48P36GALV Subpanel, Bent Galvanized
SCE-BVK Breather Vent
SCE-DF48EL36LP Panel, Dead Front (Wall Mount)
SCE-DS36SS Shield, S.S. Drip
SCE-ELMFK4SS6-OS Foot Kit, S.S. EL Mounting (4pc.)
SCE-ELSP3 KIT, Swing-Out Panel (20 High & Up)
SCE-RD48XEL3712SS Door, Replacement

Similar Part Numbers

SCE-36XEL2508SSLP.S. XEL Enclosure
SCE-36XEL3110SSLP.S. XEL Enclosure
SCE-36XEL3112SSLP.S. XEL Enclosure
SCE-42XEL3110SSLP.S. XEL Enclosure
SCE-42XEL3112SSLP.S. XEL Enclosure
SCE-42XEL3712SSLP.S. XEL Enclosure
SCE-42XEL3716SSLP.S. XEL Enclosure
SCE-48XEL3710SSLP.S. XEL Enclosure
SCE-48XEL3716SSLP.S. XEL Enclosure
SCE-60XEL3712SSLP.S. XEL Enclosure

Installation Information

- * ABB Flange Mounted, Disconnects and Circuit Breakers
- * Allen-Bradley Flange Mounted, Disconnects and Circuit Breakers
- * Bussmann Flange Mounted, Disconnects and Circuit Breakers
- * Cutler-Hammer Flange Mounted, Disconnects and Circuit Breakers
- * GE Flange Mounted, Disconnects and Circuit Breakers
- * Gould Flange Mounted, Disconnects and Circuit Breakers
- * Moller Flange Mounted, Disconnects and Circuit Breakers
- * Siemens Flange Mounted, Disconnects and Circuit Breakers
- * Square D Flange Mounted, Disconnects and Circuit Breakers
- * Mounting Foot Kit for Enviroline Enclosures
- * Drip Shield Kit Assembly
- * Swing Panel Assembly for Enviroline Enclosures
- * Swing Panel ELSP3 for Encl. Height > 16
- * Sealing Washer Specifications
- * LS Electric Flange Mounted Disconnects
- * Enviroline Series Single Door Enclosures For Flange Mounted Disconnects
- * Dead Front Wall Mount Installation Instructions. XEL-LP REV. 2



Your Enclosure Source®

Saginaw Control and Engineering
 95 Midland Road Saginaw, MI 48638-5770
 (800) 234-6871 - Fax: (989) 799-4524
 SCE@SaginawControl.com

SCE-48P36

Product Specifications:

Part Number: SCE-48P36
Description: Subpanel, Bent
Height: 45.00"
Width: 33.00"
Depth: 0.88"
Price Code: P3
List Price: \$190.79
Catalog Page: 444
Est. Ship Weight: 55.00 lbs



Finish

Powder Coated White.

Industry Standards - (IS17)

- ✱ NEMA Not Applicable
- ✱ UL Not Applicable
- ✱ CSA N/A

Similar Part Numbers

SCE-36P24Subpanel, Bent
 SCE-36P30Subpanel, Bent
 SCE-36P36Subpanel, Bent
 SCE-40P24Subpanel, Bent
 SCE-42P24Subpanel, Bent
 SCE-42P30Subpanel, Bent
 SCE-42P36Subpanel, Bent
 SCE-42P42Subpanel, Bent
 SCE-48P24Subpanel, Bent
 SCE-48P30Subpanel, Bent

Installation Information

- ✱ Sub-Plate Layout & Grounding for 10-32



Saginaw Control and Engineering
 95 Midland Road Saginaw, MI 48638-5770
 (800) 234-6871 - Fax: (989) 799-4524
 SCE@SaginawControl.com

STAINLESS STEEL WALL MOUNT FOOT KIT

SCE-ELMFK4SS6-OS

TAGS: ENC

Product Specifications:



Part Number: SCE-ELMFK4SS6-OS

Description: Foot Kit, S.S. EL Mounting (4pc.)

Height: 3.00"

Width: 1.50"

Depth: 2.00"

Price Code: P2

List Price: \$66.08

Catalog Page: 437

Est. Ship Weight: 0.70 lbs

Application

SCE-ELMFK4SS6-OS: Made for use with all SCE Enviroline enclosures and two-door wall-mount enclosures. Made from heavy gauge stainless steel type 316 with 3/18-16 stainless steel stud to maintain type 3, 3R, 4, 4X and 12 rating of your enclosure. Available in kits of four.

~~SCE-HLPMFK: Made for use on HLP and SA LPPL Enclosure. Zinc Die Cast and Zinc Plated.~~

Similar Part Numbers

~~SCE-HLPMFK Mounting Foot Kit for HLP and SA LPPL Enc.~~

Installation Information

- ~~* Mounting Foot Kit for Stainless Steel Enviroline Enclosures~~
- ~~* Mounting Foot Kit for HLP and SA LPPL Enclosures~~

Industry Standards - (IS17)

- * NEMA Not Applicable
- * UL Not Applicable
- * CSA N/A

Data Sheet 2

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Square D: Flange Mounted Disconnect Handle - NEMA 4X Model Number: 9422A2 Tags/Service: DISC / SPMP-01/02 RVSS Control Panels Specifications: • Flange mounted disconnect handle • 6 in. handle mechanism • Variable depth disconnect switch • For NEMA 4X enclosure, NEMA 4X rated
1	Mfg: Square D: Cable Operated Disconnect Mechanism Model Number: 9422CSB30 Tags/Service: DISC / SPMP-01/02 RVSS Control Panels Specifications: • Single cable operating mechanism • For PowerPact B 3 circuit breakers • 36" cable length

Product data sheet

Specifications

FLANGE MOUNTED DISCONNECT HANDLE

SQUARE D



TAGS: DISC

Operating mechanism, flange mounted, variable depth, handle mechanism, 6in handle, NEMA 4X enclosure

9422A2

Product availability: Stock - Normally stocked in distribution facility

Main

Product	Handle Mechanism
For Use With	Disconnect switches (30...200 A)

Complementary

Product Type	Variable depth
Product destination	disconnect switches (30...200 A)
Enclosure Types	NEMA 4/4X enclosures
Handle Length	6 in (152.4 mm)

Ordering and shipping details

Category	US10CP121732
Discount Schedule	0CP1
GTIN	785901739807
Returnability	Yes
Country of origin	MX

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	1.800 in (4.572 cm)
Package 1 Width	3.800 in (9.652 cm)
Package 1 Length	9.500 in (24.130 cm)
Package weight(Lbs)	2.749 lb(US) (1.247 kg)


Contractual warranty

Warranty (in months)	18
----------------------	----

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Dimensions Drawings

Approximate Dimensions



Product data sheet

Specifications

CABLE OPERATED DISCONNECT MECHANISM

TAGS: DISC

SQUARE D



Disconnect mechanism, circuit breaker, cable operated, 125A, 3 pole, PowerPacT B breaker, 36 inch cable

9422CSB30

Product availability: Stock - Normally stocked in distribution facility

Main

Range	9422C
Product	Single Cable Operating Mechanism

Complementary

Circuit Breaker Type	PowerPacT B 2 PowerPacT B 3
Number of Cables	1
Cable Length	36 in

Ordering and shipping details

Category	US10CP121732
Discount Schedule	0CP1
GTIN	785901093503
Returnability	Yes
Country of origin	MX

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	7.000 in (17.780 cm)
Package 1 Width	12.600 in (32.004 cm)
Package 1 Length	13.300 in (33.782 cm)
Package weight(Lbs)	5.370 lb(US) (2.436 kg)

Contractual warranty

Warranty (in months)	18
----------------------	----

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Data Sheet 3

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Trumeter: Elapsed Time Meter Model Number: 722-0001 Tags/Service: ETM / SPMP-01/02 RVSS Control Panels Specifications: • 120VAC 50/60Hz operating voltage • 6 Figure display, 99999.9 • 0.14" figure height • Hours and indicator - white on black, Decimal - black on white • Quartz accuracy • Non-reset • Black polymer case material • Polymer lens material • $\pm 0.02\%$ accuracy over entire range
1	Mfg: Trumeter: Gasket, Rectangular, 2-Hole Model Number: 5003-010 Tags/Service: ETM / SPMP-01/02 RVSS Control Panels Specifications: • NEMA 4X rated • For Trumeter 722-0001 elapsed time meter • 2-hole rectangular gasket

722 Series

Electromechanical Hour Meter



The Model 722 provides an AC Hour Meter with an operating range of 90-264VAC 50/60 Hz. You no longer require two separate meters, one for 115VAC and one for 230VAC. Models are available in the standard industry housings, 2-Hole Rectangular, Flush-Round, Square and 3-Hole Round. Its quartz time base insures accurate long-term time keeping. The totally sealed case protects against the environment and provides years of reliable service. All models are NEMA 4X,12 rated when mounted with optional gasket.

Key Features

- Operating voltage 90-264VAC 50/60Hz
- Totally Sealed
- UL/cUL Recognized, CE & RoHS Compliant
- 6 Figure, 99999.9
- Quartz accuracy
- Options include:
 - ~~Wire leads~~
 - Gasket kit (for NEMA 4X, 12 rating)
 - ~~Custom lens~~
 - ~~Terminals up, down, straight~~

Applications


- ~~Medical Equipment~~
- Control Panels
- ~~Office Equipment~~
- ~~Test Equipment~~
- ~~Generators~~

Specification

Figures	6 - digits, 0.14" [3.6mm] 99999.9 Hours and indicator - white on black Decimal - black on white
Reset	Non-reset
Voltage	90-264VAC
Frequency	50/60Hz
Power	1 watt max.
Mount	Clip or mounting holes
Terminations	1/4" [6.3mm] spade terminals
Weight	~2 oz [57 g]
Accuracy	± 0.02% over entire range
Case Material	Black polymer
Lens Material	Polymer
Approvals	UL/cUL Recognized, CE, UKCA & RoHS Compliant, SAE & NEMA 4X, 12 Compliant
Environmental	Totally Sealed
Front Panel	NEMA 4X, 12 rated with optional gasket
Temp. Range	-40°F to +185°F [-40°C to + 85°C]
Humidity	95% (SAE J1378)
Vibration	10-80 Hz. 20g max. (SAE J1378)
Shock	55g @ 9 - 13msec (SAE J1378)


Dimensions

2-Hole




Panel Opening: 1.45" X 0.95" [36.8 X 24.1]
 Recommended cut out hole size: 0.15 [3.8mm]

Flush-Rectangular



Panel Opening: 1.45" X 0.95" [36.8 X 24.1]
 Panel Thickness: 0.03 to 0.63 [0.76 to 16.00]



Part Numbers

722-0001	2-Hole Rectangular, 90-264VAC 50/60Hz, 1/4" [6.3mm] spade terminals, hours & 1/10's
722-0002	Flush-Rectangular, 90-264VAC 50/60Hz, 1/4" [6.3mm] spade terminals, hours & 1/10's
722-0003	Flush Round, 90-264VAC 50/60Hz, 1/4" [6.3mm] spade terminals, hours & 1/10's
722-0004	3-Hole Round, 90-264VAC 50/60Hz, 1/4" [6.3mm] spade terminals, hours & 1/10's
722-0030	Square 1.9", 90-264VAC 50/60Hz, 1/4" [6.3mm] spade terminals, hours & 1/10's
5003-010	NEMA 4X, 12 Gasket for Model 722-0001
5003-009	NEMA 4X, 12 Gasket for Model 722-0002
5003-008	NEMA 4X, 12 Gasket for Model 722-0003
5003-011	NEMA 4X, 12 Gasket for Model 722-0004

custom
is our passion



Data Sheet 4

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Schneider Electric: PTT Light, 120VAC LED, Green Model Number: 9001SKT38LGG31 Tags/Service: LT0330 / SPMP-01/02 RVSS Control Panels Specifications: • Push-to-test pilot light • Spring return operator type • Green projecting, unmarked operator profile • Plastic bezel material • 120VAC rated supply voltage • 0.55A rated operational current • 1 C/O contact • Silver alloy contact material • 60kA rated short-circuit making capacity • 6kA rated breaking capacity • Green fresnel polycarbonate lens
1	Mfg: Schneider Electric: PTT Light, 120VAC LED, Red Model Number: 9001SKT38LRR31 Tags/Service: LT0335 / SPMP-01/02 RVSS Control Panels Specifications: • Push-to-test pilot light • Spring return operator type

	• Red projecting, unmarked operator profile • Plastic bezel material • 120VAC rated supply voltage • 0.55A rated operational current • 1 C/O contact • Silver alloy contact material • 60kA rated short-circuit making capacity • 6kA rated breaking capacity • Red fresnel polycarbonate lens
3	Mfg: Schneider Electric: PTT Light, 120VAC LED, Amber Model Number: 9001SKT38LYA31 Tags/Service: LT0402, LT0410, LT0411 / SPMP-01/02 RVSS Control Panels Specifications: • Push-to-test pilot light • Spring return operator type • Amber projecting, unmarked operator profile • Plastic bezel material • 120VAC rated supply voltage • 0.55A rated operational current • 1 C/O contact • Silver alloy contact material • 60kA rated short-circuit making capacity • 6kA rated breaking capacity • Amber fresnel polycarbonate lens

Product data sheet

PTT LIGHT, 120VAC LED, GREEN

Specifications

TAGS: LT0330



Push-to-test pilot light, Harmony 9001SK, plastic, polycarbonate, fresnel lens, green, 30mm, LED green, 120V

9001SKT38LGG31

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Harmony 9001SK
Product or Component Type	Push-to-test pilot light
Device short name	9001SK
Type of operator	spring return
Operator profile	Green projecting, unmarked

Complementary

Bezel material	Plastic
Mounting diameter	1.2 in (30 mm)
Shape of signaling unit head	Octagonal
Light source	LED
Light source	LED
Bulb base	BA 9s
Light block supply	Direct
[Us] rated supply voltage	120 V AC/DC
[Us] rated supply voltage	120 V AC/DC
Contacts type and composition	1 C/O
Connections - terminals	Screw clamp terminals 1 x 0.22...2 x 1.5 mm² IEC 60947-1
Tightening torque	7.08 lbf.in (0.8 N.m) IEC 60947-1
shape of screw head	Cross slotted
Mechanical durability	5000000 cycles
Operating position	Any position
[Ie] rated operational current	0.55 A 125 V, DC-13, A600-Q600 NEMA
[Ui] rated insulation voltage	250 V 3)IEC 60947-1
[Uimp] rated impulse withstand voltage	2.5 kV IEC 60947-1
Contacts material	Silver alloy contacts
Positive opening	Without
Short-circuit protection	10 A cartridge fuse IEC 60947-5-1
[Ith] conventional free air thermal current	10 A

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

[Icm] rated short-circuit making capacity	12 kA 600 V AC-15, 7200 VA 15 kA 480 V AC-15, 7200 VA 30 kA 240 V AC-15, 7200 VA 60 kA 120 V AC-15, 7200 VA
Rated breaking capacity	1.2 kA 600 V AC-15, 720 VA 1.5 kA 480 V AC-15, 720 VA 3 kA 240 V AC-15, 720 VA 6 kA 120 V AC-15, 720 VA 0.1 kA 600 V DC-13 0.27 kA 250 V DC-13 0.55 kA 125 V DC-13
Net Weight	0.430 lb(US) (0.195 kg)
Device presentation	Complete product
Cap/operator or lens colour	Green
Lens type	Fresnel
[Us] rated supply voltage	120 V
Light source colour	Green
Lens material	Polycarbonate
Size	30 mm

Environment

Standards	IEC 60947-5-1 UL 508 JIS C8201-5-1 IEC 60947-5-4 JIS C 852 CSA C22.2 No 14 IEC 60947-1 JIS C8201-1
Product Certifications	UL 508 NEMA
Protective treatment	TC
Ambient Air Temperature for Storage	-40...158 °F (-40...70 °C)
Ambient Air Temperature for Operation	-13...158 °F (-25...70 °C)
Vibration resistance	7 gn (f= 2...500 Hz) conforming to IEC 60068-2-6
Shock resistance	50 gn IEC 60068-2-27
Electrical shock protection class	Class II conforming to IEC 61140
IP Degree of Protection	IP65 IP66
NEMA degree of protection	NEMA 1 NEMA 12 NEMA 13 NEMA 2 NEMA 3 NEMA 3R NEMA 4 NEMA 4X

Ordering and shipping details

Category	US10CS121429
Discount Schedule	0CS1
GTIN	785901044482
Returnability	Yes

Country of origin	MX
-------------------	----

Packing Units


Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	2.00 in (5.08 cm)
Package 1 Width	2.300 in (5.842 cm)
Package 1 Length	4.50 in (11.43 cm)
Package weight(Lbs)	4.32 oz (122.47 g)

Contractual warranty

Warranty (in months)	18
----------------------	----

Dimensions Drawings

Dimensions




e panel thickness: 1 to 6 mm / 0.04 to 0.24 in.

Mounting and Clearance

Contact Block Mounting Position

Top and Rear views



(1) It is possible to mount up to 3 levels of contacts blocks (maximum of 6 contacts blocks)

(2) Operator

(3) Locating notch

(4) Side 1

(5) Side 2

Product data sheet

PTT LIGHT, 120VAC LED, RED

Specifications

TAGS: LT0335



Push-to-test pilot light, Harmony 9001SK, plastic, polycarbonate, fresnel lens, red, 30mm, LED red, 120V

9001SKT38LRR31

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Harmony 9001SK
Product or Component Type	Push-to-test pilot light
Device short name	9001SK
Type of operator	spring return
Operator profile	Red projecting, unmarked

Complementary

Bezel material	Plastic
Mounting diameter	1.2 in (30 mm)
Shape of signaling unit head	Octagonal
Light source	LED
Light source	LED
Bulb base	BA 9s
Light block supply	Direct
[Us] rated supply voltage	120 V AC/DC
[Us] rated supply voltage	120 V AC/DC
Contacts type and composition	1 C/O
Connections - terminals	Screw clamp terminals 1 x 0.22...2 x 1.5 mm² IEC 60947-1
Tightening torque	7.08 lbf.in (0.8 N.m) IEC 60947-1
shape of screw head	Cross slotted
Mechanical durability	5000000 cycles
Operating position	Any position
[Ie] rated operational current	0.55 A 125 V, DC-13, A600-Q600 NEMA
[Ui] rated insulation voltage	250 V 3)IEC 60947-1
[Uimp] rated impulse withstand voltage	2.5 kV IEC 60947-1
Contacts material	Silver alloy contacts
Positive opening	Without
Short-circuit protection	10 A cartridge fuse IEC 60947-5-1
[Ith] conventional free air thermal current	10 A

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

[Icm] rated short-circuit making capacity	12 kA 600 V AC-15, 7200 VA 15 kA 480 V AC-15, 7200 VA 30 kA 240 V AC-15, 7200 VA 60 kA 120 V AC-15, 7200 VA
Rated breaking capacity	1.2 kA 600 V AC-15, 720 VA 1.5 kA 480 V AC-15, 720 VA 3 kA 240 V AC-15, 720 VA 6 kA 120 V AC-15, 720 VA 0.1 kA 600 V DC-13 0.55 kA 125 V DC-13
Net Weight	0.430 lb(US) (0.195 kg)
Device presentation	Complete product
Cap/operator or lens colour	Red
Lens type	Fresnel
[Us] rated supply voltage	120 V
Light source colour	Red
Lens material	Polycarbonate
Size	30 mm

Environment

Standards	UL 508 CSA C22.2 No 14 JIS C8201-5-1 JIS C 852 IEC 60947-5-4 IEC 60947-1 IEC 60947-5-1 JIS C8201-1
Product Certifications	UL 508 NEMA
Protective treatment	TC
Ambient Air Temperature for Storage	-40...158 °F (-40...70 °C)
Ambient Air Temperature for Operation	-13...158 °F (-25...70 °C)
Vibration resistance	7 gn (f= 2...500 Hz) conforming to IEC 60068-2-6
Shock resistance	50 gn IEC 60068-2-27
Electrical shock protection class	Class II conforming to IEC 61140
IP Degree of Protection	IP65 IP66
NEMA degree of protection	NEMA 1 NEMA 12 NEMA 13 NEMA 2 NEMA 3 NEMA 3R NEMA 4 NEMA 4X

Ordering and shipping details

Category	US10CS121429
Discount Schedule	0CS1
GTIN	785901044505
Returnability	Yes
Country of origin	MX

Packing Units


Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	2.00 in (5.08 cm)
Package 1 Width	2.300 in (5.842 cm)
Package 1 Length	4.50 in (11.43 cm)
Package weight(Lbs)	4.32 oz (122.47 g)

Contractual warranty

Warranty (in months)	18
----------------------	----

Dimensions Drawings

Dimensions




e panel thickness: 1 to 6 mm / 0.04 to 0.24 in.

Mounting and Clearance

Contact Block Mounting Position

Top and Rear views



- (1) It is possible to mount up to 3 levels of contacts blocks (maximum of 6 contacts blocks)
- (2) Operator
- (3) Locating notch
- (4) Side 1
- (5) Side 2



Push-to-test pilot light, Harmony 9001SK, plastic, polycarbonate, fresnel lens, amber, 30mm, LED yellow, 120V

9001SKT38LYA31

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Harmony 9001SK
Product or Component Type	Push-to-test pilot light
Device short name	9001SK
Type of operator	spring return
Operator profile	Amber projecting, unmarked

Complementary

Bezel material	Plastic
Mounting diameter	1.2 in (30 mm)
Shape of signaling unit head	Octagonal
Light source	LED
Light source	LED
Bulb base	BA 9s
Light block supply	Direct
[Us] rated supply voltage	120 V AC/DC
[Us] rated supply voltage	120 V AC/DC
Contacts type and composition	1 C/O
Connections - terminals	Screw clamp terminals 1 x 0.22...2 x 1.5 mm² IEC 60947-1
Tightening torque	7.08 lbf.in (0.8 N.m) IEC 60947-1
shape of screw head	Cross slotted
Mechanical durability	5000000 cycles
Operating position	Any position
[Ie] rated operational current	0.55 A 125 V, DC-13, A600-Q600 NEMA
[Ui] rated insulation voltage	250 V 3)IEC 60947-1
[Uimp] rated impulse withstand voltage	2.5 kV IEC 60947-1
Contacts material	Silver alloy contacts
Positive opening	Without
Short-circuit protection	10 A cartridge fuse IEC 60947-5-1
[Ith] conventional free air thermal current	10 A

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

[Icm] rated short-circuit making capacity	12 kA 600 V AC-15, 7200 VA 30 kA 480 V AC-15, 7200 VA 60 kA 120 V AC-15, 7200 VA
Rated breaking capacity	1.2 kA 600 V AC-15, 720 VA 3 kA 480 V AC-15, 720 VA 6 kA 120 V AC-15, 720 VA 0.27 kA 250 V DC-13 0.55 kA 125 V DC-13
Net Weight	0.430 lb(US) (0.195 kg)
Device presentation	Complete product
Cap/operator or lens colour	Amber
Lens type	Fresnel
[Us] rated supply voltage	120 V
Light source colour	Yellow
Lens material	Polycarbonate
Size	30 mm

Environment

Standards	JIS C8201-5-1 CSA C22.2 No 14 IEC 60947-5-1 IEC 60947-5-4 IEC 60947-1 UL 508 JIS C 852 JIS C8201-1
Product Certifications	NEMA UL 508
Protective treatment	TC
Ambient Air Temperature for Storage	-40...158 °F (-40...70 °C)
Ambient Air Temperature for Operation	-13...158 °F (-25...70 °C)
Vibration resistance	7 gn (f= 2...500 Hz) conforming to IEC 60068-2-6
Shock resistance	50 gn IEC 60068-2-27
Electrical shock protection class	Class II conforming to IEC 61140
IP Degree of Protection	IP65 IP66
NEMA degree of protection	NEMA 1 NEMA 12 NEMA 13 NEMA 2 NEMA 3 NEMA 3R NEMA 4 NEMA 4X

Ordering and shipping details

Category	US10CS121429
Discount Schedule	0CS1
GTIN	785901500582
Returnability	Yes
Country of origin	MX

Packing Units


Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	1.969 in (5.000 cm)
Package 1 Width	2.362 in (6.000 cm)
Package 1 Length	4.488 in (11.400 cm)
Package weight(Lbs)	4.233 oz (120.000 g)
Unit Type of Package 2	S01
Number of Units in Package 2	12
Package 2 Height	5.906 in (15.000 cm)
Package 2 Width	5.906 in (15.000 cm)
Package 2 Length	15.748 in (40.000 cm)
Package 2 Weight	3.616 lb(US) (1.640 kg)
Unit Type of Package 3	P12
Number of Units in Package 3	384
Package 3 Height	17.717 in (45.000 cm)
Package 3 Width	31.496 in (80.000 cm)
Package 3 Length	47.244 in (120.000 cm)
Package 3 Weight	142.154 lb(US) (64.480 kg)

Contractual warranty

Warranty (in months)	18
----------------------	----

Dimensions Drawings

Dimensions




e panel thickness: 1 to 6 mm / 0.04 to 0.24 in.

Mounting and Clearance

Contact Block Mounting Position

Top and Rear views



- (1) It is possible to mount up to 3 levels of contacts blocks (maximum of 6 contacts blocks)
- (2) Operator
- (3) Locating notch
- (4) Side 1
- (5) Side 2

Data Sheet 5

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Schneider Electric: Pushbutton, Black Model Number: 9001SKR1B Tags/Service: PB0310 / SPMP-01/02 RVSS Control Panels Specifications: • Plastic bezel material • Octagonal shape of signaling unit head • Without contact block and light source • NEMA 4X rated degree of protection • Black operator color • Flush operator profile • Spring return operator
1	Mfg: Schneider Electric: 1 NO Contact Model Number: 9001KA2 Tags/Service: PB0310 / SPMP-01/02 RVSS Control Panels Specifications: • 1 NO contact composition • Standard contact operation • Silver alloy contact material • 10A conventional free air thermal current • 0.55A rated operation current • 120VAC rated operational voltage

	• 60kA rated short-circuit making capacity • 6kA rated breaking capacity
2	Mfg: Schneider Electric: 1 NC Contact Model Number: 9001KA3 Tags/Service: PB0310 / SPMP-01/02 RVSS Control Panels Specifications: • 1 NC contact composition • Standard contact operation • Silver alloy contact material • 10A conventional free air thermal current • 0.55A rated operation current • 120VAC rated operational voltage • 60kA rated short-circuit making capacity • 6kA rated breaking capacity

Product data sheet

PUSHBUTTON, BLACK

Specifications

TAGS: PB0310



Push button head, Harmony
9001SK, plastic, flush, black, 30mm,
spring return

9001SKR1B

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Harmony 9001SK
Product or Component Type	Head for push-button
Device short name	9001SK

Complementary

Bezel material	Plastic
Mounting diameter	1.2 in (30 mm)
Shape of signaling unit head	Octagonal
Light source	without
Light block supply	Without supply
Contacts type and composition	Without contact block
Product Certifications	CE CSA LR24590 class 3211 03 UL listed file E42259 CCN NKCR
NEMA degree of protection	NEMA 3R/4X/13
Cap/operator or lens colour	Black
Operator profile	Flush
Type of operator	Spring return
Size	30 mm

Environment

IP Degree of Protection	IP65 IP66
-------------------------	--------------

Ordering and shipping details

Category	US10CS121429
Discount Schedule	0CS1
GTIN	785901793878
Returnability	Yes
Country of origin	MX

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Package 1 Height	2.800 in (7.112 cm)
Package 1 Width	2.300 in (5.842 cm)
Package 1 Length	2.00 in (5.08 cm)
Package weight(Lbs)	1.600 oz (45.359 g)

Contractual warranty

Warranty (in months)	18
----------------------	----

Product data sheet

1 NO CONTACT

Specifications

TAGS: PB0310



30mm Push Button, Types K, SK or KX, contact block, 1 NO

9001KA2

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Harmony 9001K Harmony 9001SK
Product or Component Type	Contact block
Device short name	9001K
Contacts type and composition	1 NO

Complementary

Terminals description ISO n°1	(1-2)NC
Net Weight	0.051 lb(US) (0.023 kg)
Contact operation	Standard
Positive opening	Without
Connections - terminals	Screw clamp terminals, 1 x 0.22...2 x 2.5 mm² IEC 60947-1
Tightening torque	7.08 lbf.in (0.8 N.m) IEC 60947-1
Shape of screw head	Cross slotted
Contacts material	Silver alloy contacts
Short-circuit protection	10 A cartridge fuse IEC 60947-5-1
[Ith] conventional free air thermal current	10 A
[Ui] rated insulation voltage	250 V 3)IEC 60947-1
[Uimp] rated impulse withstand voltage	2.5 kV IEC 60947-1
[Ie] rated operational current	3 A 240 V, AC-15, A600-Q600 NEMA 0.55 A 125 V, DC-13, A600-Q600 NEMA
[Icm] rated short-circuit making capacity	12 kA 600 V AC-15, 7200 VA 15 kA 480 V AC-15, 7200 VA 30 kA 240 V AC-15, 7200 VA 60 kA 120 V AC-15, 7200 VA 0.27 kA 250 V DC-13, 7200 VA 0.55 kA 125 V DC-13, 7200 VA 0.1 kA 600 V DC-13
Rated breaking capacity	3 kA 240 V AC-15, 720 VA 6 kA 120 V AC-15, 720 VA 1.2 kA 600 V AC-15, 720 VA 1.5 kA 480 V AC-15, 720 VA 0.1 kA 600 V DC-13 0.27 kA 250 V DC-13 0.55 kA 125 V DC-13
[Us] rated supply voltage	0...600 V
Connections - Terminals	Screw-clamp terminals

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Environment

Protective treatment	TC
Ambient Air Temperature for Storage	-40...158 °F (-40...70 °C)
Ambient Air Temperature for Operation	-13...158 °F (-25...70 °C)
Electrical shock protection class	Class II conforming to IEC 61140
Standards	IEC 60947-5-4 JIS C 852 IEC 60947-5-1 JIS C 4520 CSA C22.2 No 14 UL 508 IEC 60947-1 UL 60947-5-1
Product Certifications	UL 508 NEMA
Vibration resistance	7 gn (f= 2...500 Hz) conforming to IEC 60068-2-6
Shock resistance	50 gn IEC 60068-2-27

Ordering and shipping details

Category	US10CS121434
Discount Schedule	0CS1
GTIN	785901880011
Returnability	Yes
Country of origin	MX

Packing Units


Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	1.181 in (3.000 cm)
Package 1 Width	1.575 in (4.000 cm)
Package 1 Length	1.969 in (5.000 cm)
Package weight(Lbs)	0.776 oz (22.000 g)
Unit Type of Package 2	S01
Number of Units in Package 2	100
Package 2 Height	5.906 in (15.000 cm)
Package 2 Width	5.906 in (15.000 cm)
Package 2 Length	15.748 in (40.000 cm)
Package 2 Weight	5.269 lb(US) (2.390 kg)

Contractual warranty

Warranty (in months)	18
----------------------	----

Dimensions Drawings

Dimensions




e panel thickness: 1 to 6 mm / 0.04 to 0.24 in.

Mounting and Clearance

Contact Block Mounting Position

Top and Rear views



- (1) It is possible to mount up to 3 levels of contacts blocks (maximum of 6 contacts blocks)
- (2) Operator
- (3) Locating notch
- (4) Side 1
- (5) Side 2

Product data sheet

1 NC CONTACT

Specifications

TAGS: PB0310



30mm Push Button, Types K, SK or KX, contact block, 1 NC

9001KA3

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Harmony 9001K Harmony 9001SK
Product or Component Type	Contact block
Device short name	9001K
Contacts type and composition	1 NC

Complementary

Terminals description ISO n°1	(3-4)NO
Net Weight	0.051 lb(US) (0.023 kg)
Contact operation	Positive opening
Positive opening	With IEC 60947-5-2
Connections - terminals	Screw clamp terminals, 1 x 0.22...2 x 2.5 mm² IEC 60947-1
Tightening torque	7.08 lbf.in (0.8 N.m) IEC 60947-1
Shape of screw head	Cross slotted
Contacts material	Silver alloy contacts
Short-circuit protection	10 A cartridge fuse IEC 60947-5-1
[Ith] conventional free air thermal current	10 A
[Ui] rated insulation voltage	250 V 3)IEC 60947-1
[Uimp] rated impulse withstand voltage	2.5 kV IEC 60947-1
[Ie] rated operational current	3 A 240 V, AC-15, A600-Q600 NEMA 0.55 A 125 V, DC-13, A600-Q600 NEMA
[Icm] rated short-circuit making capacity	12 kA 600 V AC-15, 7200 VA 15 kA 480 V AC-15, 7200 VA 30 kA 240 V AC-15, 7200 VA 60 kA 120 V AC-15, 7200 VA 0.55 kA 125 V DC-13 0.1 kA 600 V DC-13 0.27 kA 250 V DC-13
Rated breaking capacity	3 kA 240 V AC-15, 720 VA 6 kA 120 V AC-15, 720 VA 1.2 kA 600 V AC-15, 720 VA 1.5 kA 480 V AC-15, 720 VA 0.1 kA 600 V DC-13 0.27 kA 250 V DC-13 0.55 kA 125 V DC-13
[Us] rated supply voltage	0...600 V
Connections - Terminals	Screw-clamp terminals

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Environment

Protective treatment	TC
Ambient Air Temperature for Storage	-40...158 °F (-40...70 °C)
Ambient Air Temperature for Operation	-13...158 °F (-25...70 °C)
Electrical shock protection class	Class II conforming to IEC 61140
Standards	UL 508 JIS C 4520 JIS C 852 IEC 60947-5-4 CSA C22.2 No 14 IEC 60947-1 IEC 60947-5-1 UL 60947-5-1
Product Certifications	NEMA UL 508
Vibration resistance	7 gn (f= 2...500 Hz) conforming to IEC 60068-2-6
Shock resistance	50 gn IEC 60068-2-27

Ordering and shipping details

Category	US10CS121434
Discount Schedule	0CS1
GTIN	785901880028
Returnability	Yes
Country of origin	MX

Packing Units


Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	1.378 in (3.500 cm)
Package 1 Width	1.654 in (4.200 cm)
Package 1 Length	2.008 in (5.100 cm)
Package weight(Lbs)	0.811 oz (23.000 g)
Unit Type of Package 2	S01
Number of Units in Package 2	100
Package 2 Height	5.906 in (15.000 cm)
Package 2 Width	5.906 in (15.000 cm)
Package 2 Length	15.748 in (40.000 cm)
Package 2 Weight	5.196 lb(US) (2.357 kg)

Contractual warranty

Warranty (in months)	18
----------------------	----

Dimensions Drawings

Dimensions




e panel thickness: 1 to 6 mm / 0.04 to 0.24 in.

Mounting and Clearance

Contact Block Mounting Position

Top and Rear views



- (1) It is possible to mount up to 3 levels of contacts blocks (maximum of 6 contacts blocks)
- (2) Operator
- (3) Locating notch
- (4) Side 1
- (5) Side 2

Data Sheet 6

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Schneider Electric: 3 Position Switch, Black Model Number: 9001SKS43BH2 Tags/Service: SS0321 / SPMP-01/02 RVSS Control Panels Specifications: • Plastic bezel material • 3 position, 2 C/O contact composition • Standard handle operator profile • Black operator color • Stay put operator type

TAGS: SS0321



Selector switch, Harmony 9001SK, plastic, standard handle, black, 30mm, 3 positions, stay put, 2 C/O

9001SKS43BH2

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Harmony 9001SK
Product or Component Type	Selector switch
Device short name	9001SK

Complementary

Bezel material	Plastic
Mounting diameter	1.2 in (30 mm)
Operator position information	3 positions
Contacts type and composition	2 C/O
Device presentation	Complete product
Cap/operator or lens colour	Black
Operator profile	Standard handle
Type of operator	Stay put
Size	30 mm
Cam profile	3

Environment

Protective treatment	TC
Ambient Air Temperature for Storage	-40...158 °F (-40...70 °C)
Ambient Air Temperature for Operation	-13...158 °F (-25...70 °C)
Electrical shock protection class	Class II conforming to IEC 61140
IP Degree of Protection	IP65 IP66
NEMA degree of protection	NEMA 3R/4X/13
Product Certifications	UL listed file E42259 CCN NKCR CE CSA LR24590 class 3211 03

Ordering and shipping details

Category	US10CS121429
Discount Schedule	0CS1
GTIN	785901043799
Returnability	Yes

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Country of origin	MX
-------------------	----

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	1.900 in (4.826 cm)
Package 1 Width	2.200 in (5.588 cm)
Package 1 Length	3.700 in (9.398 cm)
Package weight(Lbs)	4.000 oz (113.398 g)

Contractual warranty

Warranty (in months)	18
----------------------	----

Data Sheet 7

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Square D: CPT-480/120V, 150VA Model Number: 9070TF150D1 Tags/Service: T0315 / SPMP-01/02 RVSS Control Panels Specifications: • 480VAC primary, 120VAC secondary voltage • Accepts CC fuse types • Screw clamp terminal electrical connection • Copper winding material



Industrial control transformer, Type TF, 1 phase, 150VA, 240x480V primary, 120V secondary, 50/60Hz

9070TF150D1

Product availability: Stock - Normally stocked in distribution facility

Main

Product or Component Type	Industrial Control Transformer
Type	TF

Complementary

Number of Phases	1 phase
Power Rating	150 VA UL 150-VA-CSA 150-VA-NOM 150-VA-CE
Primary to Secondary Voltage	240 x 480 V 120 V 230 x 460 V 115 V 220 x 440 V 110 V
Fuse type	0.41 x 1.50 in CC top
Temperature rise	55 °C
Electrical Connection	Screw clamp terminals
Height	4.5 in (114.3 mm)
Width	3.75 in (95.25 mm)
Depth	3.59 in (91.19 mm)
Material	Copper: winding
Fingersafe Cover Compatibility	FSC1

Environment

Product Certifications	CSA file LR37055 guide 184-N-90 UL listed file E61239
Enclosure Type	Not rated (open device)
Insulation temperature	221 °F (105 °C)

Ordering and shipping details

Category	US10CP816202
Discount Schedule	0CP8
GTIN	785901904793
Returnability	Yes
Country of origin	MX

Packing Units

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications


Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	6.50 in (16.51 cm)
Package 1 Width	7.00 in (17.78 cm)
Package 1 Length	7.700 in (19.558 cm)
Package weight(Lbs)	6.700 lb(US) (3.039 kg)

Contractual warranty

Warranty (in months)	18
----------------------	----


Technical Illustration

Dimensions



Technical Illustration

Wiring diagram



Options

Voltage Code	Voltages		Connections	
	Primary	Secondary	Primary	Secondary
D1	220 x 440 230 x 460 240 x 480	110 115 120	220 or 230 or 240: Connect to H1 and H4 Jumper H1 with H3 Jumper H2 with H4 440 or 460 or 480: Connect to H1 and H4 Jumper H2 with H3	Connect to X1 and X2

REFER TO TECHNICAL DOCUMENTATION FOR COMPLETE INFORMATION.

Data Sheet 8

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Square D: Main Circuit Breaker, 30A Model Number: BDL36030 Tags/Service: CB0301 / SPMP-01/02 RVSS Control Panels Specifications: • 30A line rated current • 3 pole circuit breaker, toggle control type • 18kA breaking capacity • Thermal magnetic trip unit technology • 80% continuous current rating • 44.3 lbf.in tightening torque

Product data sheet

MAIN CIRCUIT BREAKER, 30A

Specifications

TAGS: CB0301



Circuit breaker, PowerPacT B, 30A, 3 pole, 600Y/347VAC, 14kA, lugs, thermal magnetic, 80%

BDL36030

Product availability: Stock - Normally stocked in distribution facility

Main

Range	PowerPact
Product name	PowerPact B
Device short name	BD 030
Product or Component Type	Circuit breaker
Device Application	Distribution

Complementary

Line Rated Current	30 A
Number of Poles	3P
Control Type	Toggle
Breaking capacity code	D
Breaking capacity	25 kA-208Y/120-V AC 50/60 Hz UL 489 25 kA-240-V AC 50/60 Hz UL 489 18 kA-480/277-V AC 50/60 Hz UL 489 18 kA 480 V AC 50/60 Hz UL 489 14 kA-600Y/347-V AC 50/60 Hz UL 489 10 kA-250-V DC UL 489
[Ue] rated operational voltage	525 V AC 50/60 Hz UL 489
Network Frequency	50/60 Hz
[Ics] rated service breaking capacity	25 kA-220...240-V AC 50/60 Hz IEC 60947-2 18 kA-500...525-V AC 50/60 Hz IEC 60947-2 25 kA-380...415-V AC 50/60 Hz IEC 60947-2 18 kA 440 V AC 50/60 Hz IEC 60947-2
[Uimp] rated impulse withstand voltage	8 kV IEC 60947-2
Trip unit technology	Thermal-magnetic
Continuous current rating	80 %
[UI] rated insulation voltage	800 V IEC 60947-2
Suitability for isolation	Yes IEC 60947-2
Utilisation category	Category A
Mechanical durability	20000 cycles IEC 947-1 Annex K ed 5.2
Electrical durability	10000 cycles IEC 947-1 Annex K ed 5.2 440 V In
Connection pitch	1.06 in (27 mm)
AWG gauge	AWG 6...AWG 2/0 fine stranded aluminium/copper AWG 14...AWG 3/0 rigid or stranded aluminium/copper
Local signalling	Presence of auxiliary contacts flag green)

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Mounting mode	Clip-on 35 x 15 mm symmetrical DIN rail) By screws plate)
Electrical connection	Everlink lug, line Everlink lug, load
Tightening torque	44.3 lbf.in (5 N.m) 0.004...0.02 in² (2.5...16 mm²) (AWG 14...AWG 4) 79.7 lbf.in (9 N.m) 0.04...0.1 in² (25...95 mm²) (AWG 3...AWG 3/0)
Number of slots	1 auxiliary switch OF plug-in) 1 voltage release MN or MX plug-in) 1 alarm switch SD plug-in)
Power wire stripping length	0.8 in (20 mm)
Color	Gray RAL 7016)
9 mm pitches	9
Height	5.4 in (137 mm)
Width	3.2 in (81 mm)
Depth	3.1 in (80 mm)
Net Weight	2.368 lb(US) (1.074 kg)
Quantity per Set	Set of 1
Circuit breaker application	HACR rated

Environment

Quality labels	CE
Standards	EN/IEC 60947-5-1 UL 489 NMX J-266 NEMA AB1 CSA C22.2 No 5 GB 14048.2 EN/IEC 60947-2
Product certifications	UL IEC CCC EAC CSA NOM
IP degree of protection	Front cover IP40 IEC 60529
IK degree of protection	IK07 conforming to IEC 62262
Pollution degree	3 IEC 60947-1
Ambient Air Temperature for Operation	-13...158 °F (-25...70 °C)
Ambient Air Temperature for Storage	-58...185 °F (-50...85 °C)
Operating altitude	< 6561.68 ft (2000 m) without derating 5000 m with derating

Ordering and shipping details

Category	US10DE201130
Discount Schedule	0DE2
GTIN	3606481153029
Returnability	Yes

Packing Units

Unit Type of Package 1	PCE
------------------------	-----

Data Sheet 9

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Weidmuller: Circuit Breaker, 120VAC, 2A Model Number: 9926251002 Tags/Service: CB0319 / SPMP-01/02 RVSS Control Panels Specifications: • 120VAC 50/60Hz nominal supply voltage • 2A rated current • 10kA interrupting capacity • 1500V, 50/60Hz dielectric strength • 100MΩ insulation resistance • 10,000 mechanical operation operating life • -40-60° C operating temperature • 20lb-in tightening torque

9926 Series Branch Rated Circuit Breakers-AC Version

Circuit Breakers

Hydraulic Magnetic Type

- Single pole and double pole versions
- Higher current ratings made of 2 or 3 poles in parallel
- KM trip curve for general purpose applications
- 120/240 VAC, 50/60 Hz
- Up to 25A
- Just 13 mm wide
- Mounts on 35mm DIN-rail
- UL 489 listed, CSA C22.2 No. 5-02, CE

**9926 Series
Single Pole**



**9926 Series
Double Pole**



Ordering Data

This image shows a single sheet of white paper with horizontal blue ruling lines. The lines are evenly spaced and run across the width of the page. There is no handwriting or other markings on the paper.

Type: Single Pole

Current Ratings (amps)	Part No. TS 35	Description
0.5	9926251000	QL-1-13-DM-KM-0.5
1	9926251001	QL-1-13-DM-KM-01
2	9926251002	QL-1-13-DM-KM-02
3	9926251003	QL-1-13-DM-KM-03
4	9926251004	QL-1-13-DM-KM-04
5	9926251005	QL-1-13-DM-KM-05
6	9926251006	QL-1-13-DM-KM-06
7	9926251007	QL-1-13-DM-KM-07
8	9926251008	QL-1-13-DM-KM-08
10	9926251010	QL-1-13-DM-KM-10
13	9926251013	QL-1-13-DM-KM-13
15	9926251015	QL-1-13-DM-KM-15
16	9926251016	QL-1-13-DM-KM-16
20	9926251020	QL-1-13-DM-KM-20
25	9926251025	QL-1-13-DM-KM-25

Type: Double Pole

Current Ratings (amps)	Part No. TS 35	Description
0.5	9926252000	QL-2-13-DM-KM-0.5
1	9926252001	QL-2-13-DM-KM-01
2	9926252002	QL-2-13-DM-KM-02
3	9926252003	QL-2-13-DM-KM-03
4	9926252004	QL-2-13-DM-KM-04
5	9926252005	QL-2-13-DM-KM-05
6	9926252006	QL-2-13-DM-KM-06
7	9926252007	QL-2-13-DM-KM-07
8	9926252008	QL-2-13-DM-KM-08
10	9926252010	QL-2-13-DM-KM-10
13	9926252013	QL-2-13-DM-KM-13
15	9926252015	QL-2-13-DM-KM-15
16	9926252016	QL-2-13-DM-KM-16
20	9926252020	QL-2-13-DM-KM-20
25	9926252025	QL-2-13-DM-KM-25

Technical Data

Voltage	120/240 VAC, 50/60Hz
Current	
minimum	0.5A
maximum	25A
Interrupting capacity	10,000A
Dielectric strength	1500V, 50/60Hz
Insulation resistance	100M Ω
Operating life	10000 mechanical operations
Operating temperature	-40...+60°C
Wire size*	
0.5-15A:	14AWG min., 10AWG max.
20-25A:	10AWG min.
Torque	20 lb-in.

Approval

UL 489 listed, CSA C22.2 No. 5-02, CE

Accessories

Bus-bar (54 pole, insulated)	67101904
------------------------------	----------



*Wire sizes: gauges specified are the minimum allowable as per CSA and UL standards

The 9926 circuit breakers do not have provisions for marking tags. A possible solution is to cut the adhesive SchS2 tag rail to length (approximately 20 mm on a single pole unit so the current rating remains visible or approximately 30 mm on a two pole unit).

The SchS2 accepts DEK, WS and ESG 8/17 marking tags.

The part number for adhesive SchS2 is **1720600000**.

9926 Series AC Version - dimensions in mm



Trip Curves—Hydraulic Magnetic Type
Typical time/current characteristics at 40°C


Sample trip characteristics

	125%	150%	200%	400%	600%	800%	1000%
minimum (sec)	15	8	4	0.7	0.09	0.007	0.005
maximum (sec)	300	90	28	4	1.5	0.6	0.4

Although the 9926 series uses a magnetic only trip mechanism, CSA testing indicates a trip characteristic similar to thermal magnetic trip mechanisms. No de-rating is required at elevated temperatures.

Additional trip curves and amp ratings are available upon request.

9926 Series-AC version



Data Sheet 10

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
4	Mfg: Schneider Electric: Miniature Relay, 120VAC, 8 Blade Model Number: RXM2AB2F7 Tags/Service: CR0324, CR0332, CR0336, CR0401 / SPMP-01/02 RVSS Control Panels Specifications: • Miniature plug-in relay • 2 C/O contacts • With status LED and lockable test button • 120VAC control circuit voltage • 10A continuous output current • 12A rated operational current • 100000 cycles resistive electrical durability • 1.2VA average power consumption • Silver nickel contact material
4	Mfg: Schneider Electric: Relay Socket, 120VAC, 8 Blade, DIN Model Number: RXZE2M114 Tags/Service: CR0324, CR0332, CR0336, CR0401 / SPMP-01/02 RVSS Control Panels Specifications: • For miniature plug-in relay RXM, 2 C/O contact composition • Screw clamp terminals, clip-on DIN rail mounting

	• Mixed contact terminal arrangement • < 300VAC UL rated operational voltage
--	---

Product data sheet

MINIATURE RELAY, 120VAC, 8 BLADE

Specifications

TAGS: CR0324, CR0332, CR0336, CR0401



miniature plug in relay, Harmony Electromechanical Relays, 12A, 2CO, with LED, lockable test but to n, 120V AC

RXM2AB2F7

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Harmony Electromechanical Relays
Series name	RXM series
Product or Component Type	Plug-in relay
Relay Type	Miniature relay
Contacts type and composition	2 C/O
Status LED	With
Control Type	Lockable test button
[Uc] control circuit voltage	120 V AC 50/60 Hz
[Ithe] conventional enclosed thermal current	12 A
Continuous output current	10 A

Complementary

[Uimp] rated impulse withstand voltage	4 kV 1.2/50 µs
[Ie] rated operational current	12 A 28 V DC) NO-IEC 12 A 250 V AC) NO-IEC 6 A 28 V DC) NC-IEC 6 A 250 V AC) NC-IEC 12 A 28 V DC) UL 12 A 277 V AC) UL
Minimum switching capacity	170 mW 10 mA, 17 V
Electrical durability	100000 cycles resistive
Average coil consumption in VA	1.2 60 Hz
Rated operational voltage limits	96...132 V AC
[Ui] rated insulation voltage	250 V IEC 300 V CSA 300 V UL
Average consumption	1.2 VA 60 Hz
Maximum switching voltage	250 V IEC
Drop-out voltage threshold	>= 0.15 Uc
Load current	12 A 250 V AC 12 A 28 V DC
Operating time	20 ms
Maximum switching capacity	3000 VA/336 W
Average resistance	4430 Ohm 20 °C +/- 15 %

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Mechanical durability	10000000 cycles
Safety reliability data	B10d = 100000
Operating rate	<= 1200 cycles/hour under load <= 18000 cycles/hour no-load
Utilisation coefficient	20 %
CAD overall height	3.1 in (79 mm)
CAD overall depth	3.09 in (78.45 mm)
reset time	20 ms
Dielectric strength	1300 V AC between contacts with micro disconnection 2000 V AC between coil and contact with basic insulation 2000 V AC between poles with basic insulation
Compatibility code	RXM
Protection category	RT I
Pollution degree	3
Operating position	Any position
Test levels	Level A group mounting
Device presentation	Complete product
Contacts material	AgNi
Shape of pin	Flat (faston type)
Net Weight	0.082 lb(US) (0.037 kg)

Environment

Ambient air temperature for operation	-40...131 °F (-40...55 °C)
IP degree of protection	IP40 conforming to IEC 60529
Standards	CSA C22.2 No 14 IEC 61810-1 UL 508
Product Certifications	UL Lloyd's CE CSA GOST IECEE CB Scheme
Ambient Air Temperature for Storage	-40...185 °F (-40...85 °C)
Vibration resistance	3 gn +/- 1 mm 10...150 Hz)5 cycles in operation 5 gn +/- 1 mm 10...150 Hz)5 cycles not operating
Shock resistance	10 gnin operation 30 gnnot operating

Ordering and shipping details

Category	US10CP221127
Discount Schedule	0CP2
GTIN	3389119403504
Returnability	Yes
Country of origin	CN

Packing Units


Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	0.827 in (2.100 cm)
Package 1 Width	1.063 in (2.700 cm)
Package 1 Length	1.811 in (4.600 cm)
Package weight(Lbs)	1.305 oz (37.000 g)
Unit Type of Package 2	BB1
Number of Units in Package 2	10
Package 2 Height	1.181 in (3.000 cm)
Package 2 Width	4.016 in (10.200 cm)
Package 2 Length	4.921 in (12.500 cm)
Package 2 Weight	13.686 oz (388.000 g)
Unit Type of Package 3	S02
Number of Units in Package 3	240
Package 3 Height	5.906 in (15.000 cm)
Package 3 Width	11.811 in (30.000 cm)
Package 3 Length	15.748 in (40.000 cm)
Package 3 Weight	21.625 lb(US) (9.809 kg)

Contractual warranty


Warranty (in months)	18
----------------------	----

Dimensions Drawings

Dimensions




Pin Side View



Connections and Schema

Wiring Diagram




Symbols shown in blue correspond to Nema marking.

Performance Curves


Electrical Durability of Contacts

Durability (inductive load) = durability (resistive load) x reduction coefficient.
Resistive AC load




X Switching capacity (kVA)
Y Durability (Number of operating cycles)
A RXM2AB...
B RXM3AB...
C RXM4AB...
D RXM4GB...

Reduction coefficient for inductive AC load (depending on power factor cos φ)




Y Reduction coefficient (A)
Maximum switching capacity on resistive DC load



X Voltage DC
Y Current DC
A RXM2AB...
B RXM3AB...
C RXM4AB...
D RXM4GB...

Note : These are typical curves, actual durability depends on load, environment, duty cycle, etc.
For inductive load, to increase relay life cycles, please add a proper load protection circuit (eg: RC protection/Varistor/free Wheeling diode -DC load only-).
For low level loads (below 10mA), we recommend to use RXM*GB series with bifurcated contacts relays instead.


AC Coil Voltage and Operating Temperature under continuous duty



X : Operating temperature (°C)
Y : AC coil voltage (UC)

Technical Illustration

Dimensions



Product data sheet

Specifications

MINIATURE RELAY SOCKET, 120VAC, 8 BLADE, DIN



Harmony, plugin relay socket, mixed contact, 10 A, 250 V, screw clamp, for RXM2 or RXM4 relays

RXZE2M114

TAGS: CR0324, CR0332, CR0336, CR0441

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Harmony Electromechanical Relays Harmony Timer Relays
Product compatibility	Plug-in relay RXM 2 C/O Plug-in relay RXM 4 C/O Plug-in relay REXL 2 C/O Plug-in relay REXL 4 C/O Plug-in relay 782H 4 C/O
Device short name	RXZ
[Ith] conventional free air thermal current	10 A
Product or Component Type	Socket
Contacts type and composition	4 C/O

Complementary

[Ue] rated operational voltage	< 250 V IEC < 300 V UL
Connections - terminals	Screw clamp terminals, 1 x 0.34...1 x 1 mm ² AWG 22...AWG 17) flexible with cable end Screw clamp terminals, 2 x 0.34...2 x 1 mm ² AWG 22...AWG 17) flexible with cable end Screw clamp terminals, 1 x 0.5...1 x 1.5 mm ² AWG 20...AWG 16) solid without cable end Screw clamp terminals, 2 x 0.5...2 x 1.5 mm ² AWG 20...AWG 16) solid without cable end
Shape of pin	Flat
Tightening torque	< 1 N.m M3
Fixing mode	By screw (panel) Clip-on (35 mm symmetrical DIN rail)
Wire stripping length	0.3 in (8 mm)
Contact terminal arrangement	Mixed
[Uimp] rated impulse withstand voltage	4 kV
Overvoltage category	III
Pollution degree	3
Sale per indivisible quantity	10
Width	1.2 in (30 mm)
Net Weight	0.112 lb(US) (0.051 kg)

Environment

IP degree of protection	IP20 conforming to IEC 60529
-------------------------	------------------------------

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Dielectric strength	2500 V
Standards	IEC 61984
Product Certifications	UL CSA Lloyd's
Marking	CE
Ambient Air Temperature for Storage	-40...185 °F (-40...85 °C)
Ambient Air Temperature for Operation	-40...131 °F (-40...55 °C)

Ordering and shipping details

Category	US10CP221128
Discount Schedule	0CP2
GTIN	3389119404242
Returnability	Yes
Country of origin	CN

Packing Units


Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	1.024 in (2.600 cm)
Package 1 Width	1.220 in (3.100 cm)
Package 1 Length	2.756 in (7.000 cm)
Package weight(Lbs)	1.975 oz (56.000 g)
Unit Type of Package 2	BB1
Number of Units in Package 2	10
Package 2 Height	2.992 in (7.600 cm)
Package 2 Width	3.504 in (8.900 cm)
Package 2 Length	6.102 in (15.500 cm)
Package 2 Weight	21.164 oz (600.000 g)
Unit Type of Package 3	S03
Number of Units in Package 3	200
Package 3 Height	11.811 in (30.000 cm)
Package 3 Width	11.811 in (30.000 cm)
Package 3 Length	15.748 in (40.000 cm)
Package 3 Weight	27.445 lb(US) (12.449 kg)

Contractual warranty

Warranty (in months)	18
----------------------	----


Dimensions Drawings

Dimensions




Connections and Schema

Wiring Diagram



Technical Illustration

Dimensions



Data Sheet 11

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Mersen: Fuse, Fast Acting, 2A Model Number: ATMR2 Tags/Service: FU0315B / SPMP-01/02 RVSS Control Panels Specifications: • Fast acting, very current limiting • 200kA I.R. AC rating • For individual component and branch circuit protection • 600VAC voltage rating
4	Mfg: Mersen: Fuse, Fast Acting, 0.5A Model Number: ATMR1/2 Tags/Service: FU0304, FU0304A, FU0305, FU0305A / SPMP-01/02 RVSS Control Panels Specifications: • Fast acting, very current limiting • 200kA I.R. AC rating • For individual component and branch circuit protection • 600VAC voltage rating
2	Mfg: Mersen: Fuse, Time Delay, 0.8A Model Number: ATQR8/10

	Tags/Service: FU0315, FU0315A / SPMP-01/02 RVSS Control Panels Specifications: • Time delay, class CC fuse • 200kA I.R. AC rating • For control transformer inrush loads • Highly current limiting for low peak let-thru current • 600VAC voltage rating • High-grade silica filler for fast arc quenching and high current limitation
1	Mfg: Mersen: Fast Blow Fuse, 0.6A Model Number: GGM6/10 Tags/Service: FU0408 / SPMP-01/02 RVSS Control Panels Specifications: • Miniature 5x20mm fuse • Fast acting • Glass body • 10kA I.R. at 125VAC • 0.6A current rating
1	Mfg: Phoenix Contact: Fuse Terminal Block, 120VAC Model Number: 3046100 Tags/Service: FU0408 / SPMP-01/02 RVSS Control Panels Specifications: • Type III overvoltage category • 110VAC...250VAC LED voltage range

	• 4kV rated surge voltage • 1.02W maximum power dissipation for nominal condition • PA insulating material
1	Mfg: Mersen: Class CC Fuse Block, 4 Poles Model Number: 30324R Tags/Service: BLOCK / SPMP-01/02 RVSS Control Panels Specifications: • Pressure plate with double quick-connects • 600VAC voltage rating • 30A maximum current • 10kA SCCR when using quick connect terminal • Tin-plated copper alloy fuse clips • 20in-lb tightening torque

FUSE, FAST ACTING, 2A

FUSE, FAST ACTING, 0.5A

TAGS: FU0315B

TAGS: FU0304, FU0304A, FU0305, FU0305A

ATMR

Fast Acting/Class CC

UL/CSA LISTED POWER FUSES

SMALL FUSE - BIG PROTECTION
FOR GENERAL CIRCUITS




Amp-Trap® ATMR fuses, in the Class CC family, are the smallest dimension 600VAC/DC fuses suitable for branch circuit protection. The ATMR is a popular choice for economical protection of control circuits and control circuit transformers where available short circuit currents exceed 10,000 amperes. ATMR's rejection dimensions prevent substitution by lesser rated fuses. These fast acting fuses give current-limiting protection to general circuits.

CATALOG NUMBERS (AMPS)

ATMR1/10	ATMR1	ATMR4	ATMR10
ATMR1/8	ATMR1 1/4	ATMR5	ATMR12
ATMR2/10	ATMR1 1/2	ATMR6	ATMR15
ATMR1/4	ATMR2	ATMR7	ATMR20
ATMR3/10	ATMR2 1/2	ATMR8	ATMR25
ATMR1/2	ATMR3	ATMR9	ATMR30
ATMR3/4	ATMR3 1/2		

DIMENSIONS



RECOMMENDED FUSE BLOCKS FOR AMP-TRAP® CLASS CC FUSES

Number of Poles	UltraSafe™ Indicating Fuse Holders	Screw Connector with Double Quick Connects	Pressure Plate Connector with Double Quick Connects	Copper Box Connector
Adder	—	30310R	30320R	30350R
1	USCC1I	30311R	30321R	30351R
2	USCC2I	30312R	30322R	30352R
3	USCC3I	30313R	30323R	30353R
3	USFMCCI	—	—	—

A variety of pole configurations and termination provisions are available. Refer to Section FB for details.

RATINGS

- **Volts:** 600VAC / DC
- **Amps:** 1/10 to 30A
- **I.R.:** 200kA I.R. AC, 100kA I.R. DC

HIGHLIGHTS

- Fast acting
- Very current limiting

FEATURES/BENEFITS

- Rejection-style design prevents replacement errors when used with recommended fuse blocks
- Versatile design for individual component and branch circuit protection

APPLICATIONS

- Control circuits
- Lighting
- General loads
- Branch circuit protection

APPROVALS/STANDARDS

- UL Listed to Standard 248-4 File E2137
- CSA Certified to Standard C22.2 No. 248.4
- DC listed to UL Standard 248



FUSE, TIME DELAY, 0.8A

TAGS: FU0315, FU0315A

ATQR

Time Delay/Class CC

UL/CSA LISTED POWER FUSES

TAKE CONTROL OF FAULT CURRENTS HEADED
FOR YOUR CONTROL TRANSFORMER



ATQR small-dimension fuses feature time-delay characteristics ideally suited for the high inrush currents of control transformers, solenoids, and similar inductive loads. Mersen's ATQR fuses provide superior protection for the branch circuits of electrical distribution systems.

FEATURES/BENEFITS

- Time delay for control transformer inrush loads without nuisance opening
- Highly current limiting for low peak let-thru current
- Rejection-style design prevents replacement errors (when used with recommended fuse blocks)
- High visibility orange label ensures instant brand recognition, and simplifies replacement
- Metal-embossed date and catalog number for traceability and lasting identification
- Fiberglass body provides dimensional stability in harsh industrial settings
- High-grade silica filler ensures fast arc quenching and high current limitation

HIGHLIGHTS

- Time delay
- Best choice for small transformer protection
- Current limiting

RATINGS

Volts: 600VAC (1/10-30A),
300VDC (3-2/10 - 30A)

Amps: 1/10 to 30A

I.R.: 200kA I.R. AC,
100kA I.R. DC

APPLICATIONS

- Control transformers
- Solenoids
- Inductive loads
- Lighting, heating, and general-purpose loads

Note: See motor fuse applications tables for more information

APPROVALS/STANDARDS

- UL listed to standard 248-4 File E2137
- DC listed to UL standard 248
- CSA certified to standard C22.2 No. 248.4




CATALOG NUMBERS (AMPS)

ATQR1/10	ATQR8/10	ATQR2 8/10	ATQR7 1/2
ATQR1/8	ATQR1	ATQR3	ATQR8
ATQR3/16	ATQR1 1/8	ATQR3 2/10	ATQR9
ATQR2/10	ATQR1 1/4	ATQR3 1/2	ATQR10
ATQR1/4	ATQR1 4/10	ATQR4	ATQR12
ATQR3/10	ATQR1 1/2	ATQR4 1/2	ATQR15
ATQR4/10	ATQR1 6/10	ATQR5	ATQR17 1/2
ATQR1/2	ATQR1 8/10	ATQR5 6/10	ATQR20
ATQR6/10	ATQR2	ATQR6	ATQR25
ATQR3/4	ATQR2 1/4	ATQR6 1/4	ATQR30
	ATQR2 1/2	ATQR7	

RECOMMENDED FUSE BLOCKS
FOR CLASS CC FUSES

Number of Poles	Catalog Numbers			
	UltraSafe™ Indicating Fuse Holder	Screw Connector w/ Double Quick Connects	Pressure Plate Connector w/ Double Quick Connects	Copper Box Connector
Adder	—	30310R	30320R	30350R
1	USCC1I	30311R	30321R	30351R
2	USCC2I	30312R	30322R	30352R
3	USCC3I	30313R	30323R	30353R
3	USFMCCI	—	—	—

DIMENSIONS



© 2025 Mersen. All rights reserved. Mersen reserves the right to change, update, or correct, without notice, any information contained in this datasheet.

FAST BLOW FUSE, 0.6A

GGM/GGM-V
Electronic/Glass Fuses

TAGS: FU0408

MIDGET, PC MOUNT & MINIATURE FUSES

FEATURES/BENEFITS

- Glass body
- Fast-acting
- 5 x 20 mm
- ~~GGM-V: 1-1/2"~~
Axial Leads

APPROVALS/
STANDARDS

- 4/10A through 2A,
250VAC, UL Listed
and CSA Certified
- 8A, 125VAC,
UL Listed and
CSA Certified



STANDARD FUSE AMPERE RATINGS

Catalog Number	Axial Lead Catalog Number	Ampere Rating	Volts	I.R.
GGM4/10	GGM-V4/10	4/10A	250V	1
GGM6/10	GGM-V6/10	6/10A	250V	1
	GGM-V7/10	7/10A	250V	1
GGM8/10	GGM-V8/10	8/10A	250V	1
GGM1		1A	250V	1
GGM2		2A	250V	1
	GGM-V8	8A	125V	2

1. 250VAC @ 200A I.R./125VAC @ 10kA I.R.
2. 125VAC @ 10kA I.R.

© 2025 Mersen. All rights reserved. Mersen reserves the right to change, update, or correct, without notice, any information contained in this datasheet.

UT 4-HESILA 250 (5X20) - Fuse modular terminal block

FUSE TERMINAL BLOCK, 120VAC



3046100

<https://www.phoenixcontact.com/us/products/3046100>

TAGS: FU0408

Please be informed that the data shown in this PDF document is generated from our online catalog. Please find the complete data in the user documentation. Our general terms of use for downloads are valid.



Fuse modular terminal block, fuse type: Glass / ceramics / ..., fuse type: G / 5 x 20, nom. voltage: 250 V, nominal current: 6.3 A, connection method: Screw connection, Rated cross section: 4 mm², cross section: 0.14 mm² - 6 mm², mounting type: NS 35/7,5, NS 35/15, color: black

Your advantages

- Globally recognized: Internationally proven screw connection
- Maintenance-free and vibration-resistant thanks to the patented Reakdyn principle
- Easy integration and replacement of fuses with the lever element
- Easy checking of the fuses with optical signal unit
- Long-term stable connections with the use of high-quality materials
- Long-term stable connections with the use of high-quality materials
- Maximum efficiency in the smallest space - thanks to integrated level bridging, the connections are connected across levels

UT 4-HESILA 250 (5X20) - Fuse modular terminal block



3046100

<https://www.phoenixcontact.com/us/products/3046100>

Technical data

Notes

Order information:	Fuse-link not supplied as standard
General	The current is determined by the fuse used, the voltage by the selected LED. If the fuse is faulty, the downstream circuit will not be disconnected.

Product properties

Product family	UT
Area of application	Railway industry
	Machine building
	Plant engineering
Number of connections	2
Number of rows	1
Potentials	1

Insulation characteristics

Overvoltage category	III
Degree of pollution	3

Electrical properties

Fuse type	Glass / ceramics / ...
Rated surge voltage	4 kV
Maximum power dissipation for nominal condition	1.02 W
Fuse	G / 5 x 20
LED voltage range	110 V AC/DC ... 250 V AC/DC
LED current range	0.41 mA ... 0.96 mA
Maximum power dissipation	max. 1.6 W (with single arrangement of the fuse terminal block in the event of overload)
	max. 1.6 W (With interconnected arrangement of several fuse terminal blocks in the event of overload)
	max. 4 W (with single arrangement of the fuse terminal block in the event of a short-circuit)
	max. 2.5 W (With interconnected arrangement of several fuse terminal blocks in the event of a short-circuit)

Input data

LED voltage range	110 V AC/DC ... 250 V AC/DC
-------------------	-----------------------------

Connection data

Number of connections per level	2
Nominal cross section	4 mm ²
Connection method	Screw connection
Screw thread	M3

UT 4-HESILA 250 (5X20) - Fuse modular terminal block



3046100

<https://www.phoenixcontact.com/us/products/3046100>

Tightening torque	0.6 ... 0.8 Nm
Stripping length	9 mm
Internal cylindrical gage	A4
Connection in acc. with standard	IEC 60947-7-3
Conductor cross-section rigid	0.14 mm ² ... 6 mm ²
Cross section AWG	26 ... 10 (converted acc. to IEC)
Conductor cross-section flexible	0.14 mm ² ... 6 mm ²
Conductor cross-section, flexible [AWG]	26 ... 10 (converted acc. to IEC)
Conductor cross-section flexible ultrasound-compressed	0.34 mm ² ... 6 mm ²
Conductor cross-section, flexible [AWG] ultrasound-compressed	22 ... 10 (converted acc. to IEC)
Conductor cross-section flexible (ferrule without plastic sleeve)	0.25 mm ² ... 4 mm ²
Flexible conductor cross-section (ferrule with plastic sleeve)	0.14 mm ² ... 4 mm ²
2 conductors with same cross section, rigid	0.14 mm ² ... 1.5 mm ²
2 conductors with same cross section, flexible	0.14 mm ² ... 1.5 mm ²
2 conductors with same cross section, flexible, with ferrule without plastic sleeve	0.14 mm ² ... 1.5 mm ²
2 conductors with the same cross section, flexible, with TWIN ferrule with plastic sleeve	0.5 mm ² ... 1.5 mm ²
Nominal cross section	4 mm ²
Nominal current	6.3 A
Maximum load current	6.3 A (the current is determined by the fuse used)
Nominal voltage	250 V

Dimensions

Width	6.2 mm
Height	57.8 mm
Depth on NS 35/7,5	75.6 mm
Depth on NS 35/15	83.1 mm

Material specifications

Color	black (RAL 9005)
Flammability rating according to UL 94	V0
Insulating material group	I
Insulating material	PA
Static insulating material application in cold	-60 °C
Temperature index of insulation material (DIN EN 60216-1 (VDE 0304-21))	125 °C
Relative insulation material temperature index (Elec., UL 746 B)	130 °C
Fire protection for rail vehicles (DIN EN 45545-2) R22	HL 1 - HL 3
Fire protection for rail vehicles (DIN EN 45545-2) R23	HL 1 - HL 3
Fire protection for rail vehicles (DIN EN 45545-2) R24	HL 1 - HL 3
Fire protection for rail vehicles (DIN EN 45545-2) R26	HL 1 - HL 3
Calorimetric heat release NFPA 130 (ASTM E 1354)	27,5 MJ/kg
Surface flammability NFPA 130 (ASTM E 162)	passed
Specific optical density of smoke NFPA 130 (ASTM E 662)	passed

UT 4-HESILA 250 (5X20) - Fuse modular terminal block



3046100

<https://www.phoenixcontact.com/us/products/3046100>

Smoke gas toxicity NFPA 130 (SMP 800C)	passed
--	--------

Mechanical properties

Mechanical data

Open side panel	No
-----------------	----

Environmental and real-life conditions

Ambient conditions

Ambient temperature (operation)	-60 °C ... 110 °C (Operating temperature range incl. self-heating; for max. short-term operating temperature, see RTI Elec.)
Ambient temperature (storage/transport)	-25 °C ... 60 °C (for a short time, not exceeding 24 h, -60 °C to +70 °C)
Ambient temperature (assembly)	-5 °C ... 70 °C
Ambient temperature (actuation)	-5 °C ... 70 °C
Permissible humidity (operation)	20 % ... 90 %
Permissible humidity (storage/transport)	30 % ... 70 %

Standards and regulations

Connection in acc. with standard	IEC 60947-7-3
----------------------------------	---------------

Mounting

Mounting type	NS 35/7,5
	NS 35/15

Phoenix Contact 2026 © - all rights reserved

<https://www.phoenixcontact.com>

Phoenix Contact USA
586 Fulling Mill Road
Middletown, PA 17057, United States
(+717) 944-1300
info@phoenixcon.com

CLASS CC FUSE BLOCK, 4 POLES

TAGS: BLOCK

Midget & Class CC

600 Volt Fuse Blocks

FUSE BLOCKS & HOLDERS

600 VOLT MIDGET AND CLASS CC FUSE BLOCKS



FB

Mersen midget fuse blocks accommodate all 30 ampere 1-1/2" x 13/32" midget fuses. Class CC fuse blocks accommodate all 30 ampere Class CC fuses. A choice of box, screw, or pressure-plate connectors fit a wide range of stranded or solid copper wire. Insulators are glass-filled polycarbonate (GFPC) with verified dielectric strength in excess of 2500V. Fuse blocks feature a unique adder block which can be snapped onto 1-, 2- or 3-pole blocks to form multi-pole segmented blocks of as many poles as desired. All fuse clips are made of high conductivity tin-plated copper alloy.

RECOMMENDED FUSE USAGE:

- **Midget Fuse Block** use with ATQ, ATM, A6Y-2B, A25Z-2, TRM, OTM, A15QS-2, GFN, GGU, A60Q-2, DCT
- **Class CC Fuse Block** use with ATDR, ATMR, ATQR

CLIP & CONNECTOR TYPES

30A MIDGET/CC			
COPPER BOX CONNECTOR	SCREW WITH DOUBLE QUICK-CONNECTS	PRESSURE PLATE WITH DOUBLE QUICK-CONNECTS	PRESSURE PLATE WITH DOUBLE QUICK-CONNECTS (CLASS CC REJECTION END)
			

RATINGS:

Midget Block

- **Volts:** 600VAC / DC
- **Amps:** 30A Maximum
- **SCCR:** 100kA (depending on fuse I.R.); 10kA (when using quick connect terminal)

Class CC Block

- **Volts:** 600VAC / DC
- **Amps:** 30A Maximum
- **SCCR:** 200kA, 10kA (when using quick connect terminal)

Temperature/flammability GFPC insulators rated 125°C, 94V-0 flammability.

APPROVALS:

All fuse blocks meet the requirements of UL 4248

Midget Block

- UL recognized component guide IZLT2, File E52283
- CSA certified class 6225, File 32169

Class CC Block

- UL listed, guide IZLT, File E52283
- CSA certified class 6225, File 32169



600 VOLT, 30A MIDGET AND CLASS CC FUSE BLOCKS

Connector Type	Wire Range	Poles*	Catalog No.				Torque In - lb
			Midget	Listing	Class CC	Listing	
Screw w/ double quick connects at both ends	Cu #10-14	ADDER	30310	UL Rec. & CSA	30310R	UL & CSA	20
		1	30311		30311R		
		2	30312		30312R		
		3	30313		30313R		
		4	30314		30314R		
Pressure plate (sems) w/double quick connects at both ends	Cu #10-14	ADDER	30320	UL Rec. & CSA	30320R	UL & CSA	20
		1	30321		30321R		
		2	30322		30322R		
		3	30323		30323R		
		4	30324		30324R		
Copper box	Cu #6-14	ADDER	30350	UL Rec. & CSA	30350R	UL & CSA	35
		1	30351		30351R		
		2	30352		30352R		
		3	30353		30353R		
		4	30354		30354R		

Note: To convert Midget or Class CC adder pole to single pole, use end barrier #U09301.

* Available in any number of poles. Replace last digit in Catalog Number with number of poles needed.


Example: 303112 is a 12-pole screw/double QC connector Midget Fuse Block.

Total width of N poles = (N x .76) + .08 inches. 12 poles = (12 x .76") + .08" = 9.20".

Recommended mounting screws for all Midget and Class CC fuse blocks: #8 (.164" dia.)

DIMENSIONS

FB



Data Sheet 12

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Schneider Electric: Reduced Voltage Soft Starter Model Number: ATS490D17Y Tags/Service: RVSS / SPMP-01/02 RVSS Control Panels Specifications: • Soft starter for asynchronous motors • 480VAC power supply voltage • Normal duty, 17A rated operational current • Heavy duty, 12A rated operation current • IP20 degree of protection • 7.5kW/5.5kW in motor supply line for normal/heavy duty • 10/7.5 maximum horsepower rating for normal/heavy duty operation • 120VAC control circuit voltage

TAGS: RVSS



Soft starter, Altivar Soft Starter
ATS490, 17A, 208 to 690V AC,
control supply 110 to 230V AC

ATS490D17Y

Product availability: Stock - Normally stocked in distribution facility

Main

Range of Product	Altivar Soft Starter ATS490
Product or Component Type	Soft starter
Product destination	Asynchronous motors
Product Specific Application	Process and infrastructures
Device short name	ATS490
Phase	3 phase
Utilisation category	AC-3A AC-53A
Ue power supply voltage	208...690 V AC - 15...10 %
power supply frequency	50...60 Hz - 20...20 %
[Ie] rated operational current	Normal duty 17 A in line 104 °F (40 °C))
Service factor at Ie	100
rated current in heavy duty	12 A at 104 °F (40 °C) heavy duty
IP Degree of Protection	IP20
Motor power kW	4 kW 230 V in the motor supply line normal duty 7.5 kW 400 V in the motor supply line normal duty 7.5 kW 440 V in the motor supply line normal duty 9 kW 500 V in the motor supply line normal duty 9 kW 525 V in the motor supply line normal duty 11 kW 660 V in the motor supply line normal duty 15 kW 690 V in the motor supply line normal duty 3 kW 230 V in the motor supply line heavy duty 5.5 kW 400 V in the motor supply line heavy duty 5.5 kW 440 V in the motor supply line heavy duty 7.5 kW 500 V in the motor supply line heavy duty 7.5 kW 525 V in the motor supply line heavy duty 9 kW 660 V in the motor supply line heavy duty 11 kW 690 V in the motor supply line heavy duty 7.5 kW 230 V to the motor delta terminals normal duty 15 kW 400 V to the motor delta terminals normal duty 5.5 kW 230 V to the motor delta terminals heavy duty 11 kW 400 V to the motor delta terminals heavy duty
Maximum Horse Power Rating	3 hp 208 V normal duty 5 hp 230 V normal duty 10 hp 460 V normal duty 15 hp 575 V normal duty 2 hp 208 V heavy duty 3 hp 230 V heavy duty 7.5 hp 460 V heavy duty 40 hp 575 V heavy duty
With safety function Safe torque off (STO)	True
Safe Torque Off (STO)	STO (safe torque off): SIL 1 conforming to IEC 61508 STO (safe torque off): PL c/category 2 conforming to ISO 13849
Cybersecurity functions	True

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Cybersecurity level and standard	Security level (SL) 1 IEC 62443-4-2
Communication Port Protocol	Modbus serial Modbus TCP/EtherNet/IP
Option card	Communication module CANopen daisy chain Communication module CANopen Sub-D Communication module CANopen open style Communication module Profibus DP-V1 Communication module PROFINET

Complementary

Device connection	In the motor supply line Inside delta
Overload current profile	400 % I _e for 13 s
On-load factor	50 %
Operating cycles/hour	10 cyc/h
[U _s] control circuit voltage	110...230 V AC 50-60 Hz - 15...10 %
Apparent power	70 VA
Integrated motor overload protection	True
motor thermal protection class	Class 10E
Protection type	Phase failure mains Thermal protection starter Thermal protection motor Current overload motor Motor underload motor Excessive acceleration time motor Motor phase loss detection motor Protection against line phase inversion mains External thermal protection motor Protection delta inside wiring starter Short-circuit between motor phase and earth motor
current limiting %I _n (5 x I _e maximum)	150...700 %
[I _n] Rated current pwr loss specifctn	17 A
Power loss static current independent	19 W
Power loss per device current dependent	2 W
Power loss during starting	202 W during starting at 40 °C at 400% I _e
Standards	EN/IEC 60947-4-2 UL 60947-4-2 IEC 60664-1
Product Certifications	CE cULus UKCA RCM CCC DNV ATEX EAC KC
Marking	CE CULus UKCA RCM CCC ATEX EAC KC
[U _c] control circuit voltage	24 V DC

Discrete input number	5
Discrete input type	DI1) digital input, 4.4 kOhm DI2) digital input, 4.4 kOhm DI3) digital input, 4.4 kOhm DI4) digital input, 4.4 kOhm STO) digital input, > 1 kOhm
Input compatibility	DI1 discrete input level 1 PLC EN/IEC 61131-2 DI2 discrete input level 1 PLC EN/IEC 61131-2 DI3 discrete input level 1 PLC EN/IEC 61131-2 DI4 discrete input level 1 PLC EN/IEC 61131-2 STO discrete input level 1 PLC EN/IEC 61131-2
Discrete input logic	Digital input DI1 0...< 5 V <= 2 mA > 11 V, >= 5 mA Digital input DI2 0...< 5 V <= 2 mA > 11 V, >= 5 mA Digital input DI3 0...< 5 V <= 2 mA > 11 V, >= 5 mA Digital input DI4 0...< 5 V <= 2 mA > 11 V, >= 5 mA Digital input STO 0...< 5 V <= 2 mA > 11 V, >= 5 mA
Relay output number	3
Relay output type	Relay outputs R1A, R1C NO Relay outputs R2A, R2C NO Relay outputs R3A, R3C NO
Minimum switching current	100 mA 12 V DC relay outputs
Maximum switching current	Relay outputs 2 A / 250 V AC for AC-15 100000 cycles following IEC 60947-5-1 Relay outputs 2 A / 30 V DC for DC-13 150000 cycles following IEC 60947-5-1
Discrete output number	2
Discrete output type	Programmable digital output DQ1 <= 30 V 100 mA Programmable digital output DQ2 <= 30 V 100 mA
Output compatibility	Open collector level 1 PLC IEC 65A-68
Analogue input number	1
Analogue input type	AI1/PTC1 : PTC/PT 100/PT 1000/KTY84 temperature probe PTC2 : PTC/PT 100/PT 1000/KTY84 temperature probe PTC3 : PTC/PT 100/PT 1000/KTY84 temperature probe
Analogue output number	1
Analogue output type	Current output AQ1 : 0...20 mA/4...20 mA , impedance< 500 Ohm Voltage output AQ1 : 0...10 V , impedance> 470 Ohm
Communication port protocol	Modbus serial Modbus TCP/EtherNet/IP
Connector type	1 RJ45 for connecting Modbus serial 1 RJ45 for connecting Modbus TCP/EtherNet/IP
Physical interface	2-wire RS 485 100-BASE-TX category 5 or industrial Ethernet
Transmission frame	RTU TCP/UDP
Transmission Rate	4.8...38.4 kbps 100 BASE TX
Data format	8 bits, configurable odd, even or no parity 1or 2 stop
Number of addresses	0...247 Modbus serial
Method of access	Slave Modbus serial
Type of polarization	No impedance Modbus serial
Display screen available	True
Operating position	Vertical +/- 10 degree
Height	11.1 in (283 mm)
Width	6.3 in (160 mm)

Depth	7.3 in (185 mm)
Net Weight	8.8 lb(US) (4 kg)
internal bypass	True
Function Available	Pre-heating Smoke extraction Second motor set Deceleration with torque control Braking Boost Line contactor control Reverse contactor control Anti-jam Jog Borehole pump starting Condition monitoring Power monitoring Cybersecure firmware update
material declaration	True

Environment

Electromagnetic compatibility	Conducted and radiated emissions level A conforming to IEC 60947-4-2 Damped oscillating waves level 3 conforming to IEC 61000-4-18 Electrostatic discharge level 3 conforming to IEC 61000-4-2 Immunity to electrical transients level 4 conforming to IEC 61000-4-4 Immunity to radiated radio-electrical interference level 3 conforming to IEC 61000-4-3 Voltage/current impulse level 3 conforming to IEC 61000-4-5 Immunity to conducted interference caused by radio-electrical fields level 3 conforming to EN/IEC 61000-4-6
Pollution degree	Level 3
[Uimp] rated impulse withstand voltage	6 kV
[Ui] Rated Insulation Voltage	690 V
Environmental class (during operation)	Class 3C3 according to IEC 60721-3-3 Class 3S3 according to IEC 60721-3-3
Ambient air temperature for operation	-13...104 °F (-25...40 °C) (without derating) 104...140 °F (40...60 °C) (with current derating of 1 % per °C above 40 °C)
Ambient Air Temperature for Storage	-40...158 °F (-40...70 °C)
Ambient air transport temperature	-40...158 °F (-40...70 °C)
Operating altitude	<= 6561.68 ft (2000 m) without derating > 2000...4800 m with current derating 1 % per 100 m above 2000 m
Relative humidity	5...95 % without condensation or dripping water EN/IEC 60068-2-3
Maximum deflection under vibratory load (during operation)	1.5 mm at 2...13 Hz
Maximum deflection under vibratory load (during storage)	1.75 mm at 2...9 Hz
Maximum deflection under vibratory load (during transport)	1.75 mm at 2...9 Hz
Maximum acceleration under vibrational stress (during operation)	1 gn at 13...200 Hz
Maximum acceleration under vibratory load (during storage)	1 gn at 9...200 Hz 1.5 gn at 200...500 Hz
Maximum acceleration under vibratory load (during transport)	1 gn at 9...200 Hz 1.5 gn at 200...500 Hz
Maximum acceleration under shock impact (during operation)	15 gn at 11 ms
Maximum acceleration under shock load (during storage)	10 gn at 11 ms
Maximum acceleration under shock load (during transport)	10 gn at 11 ms

Ordering and shipping details

Category	US1CP1G22588
Discount Schedule	CP1G
GTIN	3606486948750
Returnability	Yes
Country of origin	ID

Packing Units


Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	9.055 in (23.000 cm)
Package 1 Width	9.055 in (23.000 cm)
Package 1 Length	14.173 in (36.000 cm)
Package weight(Lbs)	11.199 lb(US) (5.080 kg)
Unit Type of Package 2	S06
Number of Units in Package 2	8
Package 2 Height	29.528 in (75.000 cm)
Package 2 Width	23.622 in (60.000 cm)
Package 2 Length	31.496 in (80.000 cm)
Package 2 Weight	111.334 lb(US) (50.500 kg)

Contractual warranty

Warranty (in months)	18
----------------------	----

Dimensions Drawings


Dimensions



Mounting and Clearance

Mounting Position


The soft starter is designed to be mounted inside cabinets vertically at $\pm 10^\circ$ for cooling purposes. Respect the minimum clearances so that the cooling air can circulate from the bottom to the top of the soft starter. The minimum clearances apply to any device close to the soft starter such as circuit breakers, fuses and contactors. Do not install the soft starter above heating elements.



Connections and Schema

Wiring

Wiring the Power Part



Use class C cables for the power connections.

1/L1, 3/L2, 5/L3 : Mains supply inputs

2/T1, 4/T2, 6/T3 : Outputs to motor

(1) : Mains side

(2) : Motor side (bottom)


(3) : Ground connection

Connection In Line, No Line Contactor, Type 1 or 2 Coordination, 2-wire or 3-wire control

S5	Normally open contact push-button	RUN command for 3-wire control
S6	Selector switch, 2 positions, stay-out, normally open contact	RUN/STOP command for 2-wire control

Connection In Line, With Line Contactor, Type 1 or 2 Coordination, 2-wire control

Line contactor controlled based on RUN & STOP or on detected error.
Use relay output R1 set to [Mains Contactor]




- (1) : Installation of additional fast-acting fuses is mandatory to upgrade to type 2 coordination according to IEC 60947–4–2.
(2) : Take into account the electrical characteristics of the relays.
(3) : The transformer must supply 110...230 Vac +10% - 15%, 50/60Hz.
(4) : 2–wire control and 3–wire control.
(5) : Select the appropriate voltage surge suppressor.
(6) : STO Safe Torque Off.

Designation	Component	Description
Q1	Circuit breaker	Short circuit protection device for the motor
Q2	Circuit breaker	Short circuit protection device for the primary of the transformer
Q3	Fast acting fuses	Short circuit protection device of the soft starter to be used only when type 2 coordination according to IEC 60947-4-2 is required
Q4	Circuit breaker	Short circuit protection device for the secondary of the transformer
Q5	Circuit breaker	Short circuit protection device for the control part of the soft starter

KM1	Contactor	Line contactor
S1	Emergency Stop push-button	Emergency Stop to de-energized KM1 line contactor
S4	Normally close contact push-button	STOP command for 3-wire control
S5	Normally open contact push-button	RUN command for 3-wire control
S6	Selector switch, 2 positions, stay-put, normally open contact	RUN/STOP. command for 2-wire control

Connection Inside the Delta, Type 1 and 2 Coordination, 2-wire or 3-wire

Line contactor controlled based on RUN and STOP command or detected error
Use relay output R1 set to [Operating State Fault] (factory setting).




- (1) : Installation of additional fast-acting fuses is mandatory to upgrade to type 2 coordination according to IEC 60947-4-2.
- (2) : KM1 is mandatory to avoid uncontrolled voltage on the motor.
- (3) : The transformer must supply 110...230 Vac +10% — 15%, 50/60Hz.
- (4) : Take into account the electrical characteristics of the relays, especially when connecting to high rating contactor.
- (5) : 3-wire control, 2-wire control.
- (6) : STO Safe Torque Off.
- (7) : Select the appropriate voltage surge suppressor.

Designation	Component	Description
Q1	Circuit breaker	Short circuit protection device for the motor
Q2	Fast acting fuses	Short circuit protection device of the soft starter to be used only when type 2 coordination according to IEC 60947-4-2 is required
Q3	Circuit breaker	Short circuit protection device for the primary of the transformer


(7) : Select the appropriate voltage surge suppressor.

Designation	Component	Description
Q1	Circuit breaker	Short circuit protection device for the motor
Q2	Circuit breaker	Short circuit protection device for the primary of the transformer
Q3	Fast acting fuses	Short circuit protection device of the soft starter to be used only when type 2 coordination
Q4	Circuit breaker	Short circuit protection device for the secondary of the transformer
Q5	Circuit breaker	Short circuit protection device for the control part of the soft starter
KM1	Contactor	Line contactor
S1	Emergency Stop push-button	Emergency Stop to de-energized KM1 line contactor
S4	Normally close contact push-button	STOP command for 3-wire control and power Off
S5	Normally open contact push-button	RUN command for 3-wire control and power On
S6	Selector switch, 2 positions, stay-put, normally open contact	RUN/STOP command for 2-wire control

Control Block Wiring Diagram




R1A, R1C, R2A, R2C, R3A, R3C : Programmable NO relays
DI1, DI2, DI3, DI4 : Digital inputs
AQ1 : Analogue output
PTC1/AI1, PTC2, PTC3 : Motor thermal sensor connection
DQ1, DQ2, DQ+ : Digital outputs
ST0 : Safety function STO input
(1) : STO Safe Torque Off
(2) : 2 wire PTC/PT100/PT1000/KTY
(3) : Optional, in case of +24 External Supply usage
PT100, PT1000 Thermal Probe 3 Wires :



(4) : 3 wire PT100/PT1000


Technical Illustration

Dimensions



Technical Illustration

Wiring diagram



Data Sheet 13

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Socomec: Modbus Power Meter Model Number: 48250500 Tags/Service: PWS0306 / SPMP-01/02 RVSS Control Panels Specifications: • Modbus RTU communication protocols • RS485 communication ports • 110-277VAC power supply voltage • 10-key capacitive touch-screen • 50-300VAC max voltage (phase/neutral) • 14-158° F operating temperature • 3 digital inputs, 2 digital outputs • 3 current sensor inputs • IP65 degree of protection on front side
3	Mfg: Socomec: Split Core TR-10 Sensor, 25-63A Model Number: 48290555 Tags/Service: PWS0306 / SPMP-01/02 RVSS Control Panels Specifications: • TR-10 split-core current sensors for DIRIS B power monitoring devices • Attachable current transformer • 25-63A rated current - 0.5-75A actual coverage range

	• RJ12 connection type • 300VAC max voltage (phase/neutral) • CAT III measurement category • 14-158° F operating temperature
1	Mfg: Socomec: RJ12 Connection Cable, 3 Count Model Number: 48290584 Tags/Service: PWS0306 / SPMP-01/02 RVSS Control Panels Specifications: • Red, Black, Yellow cable colors • RJ12 connector • 2m cable length • Connection cable for TR current sensors • Grey color outer sheath • 26AWG size

DIRIS A-40

Multifunction power meter - panel mounted

Works with RJ12 smart current sensors

TAGS: PWS0306



DIRIS A-40



Function

The **DIRIS A-40** is a panel mounted power monitoring device compatible with TE/TR/ITR/TF smart current sensors, suitable for new or existing electrical installations.

The DIRIS A-40 has 3 native digital inputs and 2 digital outputs for additional versatility and includes RS485 Modbus RTU, Ethernet Modbus TCP and BACnet IP, and Profibus DP communication to report measurements to external management systems.

Advantages

Plug & Play

- Color-coded RJ12 cables for easy phase identification when wiring current sensors to the DIRIS A-40.
- Automatic detection of current sensor type and rating.
- Using low-voltage mV current sensors, no shunting blocks are needed, they can be disconnected safely under load.

Smart sensors

Three current sensor formats (solid-core TE, split-core TR/ITR and Rogowski coil TF) allow integration of the DIRIS A-40 into new and existing electrical installations.

Assisted configuration

A configuration wizard guides the user in a step by step process to configure the DIRIS A-40 directly from the screen. It also detects and corrects configuration errors which cuts the commissioning time in half and always delivers a reliable result.

Better than revenue grade

Compliant with the IEC 61557-12 standard, guaranteeing the quality and accuracy of the Power Meter:

- Class 0.2 for the meter alone.
- Class 0.5 from 2% to 120% of the rated current, for the global measurement chain (with TE/ITR/TF current sensors).

The solution for

- > Industry
- > Building
- > Infrastructure
- > Data center



Strong points

- > Plug & Play
- > Assisted configuration
- > Smart sensors
- > Better than revenue grade

Integrated technologies



PreciSense



AutoCorrect



VirtualMonitor

For more information see our website
www.socomec.us

Conformity to standards

- > UL 61010-1
CSA-C22.22
No.61010-1
Guide FTRZ/PICQ
File E257746



- > ANSI 12.20

- > PBI Meter per
CA Energy
Commission



- > IEC 61557-12



- > ISO 14025

DIRIS A-40

Multifunction power meter - panel mounted

Works with RJ12 smart current sensors

			
DIRIS A-40			
Current sensor technology	RJ12	RJ12	RJ12
General			
Format	Door Mount	Door Mount	Door Mount
Number of current sensor inputs	3	3	3
Available enclosed		•	
Electrical			
Power supply	110 - 277 VAC	110 - 277 VAC	110 - 277 VAC
Voltage measurement	50 - 300 VAC L-N 87 - 520 VAC L-L	50 - 300 VAC L-N 87 - 520 VAC L-L	50 - 300 VAC L-N 87 - 520 VAC L-L
Communication			
RS485 Modbus RTU	•	•	•
Ethernet (Modbus TCP/BACnet IP)		•	
Profibus DPV1			•
WEBVIEW web interface		•	
Digital Input / Output	3 / 2	3 / 2	3 / 2
Analog Input / Output	- / -	- / -	- / -
Energy metering			
±kWh, ±kvarh, kVAh	•	•	•
ΣP (kW), ΣQ (kvar), ΣS (kVA), PF	•	•	•
P (kW), Q (kvar), S (kVA), PF per phase	•	•	•
Predictive Power	•	•	•
Load curves / demand profiles	•	•	•
Peak Demand	•	•	•
Multi-tariff	8	8	8
Multi - measurement			
U12, U23, U31, V1, V2, V3, f	•	•	•
U system, V system	•	•	•
I1, I2, I3, In, I system	•	•	•
Unbalance U, V, I	•	•	•
Phi, cos Phi, tan Phi	•	•	•
Power quality			
THD U, V, I	•	•	•
Individual Harmonics U, V, I (up to 63rd)			•
Crest Factor I1, I2, I3	•	•	•
K-Factor	•	•	•
PQ Events (sags, swells, interruptions, overcurrents)	•	•	•
Alarms			
Measurement thresholds	•	•	•
System alarms	•	•	•
Protective device	•	•	•
Logical (digital input status)	•	•	•
History			
Average Values	•	•	
Reference	4825 0500	4825 0501	4825 0502

DIRIS A-40

Multifunction power meter - panel mounted

Works with RJ12 smart current sensors

WEBVIEW-S - embedded webserver

Real time

- Real-time visualization of electrical values.
- View data as graphs or tables.
- Power quality analysis of the utility supply and of loads.



soft_027_a_1_fr_cat_1.eps

Historical


- Consumption curves (kWh, kvarh, kVAh)
- Demand profiles (kW, kvar, kVA) with peak demand
- Graphic display with monthly, weekly, daily or hourly breakdown.



soft_036_a_1_fr_cat_1.eps


Alarms

- List of active alarms.
- Log of finished alarms




soft_025_a_1_fr_cat_1.eps

Terminals




diris_968_a_1_en_cat_1

Dimensions (in/mm)




diris_967_a_1_us_cat_1

Current measurement




diris_989_a_1_x_cat_1

3 inputs supplied by the product




diris_971_a_1_x_cat_1

3 inputs with external power supply




diris_972_a_1_x_cat_1

Voltage measurement and power supply



1. 0.5 A gG / 0.5 A class CC fuses.


2 outputs



Ground



RS485



diris-b_024_b_1_x_cat_1


Current sensors

Associated current sensors


Various types of current sensors can be connected to the DIRIS A-40: solid-core (TE), split-core (TR/ITR) or Rogowski (TF). This range of sensors is suitable for all types of new or existing installations. A quick RJ12 connection makes wiring easy and reliable and prevents wiring errors. The DIRIS A-40 automatically recognizes the sensor type and rating. This guarantees the accuracy of the overall measurement chain (DIRIS A-40 + current sensors).

For more information on TE, TR/ITR, TF current sensors, refer to pages 348-355.

TE solid-core current sensors




TE / TR/ITR / TF current sensors



Voltage and current sensor connection examples

Three phase + Neutral


3P+N - 3 CT (1 three-phase load + calculated Neutral)



dfrs_973_a.ai

Three-phase


3P - 3CT (1 three-phase load)



dfrs_974_a.ai

Three-phase


3P - 1CT (1 balanced three-phase load)



dfrs_975_a.ai

Single-phase

1P+N - 1CT (1 single-phase load)



dfrs_976_a.ai

1.0.5 A class CC fuses.

CT: Current sensor 3~ Load

DIRIS A-40

Multifunction power meter - panel mounted

Works with RJ12 smart current sensors

DIRIS A-40 characteristics

Mechanical characteristics

Type of screen	Capacitive touch-screen technology, 10 keys
Screen resolution	350 x 160 pixels
Ingress Protection	IP65, front face

Electrical characteristics

Power supply input	110-277 VAC L-N / 277-400 VAC L-L - CAT III 120-300 VDC - CAT III
Power consumption	5 VA AC / 1.5 VA DC (4825 0500) 8 VA AC / 2.5 VA DC (4825 0501 & 4825 0502)
Connection	Removable screw terminal block, 2 positions, AWG 14 ... AWG 20 / 0.5 ... 2.5 mm² solid cable or stranded cable with ferrule
Voltage measurement input	50-300 VAC (Ph/N) - 87-520 VAC (Ph/Ph) - CAT III
Electrical Network (Service) type	Single-Phase - Two-Wire, Line-to-Neutral Single-Phase - Two-Wire, Line-to-Line Single-Phase - Three-Wire (Split-Phase) Three-Phase - Three-Wire (Delta) ← Three-Phase - Four-Wire (Wye)
Frequency range	45 ... 65 Hz
Input consumption	≤ 0.1 VA
Connection	Removable screw terminal block, 4 positions, AWG 14 ... AWG 24 / 0.25 ... 2.5 mm² solid cable or stranded cable with ferrule

Measuring characteristics

Voltage measurement	
Sampling rate	9.6 kHz
Voltage measurement accuracy	Class 0.2
Frequency measurement accuracy	Class 0.02
Current measurement	
Number of current inputs	3
Associated current sensors	Solid-core TE, split-core TR/ITR, flexible TF current sensors
Connection type	Socomec RJ12 cables
Current measurement accuracy	Class 0.2 DIRIS A-40 alone Class 0.5 with TE, ITR, TF sensors Class 1 with TR sensors

Current measurement

Active Power/Energy accuracy	Class 0.2 DIRIS A-40 alone Class 0.5 with TE, ITR, TF sensors Class 1 with TR sensors
Reactive Power accuracy	Class 1 with TE, ITR, TF sensors Class 2 with TR sensors
Reactive Energy accuracy	Class 2 with TE, TR/ITR, TF sensors

Digital inputs

Number of digital inputs	3
Digital input type	Optocoupler with internal (12 VDC ± 10%) or external (12-24 VDC ± 20%) polarisation
Function	Logical status, pulse meter, multi-tariff
Connection	Removable screw terminal block, 5 positions, stranded or solid AWG 15 to AWG 24 / 0.2 to 1.5 mm² cable

Digital outputs

Number of digital outputs	2
Relay type	Optocoupler 30 VDC, 20 mA max. - SELV
Function	Manual command, pulse output, load shedding, alarm report
Connection	Removable screw terminal block, 4 positions, stranded or solid AWG 13 to AWG 24 / 0.2 to 2.5 mm² cable

Communication characteristics

RS485

Connection type	Half-Duplex, 2-3 wires
Protocol	Modbus RTU
Baudrate	9600 bds - 115200 bds

Ethernet

Connection type	RJ45 10/100 Mbs
Protocol	Modbus TCP/IP, BACnet IP, HTTP, FTP, SMTP

USB

Connection type	USB Type Micro-B
Protocol	Modbus RTU over USB
Function	Firmware upgrade and configuration

Environmental characteristics

Storage temperature	-13 to +185 °F / -25 to +85 °C
Operating temperature	+14 to +158 °F / -10 to +70 °C
Humidity	0% to 97% RH / +131 °F/+55 °C, non condensing
Operating altitude	≤ 6560 ft / 2000 m

Expert Services

Our service engineers are an essential part of our team, and they are dedicated to ensuring your power monitoring system provides accurate and reliable measurements to your EPMS software or SCADA system. Our services include:

- > Site audits to verify the proper wiring of your system
- > Personnel training on how to configure, operate and maintain power monitoring equipment and associated software
- > Remote and on-site commissioning to ensure that your system is up and running quickly, with peace of mind.

For further information, please contact your nearest SOCOMEC branch.



References

DIRIS A power meters		
DIRIS A-40	RS485 Modbus RTU	4825 0500
DIRIS A-40	RS485 Modbus RTU + Ethernet Modbus-TCP & BACnet-IP	4825 0501
DIRIS A-40	RS485 Modbus RTU + Profibus-DPV1	4825 0502

Accessories	Sold in multiples of	Reference
3-pole RM-Class CC fuse holder to protect voltage inputs	4	5705 0003
2-pole RM-Class CC fuse holder to protect power supply input	6	5701 0002
1A/5A secondary CT adapter with RJ12 output	1	4829 0599
6.5-ft USB Cable for configuration - Type A to Type Micro-B	1	4829 0050

RJ12 Solid-core current sensors ⁽¹⁾				
Model	Nominal current range (A)	Real range covered (A)	Window size (in/mm)	Reference
TE-18	5 ... 20	0.1 ... 24	Ø 0.33 / 8.6	4829 0500
TE-18	25 ... 63	0.5 ... 75	Ø 0.33 / 8.6	4829 0501
TE-25	40 ... 160	0.8 ... 192	0.53 x 0.53 / 13.5 x 13.5	4829 0502
TE-35	63 ... 250	1.26 ... 300	0.82 x 0.82 / 21 x 21	4829 0503
TE-45	160 ... 630	3.2 ... 756	1.22 x 1.22 / 31 x 31	4829 0504
TE-55	400 ... 1000	8 ... 1200	1.61 x 1.61 / 41 x 41	4829 0505
TE-90	600 ... 2000	12 ... 2400	2.52 x 2.52 / 64 x 64	4829 0506

(1) Refer to pages 348-351 for more information on TE current sensors

RJ12 Split-core current sensors ⁽²⁾				
Model	Nominal current range (A)	Real range covered (A)	Window size (in/mm)	Reference
TR-10 / ITR-10	25 ... 63	0.5 ... 75.6	Ø 0.39 / 10	4829 0555 / 4829 0655
TR-14 / ITR-14	40 ... 160	0.8 ... 192	Ø 0.55 / 14	4829 0556 / 4829 0656
TR-21 / ITR-21	63 ... 250	1.26 ... 300	Ø 0.83 / 21	4829 0557 / 4829 0657
TR-32 / ITR-32	160 ... 600	3.2 ... 720	Ø 1.26 / 32	4829 0558 / 4829 0658

(2) Refer to pages 352-353 for more information on TR/ITR current sensors

RJ12 Flexible Rogowski current sensors ^{(3) (4)}				
Model	Nominal current range (A)	Real range covered (A)	Window size (in/mm)	Reference
TF-40	100 ... 400	2 ... 480	Ø 1.57 / 40	4829 0573
TF-80	150 ... 600	3 ... 720	Ø 3.15 / 80	4829 0574
TF-120	400 ... 2000	8 ... 2400	Ø 4.72 / 120	4829 0575
TF-200	600 ... 4000	12 ... 4800	Ø 7.87 / 200	4829 0576
TF-300	1600 ... 6000	32 ... 7200	Ø 11.81 / 300	4829 0577
TF-600	1600 ... 6000	32 ... 7200	Ø 23.62 / 600	4829 0578
Set of 3 RJ12 female/female connectors for RJ12 lead extension between power meter and TF sensor				4829 0670

(3) TF Rogowski sensors come with a 6-ft cable lead with RJ12 male connector

(4) Refer to pages 354-355 for more information on TF current sensors

RJ12 sensor lead cables	Cable length (ft / m)										
	0.32/0.1	0.64/0.2	0.96/0.3	1.64/0.5	3.3/1	6.5/2	9.84/3	16.4/5	22.9/7	32.8/10	164/50 reel + 100 connectors
Number of cables	Reference	Reference	Reference	Reference	Reference	Reference	Reference	Reference	Reference	Reference	Reference
1	-	-	-	-	-	-	-	4829 0602	-	4829 0603	4829 0601
3	4829 0590	4829 0591	4829 0592	4829 0595	4829 0593	4829 0584	4829 0606	4829 0607	4829 0608	4829 0609	-
4	-	-	-	4829 0596	4829 0588	4829 0589	-	-	-	-	-
6	4829 0590	4829 0591	4829 0592	4829 0597	4829 0593	4829 0594	-	-	-	-	-

Commissioning		Reference
1/2 day remote commissioning	Remote commissioning including installation verification, programming and communication testing	9230100027
1/2 day on-site commissioning	On-site commissioning including installation verification, programming and communication testing	9230100004



SPLIT CORE TR-10 SENSOR, 25A-63A

TAGS: PWS0306

SPLIT CORE CT TR-10 25-63A

48290555

Split Core Current Sensor TR 63A class 0.5

[DOWNLOAD 3D MODEL](#)

[DOWNLOAD DOCUMENTS](#)

Strong Points

- + Smart sensors
- + Accurate

Function

The split-core current sensors in the TR ranges enable the current on an electrical installation to be measured. Used with a PMD from the DIRIS Digiware, DIRIS A-40, DIRIS B-10 or B-30 range, they make it possible to perform accurate measurements between 25 and 600 A, and provide access to an overall accuracy class. The RJ12 connection system makes it easier to connect it all up, and the integrated intelligence prevents any configuration errors.

UNSPSC	83101808
ETIM Class	EC002048
IGCC	6042
COMMERCE	
Description	Split-core AC current sensors TR-10 class 1 used with DIRIS Digi ware, DIRIS A-40, DIRIS B device, they make it possible to perform measurements with guaranteed accuracy
Effective date	2018-06-01
Offer Life Cycle Code	40
Country of origin	FR
ETIM - ELECTRICAL CHARACTERISTICS	
Rated primary current [A]	63
Rated secondary current [A]	0.1
Rated secondary apparent power [VA]	0.1
Accuracy class	0.5
Overcurrent limiting factor	FS 10
Calibrated	Yes
ETIM - MECHANICAL CHARACTERISTICS	
With contact protection	Yes
Height opening [mm]	10..10
Width opening [mm]	10..10
Opening diameter [mm]	10
Snap mounting	Yes

	Yes
Secondary connection	Plug-in connection
ETIM - TECHNICAL FEATURES	
Model	Attachable current transformer
Number of primary inputs	1
LOGISTICS	
GTIN/EAN	3596033018336
Customs number	8504312990
Price unit	PC
Weight of the packing unit [kg]	0.062
Length of the packing unit [m]	0.04
Width of the packing unit [m]	0.045
Depth of the packing unit [m]	0.025
NORMS	
Conformity to standards	• IEC • UL
TECHNICAL CHARACTERISTICS	
Model	TR
Opening	10
Rated current [A]	63
Secondary rated current	RJ12
Function	Current measurement

Type of product

Split core

Internal diameter

10x10

Secondary Output

Voltage

Accuracy class

1

Type of connection

RJ12

Conformity to standards

- IEC 61557-12
- UL 61010

Customisable

No



RJ12 CONNECTION CABLE, 3 COUNT

TAGS: PWS0306

CABLE RJ12 3x2M

48290584

RJ12 connection cable 2m x3

STANDARDS

Conformity to standards

- IEC
- UL

TECHNICAL CHARACTERISTICS

Height [mm]

2000

Color

Red, Black, Yellow

Connector

RJ12

Length

2 m

Type

Connection cable for TE, TR/iTR, TF current sensors

Length [m]	2
Colour outer sheath	Grey
Anti-kink sleeve	None
Cable construction	Other
AWG-size	26
Cable type	U/UTP

ETIM - TECHNICAL FEATURES

Category	5
Type of connector connection 1	RJ12 6(6)
Type of connector connection 2	RJ12 6(6)
Locking lever	No
Fire retardant version	No
Oil resistant according to EN IEC 60811-404	Yes
Pin assignment	1:1
NVP value [%]	70

LOGISTICS

GTIN/EAN	3596032776633
Customs number	8544429090
Price unit	PC
Weight of the packing unit [kg]	0.16
Length of the packing unit [m]	0.06
Width of the packing unit [m]	0.06

PRODUCT DETAILS

Effective date	2013-11-22
----------------	------------

Offer Life Cycle Code	40
-----------------------	----

Country of origin	TH
-------------------	----

CLASSIFICATION

UNSPSC	83101808
--------	----------

IGCC	6042
------	------

Data Sheet 14

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
2	Mfg: Square D: Timing Relay, 0-60 Sec, 120VAC, 8 Pin Octal, DPDT Model Number: 9050JCK13V20 Tags/Service: TR0316, TR0405 / SPMP-01/02 RVSS Control Panels Specifications: • 120VAC rated supply voltage • On-delay timer, 0.6-60 second range • 2VA power consumption • 10 current rating • DPDT, 2 NO + 2 NC contact composition • Silver nickel contact material • Socket mounting type
2	Mfg: Square D: Relay Socket, 120VAC, 8 Pin Octal, DIN Model Number: 8501NR51 Tags/Service: TR0316, TR0405 / SPMP-01/02 RVSS Control Panels Specifications: • 15A 300VAC rated current • DIN rail mounting type • Single tiered screw clamp terminal connection



TAGS: TR0316, TR0405

Timing Relay, Type JCK, plug In,
on delay, adjustable time, 0.6 to 60
seconds, 10A, 240 VAC, 120 VAC/
110 VDC

9050JCK13V20

Product availability: Stock - Normally stocked in distribution facility

Main

product range	9050JCK
product type	Timer
timing mode	On-delay
timing range	0.6...60 s
supply voltage	120 V AC 110 V DC

Complementary

power consumption	2 VA
current rating	10 A
switch function	DPDT
contact composition	2 NO + 2 NC
contact material	Silver nickel
maximum switching voltage	240 V AC
mounting type	Socket
number of pins	8
shape of pins	Tubular
for use with	8501NR52 8501NR51

Environment

certifications	CE UL Listed UL Recognized
ambient temperature range - operational	-18...150 °F (-28...66 °C)
Height	2.4 in (61 mm)
Width	1.7 in (43 mm)
Depth	4.09 in (104 mm)

Ordering and shipping details

Category	US10CP221651
Discount Schedule	0CP2
GTIN	785901032564

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Returnability	Yes
Country of origin	US

Packing Units


Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	1.900 in (4.826 cm)
Package 1 Width	2.50 in (6.35 cm)
Package 1 Length	4.300 in (10.922 cm)
Package weight(Lbs)	3.840 oz (108.862 g)
Unit Type of Package 2	CAR
Number of Units in Package 2	20
Package 2 Height	4.50 in (11.43 cm)
Package 2 Width	10.0 in (25.4 cm)
Package 2 Length	11.00 in (27.94 cm)
Package 2 Weight	5.501 lb(US) (2.495 kg)

Contractual warranty

Warranty (in months)	18
----------------------	----

Technical Illustration


Dimensions



All dimensions are approximate. Also see technical documentation.

Technical Illustration

Wiring diagram



- JCK11 – JCK19
- JCK31 – JCK39
- JCK51 – JCK59
- JCK60

Image of product / Alternate images

Alternative







Plug in relay, Type N, relay socket, 8 tubular pin, single tier, for 8501KP relays and 9050JCK timers

8501NR51

Product availability: Stock - Normally stocked in distribution facility

Main

[In] rated current	15 A 300 V AC 5 A 600 V AC
--------------------	-------------------------------

Complementary

mounting type	DIN rail Panel
electrical connection	Single tiered screw clamp terminals
package quantity	1
Width	1.6 in (40 mm)
Height	2.1 in (54 mm)
Depth	1.0 in (24.6 mm)

Ordering and shipping details

Category	US10CP221142
Discount Schedule	0CP2
GTIN	785901583592
Returnability	Yes
Country of origin	CN

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	1.000 in (2.540 cm)
Package 1 Width	1.700 in (4.318 cm)
Package 1 Length	2.200 in (5.588 cm)
Package weight(Lbs)	1.600 oz (45.359 g)
Unit Type of Package 2	CAR
Number of Units in Package 2	600
Package 2 Height	14.200 in (36.068 cm)
Package 2 Width	11.200 in (28.448 cm)
Package 2 Length	17.800 in (45.212 cm)
Package 2 Weight	64.0002 lb(US) (29.030 kg)

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.


Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Contractual warranty


Warranty (in months)	18
----------------------	----

Image of product / Alternate images

Alternative







Data Sheet 15

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
2	Mfg: Square D: Timing Relay, 0-60 Sec, 120VAC, 11 Pin Octal, DPDT Model Number: 9050JCK23V20 Tags/Service: TR0407, TR0409 / SPMP-01/02 RVSS Control Panels Specifications: • 120VAC rated supply voltage • Off-delay timer, 0.6-60 second range • 2VA power consumption • 10 current rating • DPDT, 2 NO + 2 NC contact composition • Silver nickel contact material • Socket mounting type
2	Mfg: Square D: Relay Socket, 120VAC, 11 Pin Octal, DIN Model Number: 8501NR61 Tags/Service: TR0407, TR0409 / SPMP-01/02 RVSS Control Panels Specifications: • 15A 300VAC rated current • DIN rail mounting type • Single tiered screw clamp terminal connection

Product data sheet

Specifications

TIMING RELAY, 0-60 SECOND,
120VAC, 11 PIN, DP

SQUARE D



TAGS: TR0407, TR0409

Timing Relay, Type JCK, plug In,
off delay, adjustable time, 0.6 to 60
seconds, 10A, 240 VAC, 120 VAC/
110 VDC

9050JCK23V20

Product availability: Stock - Normally stocked in distribution facility

Main

product range	9050JCK
product type	Timer
timing mode	Off-delay
timing range	0.6...60 s
supply voltage	120 V AC 110 V DC

Complementary

power consumption	2 VA
current rating	10 A
switch function	DPDT
contact composition	2 NO + 2 NC
contact material	Silver nickel
maximum switching voltage	240 V AC
mounting type	Socket
number of pins	11
shape of pins	Tubular
for use with	8501NR61 8501NR62

Environment

certifications	CE UL Recognized UL Listed
ambient temperature range - operational	-18...150 °F (-28...66 °C)
Height	2.4 in (61 mm)
Width	1.7 in (43 mm)
Depth	4.09 in (104 mm)

Ordering and shipping details

Category	US10CP221651
Discount Schedule	0CP2
GTIN	785901032632

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.

Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications

Returnability	Yes
Country of origin	US

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	2.600 in (6.604 cm)
Package 1 Width	2.00 in (5.08 cm)
Package 1 Length	4.400 in (11.176 cm)
Package weight(Lbs)	4.160 oz (117.934 g)
Unit Type of Package 2	CAR
Number of Units in Package 2	20
Package 2 Height	4.50 in (11.43 cm)
Package 2 Width	10.0 in (25.4 cm)
Package 2 Length	11.00 in (27.94 cm)
Package 2 Weight	5.501 lb(US) (2.495 kg)

Contractual warranty

Warranty (in months)	18
----------------------	----

TAGS: TR0407, TR0409

SQUARE D



Plug in relay, Type N, relay socket, 11 tubular pin, single tier, for 8510KP relays and 9050JCK timers

8501NR61

Product availability: Stock - Normally stocked in distribution facility

Main

[In] rated current	15 A 300 V AC 5 A 600 V AC
--------------------	--

Complementary

mounting type	Panel DIN rail
electrical connection	Single tiered screw clamp terminals
package quantity	1
Width	2.3 in (59 mm)
Height	2.2 in (54.8 mm)
Depth	1.0 in (24.6 mm)

Ordering and shipping details

Category	US10CP221142
Discount Schedule	0CP2
GTIN	785901583677
Returnability	Yes
Country of origin	CN

Packing Units

Unit Type of Package 1	PCE
Nbr. of units in pkg.	1
Package 1 Height	1.100 in (2.794 cm)
Package 1 Width	2.400 in (6.096 cm)
Package 1 Length	2.300 in (5.842 cm)
Package weight(Lbs)	2.240 oz (63.503 g)
Unit Type of Package 2	PAL
Number of Units in Package 2	2400
Package 2 Height	40.000 in (101.600 cm)
Package 2 Width	40.000 in (101.600 cm)
Package 2 Length	48.000 in (121.920 cm)
Package 2 Weight	336.0002 lb(US) (152.407 kg)

Price is "List Price" and may be subject to a trade discount – check with your local distributor or retailer for actual price.


Disclaimer: This documentation is not intended as a substitute for and is not to be used for determining suitability or reliability of these products for specific user applications


Contractual warranty

Warranty (in months)	18
----------------------	----

Image of product / Alternate images

Alternative





Data Sheet 16

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: Flygt: Pump Monitoring Relay Model Number: 14-407129 Tags/Service: MPR0408 / SPMP-01/02 RVSS Control Panels Specifications: • Current sensing operational principle • -20° to +65°C operating temperature • 120VAC 50-60Hz, -10% supply voltage • 120VAC / 10A relay contact rating • 12VDC +/- 10% voltage to sensor

PUMP MONITORING RELAY



TAGS: MPR0408

Issued: 4/12 Supersedes:

MiniCAS 120

Features

- Plug in Replacement for MiniCAS/FUS unit
- 120 VAC, ~~24 VAC~~, or 24 VDC Powered
- Durable Plastic Enclosure with Flange for Mounting
- Leakage & Temperature Alarm Indication
- Power Applied Indication
- Temperature Alarm Reset Mode Select Switch
- Temperature Alarm Reset Push-button
- Sensor Input Transient & Short Circuit Protected



UL FILE # E132545



MADE IN THE U.S.A.


Operation

The MiniCAS 120 provides Motor Over Temperature and Seal Leakage alarms for Flygt Submersible Pumps equipped with FLS or CLS sensors.


The unit applies 12 VDC to the sensor and measures the current flow through the sensor. The sensor controls the current in the circuit. If the sensor current is in the normal range the Temperature Alarm Relay is energized to allow normal pump operation. If the sensor circuit becomes shorted, the 12 VDC is turned off and all LEDs flash. Upon a High Motor Temperature condition, the sensor opens so that the sensor circuit current drops to zero. With the sensor current below the Trip Point ($\leq 3.0 \text{ mA} \pm 5\%$), the Overtemp Indication is turned on and the Temperature Alarm Relay is de-energized, preventing pump operation.

When the High Motor Temperature condition has cleared, the unit will reset based on the position of Alarm Reset Mode Select Switch (Auto or Manual). When in the Auto position, the Overtemp Alarm resets automatically. If the switch is in the Manual position, the Overtemp Reset Push-button must be pushed to clear the alarm.

Upon a Seal Leakage condition, the sensor increases the sensor circuit current above the Trip Point ($\geq 22 \text{ mA} \pm 5\%$), the Leakage Indication is turned on and the Leakage Alarm Relay is energized.



* INPUT VOLTAGE SUPPLIED TO EITHER PIN 2 OR PIN 6, BUT NOT BOTH.



Specifications

Input Power:	120 VAC $\pm 10\%$, 7.0 VA max 24 VAC $\pm 10\%$, 3.5 VA max 24 VDC $\pm 10\%$, 125 mA max
Output Rating:	10A Resistive @ 120VAC
Operating Temp:	-20°C to +65 °C
Storage Temp:	-45°C to +85 °C
Sensor Circuit Voltage:	12 VDC $\pm 10\%$
Temp Alarm Trip Point:	$\leq 3.0 \text{ mA} \pm 5\%$
Leak Alarm Trip Point:	$\geq 22 \text{ mA} \pm 5\%$
Enclosure:	Blue Lexan
Base:	Phenolic

ORDERING INFORMATION

Part Number – 14-407129

MiniCAS II/FUS-120 Technical Data

MiniCAS II/FUS-120 Technical Data:

Operation Principle: Current sensing

Environment: -20 to 65°C (-4 to 149°F)

Supply Voltage: 120 VAC 50-60 Hz $\pm 10\%$, ~~24 VAC $\pm 10\%$, 24 VDC $\pm 10\%$~~

Relay Contact Rating: 10 Amps @ 120 VAC

Voltage to Sensor: 12 VDC $\pm 10\%$

Values of Operation: 3.0 mA $< I < 22$ mA = OK conditions.
 $I \leq 3.0$ mA = High temp. $\pm 5\%$ (or interrupt).
 $I \geq 22.0$ mA = Leakage $\pm 5\%$ (or short circuit).
 (I = current measured by the MiniCAS II/FUS).

 Green LED On = Supply Voltage present.
 Green LED Off = No Supply Voltage present.

Leakage

Contact: Form "C" 10 A @ 120 VAC (N.C. contact for interlocking)

Reset: Automatic (N.O. contact for alarm)

LED Indicators: Red LED On = Leakage Indicated
 Red LED Off = No leakage indicated

Temperature

Contact: Form "C" 10 A @ 120 VAC (N.C. contact for interlocking, N.O. contact for alarm)

Reset: Manual - by interrupting the supply for 1 sec. or by setting the toggle switch in the "Manual" mode.
 Automatic - by setting the toggle switch in the "Auto Reset" mode.

LED Indicators: Red LED On = Over-temperature Indicated.
 Red LED Off = No Over-temperature indicated

Physical Size: Width: 2.125"
 Height: 4.250"
 Depth: 3.470" (+ socket depth)

Part Number: 14-40 71 29 (MiniCAS II/FUS -120)
 ~~14-40 70 97 (Socket, 11-pin) - optional~~

Approvals: UL - File E101681

Data Sheet 17

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
1	Mfg: SCE: Enclosure Heater Model Number: SCE-TSH50 Tags/Service: HTR0319 / SPMP-01/02 RVSS Control Panels Specifications: • DIN rail clip mounting • Designed for protection from low temperatures, condensation and corrosion • Touch safe heater • 120VAC rated operational voltage • 2 screw terminal connection style
1	Mfg: Finder: Enclosure Heater Thermostat, NC Model Number: 7T.81.0.000.2403 Tags/Service: Thermostat / SPMP-01/02 RVSS Control Panels Specifications: • 7T - 7T series thermostat • 8 - Temperature control thermostat • 1 - 1 contact • 0 - No operating voltage required • 000 - No operating voltage required • 2 - Temperature control • 4 - 1 NC contact

	• 03 - 0-60° C temperature control range • IP20 protection category • Silver nickel standard contact material
--	---



ENCLOSURE HEATER

TAGS: HTR0319

SCE-TSH50

Saginaw Control and Engineering
 95 Midland Road Saginaw, MI 48638-5770
 (800) 234-6871 - Fax: (989) 799-4524
 SCE@SaginawControl.com

Product Specifications:

**Part Number:** SCE-TSH50**Description:** Heater - 50W**Height:** 4.92"**Width:** 1.61"**Depth:** 1.61"**Price Code:** P1**List Price:** \$142.60**Catalog Page:** 402**Est. Ship Weight:** 0.35 lbs**Max. Current :** 3.5**Model Number:** 501050**Application**

PTC (Positive Temperature Coefficient)

Din rail clip design for 35mm Din Rail. Designed for protection from low temperatures, condensation and corrosion. Touch Safe with 2 screw terminal for standard AWG 14 wire. 110-240V AC.

For low temperatures management use with thermostat

For condensate management no thermostat is necessary - continuous heat is most effective see installaton Instruction for sizing.

Industry Standards - (IS24)

✱ UL Component Recognized

Notes

UL File #E358386

Optional Accessories

~~SCE-TEMD Thermostat (Dual)~~

~~SCE-TEMNC Thermostat (Normally Closed)~~

Similar Part Numbers

~~SCE-TSH100Heater - 100W~~

~~SCE-TSH150Heater - 150W~~

~~SCE-TSH25Heater - 25W~~

~~SCE-TSH75Heater - 75W~~

Installation Information

✱ Touch Safe Heaters

ENCLOSURE HEATER THERMOSTAT, NC

TAGS: THERMOSTAT

Panel Thermo-Hygrostat and Thermostats

7T
SERIES



Drying kilns



Industrial refrigeration



Road / tunnel lighting



Industrial furnaces and ovens



Automatic car-washes



Panels for electrical distribution



Control panels



Forced-air ventilators



Panel Thermo-Hygrostat

- Small, compact size (17.5 mm wide)
- Electronic control
- 4 functions
- Nominal voltage 110...240 V AC/DC
- Temperature ranges from +10 ° to +60°C
- Humidity range up to 90%
- LED status indication contact ON
- 35 mm rail (EN 60715) mount

Panel thermostat

- Small, compact size (17.5 mm wide)
- Snap action thermostatic Bimetal sensor
- Wide temperature setting range
- Long electrical life
- 35 mm rail (EN 60715) mount

7T.51/7T.81
Box clamp



* Measured with 0.3 K/min
** Measured with 0.5 %/min

For outline drawing see page 6

Contact specification

Contact configuration		1 NO (SPST-NO)	1 NC (SPST-NC)	1 NO (SPST-NO)
Rated current/Maximum peak current	A	10/15	10/20	10/20
Rated voltage/ Maximum switching voltage	V AC	250/400	250/250	250/250
Rated load AC1	VA	2500	2500	2500
Rated load AC15 (230 V AC)	VA	500	250	250
Single phase motor rating AC3 (230 V AC)	kW	—	1.1	1.1
Breaking capacity DC1: 24/110/220 V	A	10/0.3/0.12	1/0.3/0.15	1/0.3/0.15
Minimum switching load	mW (V/mA)	500 (12/10)	500 (12/10)	500 (12/10)
Standard contact material		AgNi	AgNi	AgNi

Coil specifications

Nominal Voltage	V AC/DC	110...240	—	—
Rated Power	VA (50Hz)/W	1.8/0.44	—	—
Operating range	V AC/DC	88...264	—	—

Temperature specifications *

Setting range (ventilation)	°C	+10...+60	-20...+40	-20...+60	0...+60	-20...+40	-20...+60	0...+60
Switch differential	K	4 ± 2	7 ± 4			7 ± 4		
Setting accuracy full range	K	-1...+3	—			—		

Humidity specifications **

Setting range (humidity)	%	50...90	—			—		
Hysteresis	%	4 ± 2	—			—		
Setting accuracy	%	5	—			—		

Technical data

Electrical life at rated load AC1	cycles	100 · 10 ³	100 · 10 ³			100 · 10 ³		
Ambient temperature range	°C	-25...+60	-45...+80			-45...+80		
Protection category		IP 20	IP 20			IP 20		

Approvals (according to type)

NEW 7T.51



- Thermo-Hygrostatic control
- Nominal voltage 110...240 V AC/DC

7T.81.0.000.240x



- Heating control


7T.81.0.000.230x



- Ventilation control

Ordering information


Example: 7T Series, Thermo-Hygrostat for temperature and humidity control, 110...240 V AC/DC, Multifunction, 35 mm rail (EN 60715) mount.



Technical data

Insulation		7T.51	7T.81
Dielectric strength between open contacts	V AC	1000	500
Dielectric strength between supply and contact	V AC	2000	—
Other data		7T.51	7T.81
Vibration resistance	g	—	16
Shock resistance	g	—	20
		7T.51/7T.81	
Screw torque	Nm	0.5	0.5
Max. wire size		solid cable	stranded cable
	mm ²	1 x 4 / 2 x 2.5	1 x 4 / 2 x 2.5
	AWG	1 x 12 / 2 x 14	1 x 12 / 2 x 14
Wire strip length	mm	9	9

Functions 7T.51




HT: $RH > RH_{set}$ or $T_{amb} > T_{set}$

Power is permanently applied to the thermo-hygrostat.

The contact 13-14 closes if the ambient humidity (RH) is $>$ of set humidity (RHset) or if the ambient temperature (Tamb) is $>$ of set temperature (Tset).


When contact is close, LED is ON



TH: $RH > RH_{set}$ or $T_{amb} < T_{set}$

The contact 13-14 closes if the ambient humidity (RH) is $>$ of set humidity (RHset) or if the ambient temperature (Tamb) is $<$ of set temperature (Tset).


When contact is close, LED is ON



HL: $RH < RH_{set}$

The contact 13-14 closes if the ambient humidity (RH) is $<$ of set humidity (RHset)

When contact is close, LED is ON







HM: $RH > RH_{set}$

The contact 13-14 closes if the ambient humidity (RH) is $>$ of set humidity (RHset)

When contact is close, LED is ON

Functions 7T.81




Heating control - Should the panel temperature fall below the (minimum) set temperature the contact will close to call for heat. The contact will open when this set temperature is exceeded.


Ventilation control - Should the panel temperature exceed the (maximum) set temperature then the contact will close to call for cooling. The contact will open when the temperature falls below this set temperature.

Wiring diagrams


Type 7T.51



Type 7T.81...230x




Type 7T.81...240x




G

Outline drawings

Type 7T.51
Box clamp



Type 7T.81
Box clamp



Data Sheet 18

Customer:	Johnston Construction
Reference:	Charles County Pomonkey Pump Station Improvements
Date:	02/24/2026
<u>Qty</u>	<u>Description</u>
A/R	Mfg: Phoenix Contact: Terminal Block Model Number: UT 2,5
A/R	Mfg: Phoenix Contact: Grounding Terminal Block Model Number: UT 2,5-PE
A/R	Mfg: Phoenix Contact: Terminal End Barrier Model Number: D-UT 2,5-10
A/R	Mfg: Phoenix Contact: Terminal Anchor Model Number: E/NS 35 N Tags / Service: TB-AC / SPMP-01/02 RVSS Control Panels Specifications: • Feed through and grounding terminals • Screw clamps • End plates and anchors • DIN rail mount

UT 2,5

Order No.: 3044076

<http://eshop.phoenixcontact.de/phoenix/treeViewClick.do?UID=3044076>

Universal terminal block, Type of connection: Screw connection,
Screw connection, Cross section: 0.14 mm² - 4 mm², AWG 26 - 12,
Width: 5.2 mm, Color: gray, Mounting type: NS 35/7,5, NS 35/15



Commercial data

EAN	4017918960377
Pack	50 pcs.
Customs tariff	85369010
Weight/Piece	0.008227 KG
Catalog page information	Page 26 (CL-2009)

Product notes

WEEE/RoHS-compliant since:
01/01/2003



<http://www.download.phoenixcontact.com>
Please note that the data given here has been taken from the online catalog. For comprehensive information and data, please refer to the user documentation. The General Terms and Conditions of Use apply to Internet downloads.

Technical data

General

Number of levels	1
Number of connections	2
Color	gray

Insulating material	PA
Inflammability class acc. to UL 94	V0

Dimensions

Width	5.2 mm
Length	47.7 mm
Height NS 35/7,5	47.5 mm
Height NS 35/15	55 mm

Technical data

Maximum load current	32 A (with 4 mm ² conductor cross section)
Rated surge voltage	8 kV
Pollution degree	3
Surge voltage category	III
Insulating material group	I
Connection in acc. with standard	IEC 60947-7-1
Nominal current I _N	24 A
Nominal voltage U _N	1000 V
Open side panel	ja

Connection data

Conductor cross section solid min.	0.14 mm ²
Conductor cross section solid max.	4 mm ²
Conductor cross section stranded min.	0.14 mm ²
Conductor cross section stranded max.	4 mm ²
Conductor cross section AWG/kcmil min.	26
Conductor cross section AWG/kcmil max	12
Conductor cross section stranded, with ferrule without plastic sleeve min.	0.14 mm ²
Conductor cross section stranded, with ferrule without plastic sleeve max.	2.5 mm ²
Conductor cross section stranded, with ferrule with plastic sleeve min.	0.14 mm ²
Conductor cross section stranded, with ferrule with plastic sleeve max.	2.5 mm ²
2 conductors with same cross section, solid min.	0.14 mm ²
2 conductors with same cross section, solid max.	1.5 mm ²
2 conductors with same cross section, stranded min.	0.14 mm ²

2 conductors with same cross section, stranded max.	1.5 mm ²
2 conductors with same cross section, stranded, TWIN ferrules with plastic sleeve, min.	0.5 mm ²
2 conductors with same cross section, stranded, TWIN ferrules with plastic sleeve, max.	1.5 mm ²
2 conductors with same cross section, stranded, ferrules without plastic sleeve, min.	0.14 mm ²
2 conductors with same cross section, stranded, ferrules without plastic sleeve, max.	1.5 mm ²
Type of connection	Screw connection
Stripping length	9 mm
Internal cylindrical gage	A3
Screw thread	M3
Tightening torque, min	0.6 Nm
Tightening torque max	0.8 Nm

Certificates / Approvals



Certification

CB, CSA, CUL, DNV, GL, GOST, LR, UL, VDE-PZI

Certification Ex:

IECEX, KEMA-EX

CSA

Nominal voltage U_N	600 V
Nominal current I_N	20 A
AWG/kcmil	26-12

CUL


Nominal voltage U_N	600 V
Nominal current I_N	20 A
AWG/kcmil	26-12

UL

Nominal voltage U_N	600 V
Nominal current I_N	20 A
AWG/kcmil	26-12

UT 2,5-PE

Order No.: 3044092

<http://eshop.phoenixcontact.de/phoenix/treeViewClick.do?UID=3044092>

Feed-through modular terminal block, Type of connection: Screw connection, Screw connection, Cross section: 0.14 mm² - 4 mm², AWG 26 - 12, Width: 5.2 mm, Color: green-yellow, Mounting type: NS 35/7,5, NS 35/15



Commercial data

EAN	4017918960360
Pack	50 pcs.
Customs tariff	85369010
Weight/Piece	0.012156 KG
Catalog page information	Page 32 (CL-2009)

Product notes

WEEE/RoHS-compliant since:
01/01/2003



<http://www.download.phoenixcontact.com>
Please note that the data given here has been taken from the online catalog. For comprehensive information and data, please refer to the user documentation. The General Terms and Conditions of Use apply to Internet downloads.

Technical data

General

Number of levels	1
Number of connections	2
Color	green-yellow

Insulating material	PA
Inflammability class acc. to UL 94	V0

Dimensions

Width	5.2 mm
Length	47.7 mm
Height NS 35/7,5	47.5 mm
Height NS 35/15	55 mm

Technical data

Rated surge voltage	8 kV
Pollution degree	3
Surge voltage category	III
Insulating material group	I
Connection in acc. with standard	IEC 60947-7-2
Open side panel	ja

Connection data

Conductor cross section solid min.	0.14 mm ²
Conductor cross section solid max.	4 mm ²
Conductor cross section stranded min.	0.14 mm ²
Conductor cross section stranded max.	4 mm ²
Conductor cross section AWG/kcmil min.	26
Conductor cross section AWG/kcmil max	12
Conductor cross section stranded, with ferrule without plastic sleeve min.	0.14 mm ²
Conductor cross section stranded, with ferrule without plastic sleeve max.	2.5 mm ²
Conductor cross section stranded, with ferrule with plastic sleeve min.	0.14 mm ²
Conductor cross section stranded, with ferrule with plastic sleeve max.	2.5 mm ²
2 conductors with same cross section, solid min.	0.14 mm ²
2 conductors with same cross section, solid max.	1.5 mm ²
2 conductors with same cross section, stranded min.	0.14 mm ²
2 conductors with same cross section, stranded max.	1.5 mm ²

2 conductors with same cross section, stranded, TWIN ferrules with plastic sleeve, min.	0.5 mm ²
2 conductors with same cross section, stranded, TWIN ferrules with plastic sleeve, max.	1.5 mm ²
2 conductors with same cross section, stranded, ferrules without plastic sleeve, min.	0.14 mm ²
2 conductors with same cross section, stranded, ferrules without plastic sleeve, max.	1.5 mm ²
Type of connection	Screw connection
Stripping length	9 mm
Internal cylindrical gage	A3
Screw thread	M3
Tightening torque, min	0.6 Nm
Tightening torque max	0.8 Nm

Certificates / Approvals



Certification

CB, CSA, CUL, DNV, GL, LR, UL, VDE-PZI

Certification Ex:

IECEX, KEMA-EX

CSA

AWG/kcmil	26-12
-----------	-------

CUL

AWG/kcmil	26-12
-----------	-------

UL

AWG/kcmil	26-12
-----------	-------

D-UT 2,5/10

Order No.: 3047028



<http://eshop.phoenixcontact.de/phoenix/treeViewClick.do?UID=3047028>

End cover, Length: 47.7 mm, Width: 2.2 mm, Height: 48.4 mm,
Color: gray

Commercial data

EAN	4017918960346
Pack	50 pcs.
Customs tariff	85389099
Weight/Piece	0.00248 KG
Catalog page information	Page 26 (CL-2009)

Product notes

WEEE/RoHS-compliant since:
01/01/2003



<http://www.download.phoenixcontact.com>
Please note that the data given here has been taken from the online catalog. For comprehensive information and data, please refer to the user documentation. The General Terms and Conditions of Use apply to Internet downloads.

E/NS 35 N - End bracket


0800886

<https://www.phoenixcontact.com/us/products/0800886>



Please be informed that the data shown in this PDF document is generated from our online catalog. Please find the complete data in the user documentation. Our general terms of use for downloads are valid.

End clamp, width: 9.5 mm, color: gray



Your advantages

- Large-surface marking

Commercial data


Item number	0800886
Packing unit	50 pc
Minimum order quantity	50 pc
Sales key	BE07
Product key	BE7111
GTIN	4017918129309
Weight per piece (including packing)	14.16 g
Weight per piece (excluding packing)	13.708 g
Customs tariff number	39269097
Country of origin	DE

Technical data

Connection data

Screw thread	M3
Tightening torque	0.5 ... 0.8 Nm

Dimensions

Dimensional drawing	
Width	9.5 mm
Height	48.6 mm
Depth	32.8 mm
Depth on NS 35/7,5	34.3 mm
Length	48.6 mm

Material specifications

Color	gray (RAL 7042)
Material	PA
Flammability rating according to UL 94	V0
Static insulating material application in cold	-60 °C
Temperature index of insulation material (DIN EN 60216-1 (VDE 0304-21))	125 °C
Relative insulation material temperature index (Elec., UL 746 B)	130 °C

Environmental and real-life conditions

Ambient conditions

Ambient temperature (operation)	-60 °C ... 105 °C (max. short-term operating temperature RTI Elec.)
Ambient temperature (storage/transport)	-25 °C ... 60 °C (for a short time, not exceeding 24 h, -60 °C to +70 °C)
Ambient temperature (assembly)	-5 °C ... 70 °C
Ambient temperature (actuation)	-5 °C ... 70 °C
Permissible humidity (storage/transport)	30 % ... 70 %

Mounting

Mounting type	NS 35/7,5
	NS 35/15

E/NS 35 N - End bracket

0800886

<https://www.phoenixcontact.com/us/products/0800886>



Phoenix Contact 2026 © - all rights reserved
<https://www.phoenixcontact.com>

Phoenix Contact USA
586 Fulling Mill Road
Middletown, PA 17057, United States
(+717) 944-1300
info@phoenixcon.com

**32384 CHARLES COUNTY POMONKEY PUMP STATION
IMPROVEMENTS**

Heating and Cooling Sizes:

Device		HEAT DISSIPATED (BTU/hr)
RVSS		65
Transformer		73
Total		138

Product selection result

Project

- Title: Charles County Pomonkey RVSS Panel
- Create date: Jan 15, 2026
- Amend date: Jan 15, 2026

User

- Company:
- Name:
- Address:
- City:

Enclosure		Wall		Location	
Type	Wall Mount Enclosure	Material	Stainless Steel	for Wash-down enviroments / NEMA 4/4X	
Height	36 inch			Single housing for wall mount	
Width	31 inch	k	3.7 W/m²K	Wind speed	No Wind
Depth	12 inch	Insulation	R0 = 0 inch		
		Enclosure Color	Gray	Surface according to VDE 0660 part 600	20ft²
Temperature		Rated connection value			
Min. ambient temperature	0 °F	Rated voltage: 115 V			
Max. ambient temperature	100 °F	Frequency	60 Hz		
Min. admissible temperature	14 °F				
Max. admissible temperature	131 °F				

Dissipation based on manual input 138 BTU/h

Switch cabinet acclimatisation

Total dissipation in enclosure	40 W
Dissipation due to solar radiation	0 BTU/h
Heat Dissipation from environment	0 BTU/h
Heat Dissipation to environment	397 BTU/h
Required cooling capacity	0 BTU/h
Required heating capacity	176 BTU/h

Product selection result

Warning

Ensure there is sufficient clearance for air flow around the cooling unit to prevent a so-called air short-circuit. There should be a minimum distance of approximately 200 mm (7.9 inches) to the next component in the housing and 400 mm (15.7 inches) outside the housing

32384 CHARLES COUNTY POMONKEY PUMP STATION IMPROVEMENTS

Drawings Index:

Drawing Number	Drawing Description
D32384-01	SPMP-01/02 RVSS PANEL EXTERIOR LAYOUT
D32384-02	SPMP-01/02 RVSS PANEL INTERNAL LAYOUT
D32384-03	SPMP-01/02 RVSS PANEL 480/120VAC WIRING DIAGRAM
D32384-04	SPMP-01/02 RVSS PANEL 120VAC WIRING DIAGRAM

**32384 CHARLES COUNTY POMONKEY PUMP STATION
IMPROVEMENTS**

Drawings:

WARNING NAMEPLATE DETAIL

S-L CONTROLS, DWG D32384-01
VOLTAGE: 480VAC, 60HZ, THREE PHASE
AMPS: 17

MAXIMUM PUMP HORSEPOWER: 10

SHORT CIRCUIT CURRENT: 5kA SYMMETRICAL, 480V MAXIMUM

ENCLOSURE RATING: UL TYPE 4X

CAUTION: MULTIPLE POWER SOURCES ARE PROVIDED FROM FIELD
TERMINALS. EACH SOURCE SHOULD BE DISCONNECTED FOR
SERVICING.

WARNING: TO MAINTAIN OVERCURRENT, SHORT CIRCUIT, AND
GROUND FAULT PROTECTION, THE MANUFACTURER'S INSTRUCTIONS
FOR SELECTING CURRENT ELEMENTS MUST BE FOLLOWED

NAMEPLATES SIZED AS REQUIRED

NAME PLATE LEGEND TABLE



ITEM	QTY	DESCRIPTION
1	2	SPMP-(01,02) / RVSS PANEL
2	2	HAND / OFF / AUTO
3	2	PUMP / RUNNING
4	2	PUMP / STOPPED
5	2	PUMP / FAULT
6	2	HIGH / TEMP
7	2	FAULT / RESET
8	2	SEAL / LEAK
9	2	ELAPSED TIME METER
10	2	FU0315, FU0315A: MERSEN ATQR8/10 0.8A FU0315B: MERSEN ATMR2 2A
11	2	FU0404: MERSEN MI5HF25V0.1/100 0.1A
12	2	FU0304,FU0304A,FU0305,FU0305A: MERSEN ATMR1/2 0.5A

NOTES:
ALL PLATES SHALL BE ENGRAVED ON WHITE BACKGROUND WITH
BLACK CHARACTERS. LETTER HEIGHT SHOULD BE MINIMUM 1/4"

WIRING:

- 1) □ - INDICATES CABINET TERMINAL BLOCK
2) DASHED LINES INDICATE WIRING REMOTE TO CONTROL PANEL.
3) PROVIDE 20% SPARE TERMINALS
4) UL APPROVED NO. TO BE PROVIDED AT TIME OF MANUFACTURING
5) ELECTRICAL CONNECTION TORQUES:
TERMINAL: 12 INCH POUNDS
CIRCUIT BREAKER: 45 INCH POUNDS


DRAWING IS TYP. FOR SPMP-01 AND SPMP-02 RVSS PANELS



PANEL WIRING


AREA	VOLTAGE	NOUN NAME	ID	GAGE	COLOR	TYPE
POWER	480VAC 3PH	A PHASE	(L1), (1L1), (H1)	12	BROWN	MTW
POWER	480VAC 3PH	B PHASE	(L2), (1L2), (H2)	12	ORANGE	MTW
POWER	480VAC 3PH	C PHASE	(L3), (1L3)	12	YELLOW	MTW
INTERNAL	120VAC	HOT	(1), (1A), (X1)	14	BLACK	MTW
INTERNAL	120VAC	NEUTRAL	(N)	14	WHITE	MTW
CONTROL	120VAC	HOT	VARIOUS	16	RED	MTW
CONTROL	120VAC	NEUTRAL	N	16	WHITE	MTW

TOLERANCES	REVISIONS			POMONKEY PUMP STATION IMPROVEMENTS SPMP-01/02 RVSS PANEL EXTERNAL LAYOUT		
	NO.	DATE	BY			
DECIMAL	1					
	2					
FRACTIONAL	3			DRAWN BY ZBB	SCALE NONE	MATERIAL
	4			CHK'D MN	DATE 01-22-2026	DRAWING NUMBER
ANGULAR	5			TRACED	APP'D	D32384-01
	6					



TAGS	QTY	CATALOG	DESCRIPTION	MANUFACTURER
ENC	1	SCE-48XEL1612SSLP	WALL MOUNT ENCLOSURE – NEMA 4X	SCE
ENC	1	SCE-48P16	ENCLOSURE BACKPANEL	SCE
ENC	1	SCE-ELMFK4SS6-OS	STAINLESS STEEL WALL MOUNT FOOT KIT	SCE
DISC	1	9422A2	FLANGE MOUNTED DISCONNECT HANDLE – NEMA 4X	SQUARE D
DISC	1	9422CSB30	CABLE OPERATED DISCONNECT MECHANISM	SQUARE D
ETM	1	722-0001	ELAPSED TIME METER	TRUMETER
ETM	1	5003-010	GASKET, RECTANGULAR, 2-HOLE	TRUMETER
LT0330	1	9001SKT38LGG31	PTT LIGHT, 120VAC LED, GREEN	SCHNEIDER ELECTRIC
LT0335	1	9001SKT38LRR31	PTT LIGHT, 120VAC LED, RED	SCHNEIDER ELECTRIC
LT0402, LT0410, LT0411	3	9001SKT38LYA31	PTT LIGHT, 120VAC LED, AMBER	SCHNEIDER ELECTRIC
PB0310	1	9001SKR1B	PUSHBUTTON, BLACK	SCHNEIDER ELECTRIC
PB0310	1	9001KA2	1 NO CONTACT	SCHNEIDER ELECTRIC
PB0310	2	9001KA3	1 NC CONTACT	SCHNEIDER ELECTRIC
SS0321	1	9001SKS43BH2	3 POSITION SWITCH, BLACK	SCHNEIDER ELECTRIC
T0315	1	9070TF150D1	CPT-480/120V, 150VA	SQUARE D
CB0301	1	BDL36030	MAIN CIRCUIT BREAKER, 30A	SQUARE D
CB0319	1	9926251002	CIRCUIT BREAKER, 120VAC, 2A	WEIDMULLER
CR0324, CR0332, CR0336, CR0401	4	RXM2AB2F7	MINIATURE RELAY, 120VAC, 8 BLADE	SCHNEIDER ELECTRIC
CR0324, CR0332, CR0336, CR0401	4	RXZE2M114	RELAY SOCKET, 120VAC, 8 BLADE, DIN	SCHNEIDER ELECTRIC
FU0315B	1	ATMR2	FUSE, FAST ACTING, 2A	MERSEN
FU0315, FU0315A	2	ATQR8/10	FUSE, TIME DELAY, 0.8A	MERSEN
FU0304, FU0304A, FU0305, FU0305A	4	ATMR1/2	FUSE, FAST ACTING, 0.5A	MERSEN
FU0408	1	GGM6/10	FAST BLOW FUSE, 0.6A	MERSEN
FU0408	1	3046100	FUSE TERMINAL BLOCK, 120VAC	PHOENIX CONTACT
BLOCK	1	30324R	CLASS CC FUSE BLOCK, 4 POLES	MERSEN
RVSS	1	ATS490D17Y	REDUCED VOLTAGE SOFT STARTER	SCHNEIDER ELECTRIC
PWS0306	1	48250500	MODBUD POWER METER	SOCOMEK
PWS0306	3	48290555	SPLIT CORE TR-10 SENSOR, 25-63A	SOCOMEK
PWS0306	1	48290584	RJ12 CONNECTION CABLE, 3 COUNT	SOCOMEK
TR0316, TR0405	2	9050JCK13V20	TIMING RELAY, 0-60 SEC, 120VAC, 8 PIN OCTAL, DPDT	SQUARE D
TR0316, TR0405	2	8501NR51	RELAY SOCKET, 120VAC, 8 PIN OCTAL, DIN	SQUARE D
TR0409, TR0411	2	9050JCK23V20	TIMING RELAY, 0-60 SEC, 120VAC, 11 PIN, DPDT	SQUARE D
TR0409, TR0411	2	8501NR61	RELAY SOCKET, 120VAC, 11 PIN OCTAL, DIN	SQUARE D
MPRO408	1	14-407129	PUMP MONITORING RELAY	FLYGT
HTR0319	1	SCE-TSH50	ENCLOSURE HEATER	SCE
THERMOSTAT	1	7T.81.0.000.2403	ENCLOSURE HEATER THERMOSTAT, NC	FINDER
TB-AC	20	3044076	UNIVERSAL TERMINAL BLOCK – UT 2,5	PHOENIX CONTACT
TB-AC	A/R	D-UT 2,5 / 10	TERMINAL END BARRIER	PHOENIX CONTACT
TB-AC	A/R	UT 2,5-PE	GROUNDING TERMINAL BLOCK	PHOENIX CONTACT
TB-AC	A/R	E/NS 35 N	TERMINAL ANCHOR	PHOENIX CONTACT

TOLERANCES	REVISIONS			POMONKEY PUMP STATION IMPROVEMENTS SPMP-01/02 RVSS PANEL INTERNAL LAYOUT		
	NO.	DATE	BY			
DECIMAL	1					
	2					
FRACTIONAL	3			DRAWN BY ZBB	SCALE NONE	MATERIAL
	4			CHK'D MN	DATE 01-22-2026	DRAWING NUMBER
ANGULAR	5			TRACED	APP'D	D32384-02
	6					



TOLERANCES		REVISIONS			POMONKEY PUMP STATION IMPROVEMENTS SPMP-01/02 RVSS PANEL 120VAC WIRING DIAGRAM		
		NO.	DATE	BY			
DECIMAL	1						
	2						
FRACTIONAL	3				DRAWN BY ZBB	SCALE NONE	MATERIAL
	4				CHK'D MN	DATE 01-22-2026	DRAWING NUMBER
ANGULAR	5				TRACED	APP'D	D32384-04
	6						